


[< Day Day Up >](#)



Twisted Network Programming Essentials

By Abe Fettig

.....
Publisher: **O'Reilly**

Pub Date: **October 2005**

ISBN: **0-596-10032-9**

Pages: **236**

[Table of Contents](#) | [Index](#)

Overview

Twisted Network Programming Essentials from O'Reilly is a task-oriented look at this new open source, Python-based technology. The book begins with recommendations for various plug-ins and add-ons to enhance the basic package as installed. It then details Twisted's collection simple network protocols, and helper utilities. The book also includes projects that let you try out the Twisted framework for yourself. For example, you'll find examples of using Twisted to build web services applications using the REST architecture, using XML-RPC, and using SOAP.

Written for developers who want to start building applications using Twisted, this comprehensive guide presents examples of the most common tasks you'll face when building network applications. It also helps you understand the key concepts and design patterns used in Twisted applications. Here are just some of the topics discussed in Twisted Network Programming Essentials:

- Installing Twisted
- How to make TCP connections
- How to use Twisted to work with the Web
- Twisted's authentication framework
- Usenet and SSH clients and servers

Along the way, each lesson is supported by thorough notes and explanations to make absolutely certain you're up to speed with this leading-edge Python technology.

[< Day Day Up >](#)



Twisted Network Programming Essentials

By Abe Fettig

.....
 Publisher: **O'Reilly**

Pub Date: **October 2005**

ISBN: **0-596-10032-9**

Pages: **236**

[Table of Contents](#) | [Index](#)

[Copyright](#)

[About the Author](#)

[Foreword](#)

[Preface](#)

[Why Use](#)

[Twisted?](#)

[What This](#)

[Book Covers](#)

[Conventions](#)

[Used in This](#)

[Book](#)

[What You'll](#)

[Need](#)

[Using Code](#)

[Examples](#)

[Safari&"left"](#)

[class="v2"](#)

[width="21">](#)

[Acknowledgments](#)

[Chapter 1.](#)

[Getting Started](#)

[Section 1.1.](#)

[Installing](#)

[Twisted](#)

[Section 1.2.](#)

[Installing from](#)

[Source Files](#)

[Section 1.3.](#)

[Adding](#)

[Twisted](#)

[Utilities to](#)

[Your Path](#)

[Section 1.4.](#)

[Using the](#)

[Twisted](#)

[Documentation](#)

[Section 1.5.](#)

[Finding](#)

[Answers to](#)

[Your Questions](#)

Chapter 2.
Building Simple
Clients and
Servers

Section 2.1.
Starting the
Twisted Event
Loop

Section 2.2.
Working with
Asynchronous
Results

Section 2.3.
Sending and
Receiving Data

Section 2.4.
Accepting
Connections
from Clients

Chapter 3. Web
Clients

Section 3.1.
Downloading a
Web Page

Section 3.2.
Accessing a
Password-Protected
Page

Section 3.3.
Uploading a
File

Section 3.4.
Checking
Whether a Page
Has Changed

Section 3.5.
Monitoring
Download
Progress

Chapter 4. Web
Servers

Section 4.1.
Responding to
HTTP Requests

Section 4.2.
Parsing HTTP
Requests

Section 4.3.
Working with
POST Data
from HTML
Forms

Section 4.4.
Managing a

Hierarchy of
Resources
Section 4.5.
Storing Web
Data in an SQL
Database
Section 4.6.
Running an
HTTP Proxy
Server
Chapter 5. Web
Services and RPC
Section 5.1.
Using the
REST
Architecture for
Web Services
Section 5.2.
Using a Web
Client to
Update
Resources
Through REST
Section 5.3.
Enabling Web
Services Using
XML-RPC
Section 5.4.
Calling
XML-RPC
Functions
Section 5.5.
Installing
SOAP Libraries
Section 5.6.
Sharing Web
Services with
SOAP
Section 5.7.
Calling SOAP
Web Services
Section 5.8.
Sharing Python
Objects with
Perspective
Broker
Chapter 6.
Authentication
Section 6.1.
Using
Authentication
in a Twisted
Server
Section 6.2.

Authenticating
Against a
Database Table
Section 6.3.
Representing
Users with
Different
Capabilities
Section 6.4.
Using
Authentication
with
Perspective
Broker

Chapter 7. Mail Clients

Section 7.1.
Downloading
Mail from a
POP3 Server
Section 7.2.
Sending Mail
Using SMTP
Section 7.3.
Looking Up the
SMTP Server
for a Domain
Section 7.4.
Listing
Mailboxes on
an IMAP
Server
Section 7.5.
Downloading
Messages from
an IMAP
Mailbox

Chapter 8. Mail Servers

Section 8.1.
Accepting Mail
with SMTP
Section 8.2.
Using SMTP as
a User Interface
Section 8.3.
Providing
POP3 Access
to Mailboxes
Section 8.4.
Providing
IMAP Access
to Mailboxes
Chapter 9.

NNTP Clients and Servers

Section 9.1.

Listing the
Newsgroups on
a Server

Section 9.2.

Downloading
Usenet Articles

Section 9.3.

Posting a
Message to an
NNTP Server

Section 9.4.

Running a
Basic NNTP
Server

Section 9.5.

Using NNTP as
a User Interface

Chapter 10.

SSH

Section 10.1.

Setting Up a
Custom SSH
Server

Section 10.2.

Using Public
Keys for
Authentication

Section 10.3.

Providing an
Administrative
Python Shell

Section 10.4.

Running
Commands on
a Remote
Server

Chapter 11.

Services, Processes, and Logging

Section 11.1.

Running a
Twisted
Application as
a Daemon

Section 11.2.

Setting Limits
on an

Application's
Permissions

Section 11.3.

Managing
Multiple
Services
Section 11.4.
Logging Events
and Errors
Colophon
Index

< Day Day Up >

Twisted Network Programming Essentials

by Abe Fettig

Copyright & "docText">Printed in the United States of America.

Published by O'Reilly Media, Inc., 1005 Gravenstein Highway North, Sebastopol, CA 95472.

O'Reilly books may be purchased for educational, business, or sales promotional use. Online editions are also available for most titles (safari.oreilly.com). For more information, contact our corporate/institutional sales department: (800) 998-9938 or corporate@oreilly.com.

Editor:	Jonathan Gennick
Production Editor:	Marlowe Shaeffer
Cover Designer:	Karen Montgomery
Interior Designer:	David Futato

Printing History:

October 2005:	First Edition.
---------------	----------------

Nutshell Handbook, the Nutshell Handbook logo, and the O'Reilly logo are registered trademarks of O'Reilly Media, Inc. Twisted Network Programming Essentials, the image of a ball of snakes, and related trade dress are trademarks of O'Reilly Media, Inc.

Many of the designations used by manufacturers and sellers to distinguish their products are claimed as trademarks. Where those designations appear in this book, and O'Reilly Media, Inc. was aware of a trademark claim, the designations have been printed in caps or initial caps.

While every precaution has been taken in the preparation of this book, the publisher and author assume no responsibility for errors or omissions, or for damages resulting from the use of the information contained herein.

ISBN: 0-596-10032-9

[M]

About the Author

Abe Fettig is a software developer specializing in Internet applications. He currently works as a software engineer for JotSpot, Inc. His open source projects include Yarn, a Python library that uses Twisted to transfer information between RSS, email, weblogs, and web services. Abe lives in Portland, Maine with his wife, Hannah.

Foreword

"My name is Ozymandius, king of kings:
 Look on my words, ye Mighty, and despair!"
 Nothing beside remains. Round the decay
 Of that colossal wreck, boundless and bare
 The lone and level sands stretch far away.

—Percy Bysshe Shelly "Ozymandius"

As the Twisted project's originator and nominal leader—and as someone who is not being paid for writing this—I can very honestly say that this is a fine book, and it has made me proud of what I've started. You now hold in your hands a wondrous key that contains the knowledge to unlock a very powerful software system—a software system borne of a consistent, methodical vision; a vision half a decade in realization and hundreds of man-years in implementation; a vision for a video game that has yet to be written, called "Divunal."

I have been lauded many times for my role in Twisted's creation, and in this foreword I will attempt to disabuse you of the notion that any of it was on purpose. Not only was it an accident, but neither I, nor anyone else, has made one iota of progress towards my original goal of writing a game.

When I was eight years old, I decided I wanted to be a writer. I was going to write video games just like my favorite ones, the text-based games from Infocom. They were like books, but better. I knew how to write already—at a fourth-grade level, or so I'm told—and all I needed to figure out was the part where the computer wrote back. Lucky for you nobody thought to tell me how hard that step between the input and the output was, or Twisted would be a series of detective novels instead of a Python program.

Tolkien said it best: "The tale grew in the telling," and I'll say it worse: the code grew in the hacking. Twisted began over a decade after my aforementioned first plunge into the netherworld of software, as a solitary attempt to create a networking subsystem for a small online fantasy world. Since then, it has become an ongoing community quest to unify all manner of asynchronous communications. This book will take you on an adventure through Twisted for the Web, Twisted for email, Twisted for chat, and of course, Twisted for whatever new kind of networked application you want to dream up—maybe even an online video game.

Much as the tale of Twisted has grown and changed, its origins still have a profound effect on its nature, and on its future. Having origins in an eclectic^[*] problem domain has attracted an eclectic^[†] audience. As Mr. Fettig will warn you later in these pages, the community in the online support forum engages in discussions which are "often funny." I thank him for his tact, but to put it more directly: we're weird.

[*] And difficult! Making an online game work properly is hard.

[†] And intelligent! People who solve unusual problems are always learning.

"Weird" is a badge I have long worn with pride, dear reader, so please take it as a compliment that I bestow it upon you. You're not simply non-average, you're better than average. Almost by definition, Twisted hackers are the ones for whom "good enough" isn't good enough. You are the web programmers who can't use their operating system's stock HTTP daemon because you need more power and more control over how it's run; the chat developers who aren't content with chatting on a perfectly working network just because it doesn't support some cool new features you want; the (dare I say it?) gamers who aren't content with the market's offerings of online games. You want to create something newer, different, better. To build higher than those who have come before, because you are building not merely upon the shoulders of giants, but upon the apex of an acrobatic balancing act of giants, or more literally an interlocking network of frameworks and libraries

for different tasks, rather than just one at a time.

Twisted will let you do that, by letting you leverage code written by far more and far better programmers than I. Twisted provides a common method for that code to cooperate, which means you can use all of that code without performing a complex integration pass. In this spirit, I'd like to invite you to release your Twisted-based projects, or the infrastructure components of them, as open source software, so that we might together build a Twisted commons upon which many more fantastic applications will be built.

Don't mistake this friendly vision for altruism, however. I didn't have anything to do with the start of the Free Software or Open Source movements, respectively, but they came along at a convenient time for me. This feeling of share-and-share-alike has been a feature of the Twisted community since day one, not because I care about sharing.^[4] It is because—I may have mentioned this—I want to write a video game one day. A game that effortlessly connects to the Web and to your email, that politely requests that you play when you have time, and that reminds you to get back to work when you do not.

^[4] Caution for the humorless: this is a joke. I am not actually an enemy of freedom. Still, there is some truth to this.

You see, the majority of Twisted's core developers, including myself, suffer from Attention Deficit Disorder. This malady is the grease that makes the magic wheels of integration turn. While most developers—sane developers—would be content to write a perfectly good web server that could work only as a web server and leave it at that, we are always afraid we'll suddenly lose interest and need a chat application instead—or maybe it should be a mail server? Hey, there's a squirrel! I don't like this song.

What was I saying? Oh yes. The essence of Twisted is apparently paradoxical. Created on a whim by crazed eccentrics, designed to be a toy, and yet powerful enough to drive massive email systems, high-traffic web sites, transaction-processing systems, and inventory management applications.

However, the paradox is an illusion. People produce the best work when they are working and having fun at the same time. It takes a sense of humor to call yourself a crazed eccentric (whether it's true or not). You have to have a sense of fun to try and build a toy. In enjoying ourselves, we have brought to life a system that many of us have tried, and been unable, to create in more serious surroundings.

So, when I look out upon the "lone and level sands" of Divunal, a game whose incarnation today is little more than its name, I am not concerned. I am having a good time with Twisted. With this book in hand, I have no doubt that you will, too.

CTO at Divmod, Inc.
(not a game company)
(yet)
August 2005

—Matthew "the Glyph" Lefkowitz

< Day Day Up >

Preface

This is a book about Twisted. Twisted is an open source Python framework for building network applications.^[*] It gives developers a complete set of tools for communicating across networks and the Internet. Twisted includes both high- and low-level tools. You can create a web or mail server with just a few lines of code, or you can write your own protocol from scratch. At every level, Twisted provides a tested, well-designed API that makes it possible to rapidly develop powerful network software.

^[*] See <http://open-source.org> for more information on open source software (OSS).

This book is for developers who want to start building applications using Twisted. It contains lots of examples of working code, with thorough notes and explanations. It focuses on practical examples of how you can use Twisted to do useful things.

Why Use Twisted?

If you're not already using Twisted, you may have some reservations about adopting it for your own applications. Why should you use Twisted instead of some other networking library or framework? Here are a few compelling reasons:

Python-powered

Twisted is written in Python, a powerful, object-oriented, interpreted language. Python is a language that inspires great enthusiasm among its fans, and for good reason. It's a joy to program in Python, which is easy to write, easy to read, and easy to run. And because Python is cross-platform, you can run the same Twisted application on Linux, Windows, Unix, and Mac OS X.

Asynchronous and event-based

Synchronous network libraries leave developers with a painful choice: either allow the application to become unresponsive during network operations, or introduce the additional complexity of threading. Twisted's event-based, asynchronous framework makes it possible to write applications that stay responsive while processing events from multiple network connections, without using threads.

Full-featured

Twisted includes an amazing amount of functionality. Mail, web, news, chat, DNS, SSH, Telnet, RPC, database access, and more—it's all there, ready for you to use.

Flexible

Twisted provides high-level classes to let you get started quickly. But you'll never find yourself limited by the way things work out of the box. If you need advanced functionality, or you need to customize the way a protocol works, you can. You can also write your own protocol implementation, for complete control of every byte sent over the wire.

Open source

Twisted is free, both as in beer and as in freedom. It includes full source code, and is released under a liberal license. Want to distribute all or part of Twisted along with your application? You're welcome to do so, with no obligations to release your own code or pay any licensing fees. Want to get a better understanding of how an object in Twisted works? Take a look at the source. And when you get to the point where you're developing your own improvements and extensions to Twisted, you can contribute them to the community for the benefit of others.

Community-backed

Twisted has an active community of developers and users. If you run into a problem, you'll find many fellow developers ready to help on one of the Twisted mailing lists. See "[Finding Answers to Your Questions](#)," in [Chapter 1](#). Or you can drop into the #twisted IRC channel, where the chances are good you'll be able to start a live conversation with the very person who wrote the code you're having trouble with.

An integration-friendly platform

A Twisted application can share data between several different services within the same process. This makes integration tasks a snap. You can write an SMTP-to-XMLRPC proxy, an SSH server that lets you update a website, or a web discussion board that includes an NNTP interface. If you need to transfer data between systems that don't speak the same protocol, Twisted will make your job a whole lot easier.

[< Day Day Up >](#)

What This Book Covers

This book does not attempt to exhaustively document every module and class available for the Twisted framework. Instead, it focuses on presenting practical examples of the most common tasks that face developers building network applications. This book will also help you to understand the key concepts and design patterns used in Twisted applications. Here's a summary of the main topics covered:

Installing Twisted

[Chapter 1](#) covers downloading and installing Twisted, and some additional libraries, on the operating system of your choice.

Working with TCP connections

[Chapter 2](#) shows how you can use Twisted to make TCP connections to servers, and how to write a server that accepts TCP connections from clients.

Web clients and servers

[Chapters 3](#) and [4](#) show how to use Twisted to work with the Web. [Chapter 3](#) covers HTTP clients. [Chapter 4](#) demonstrates how to write a web server of your own, from the basics of responding to HTTP requests to higher-level concepts like managing a hierarchy of resources and storing data in an SQL database.

Web services and RPC

Twisted includes support for several different kinds of web services and remote procedure calls. [Chapter 5](#) shows how you can design a Twisted web application for programmatic accessing using the REST architectural style. It also demonstrates how to write XML-RPC and SOAP clients and servers, and how you can use the Twisted Perspective Broker framework to transfer native Python objects over a network connection.

Authentication

Managing users and authentication is one of the core tasks in any server application. [Chapter 6](#) discusses the Twisted authentication framework, which provides an extremely flexible approach to authenticating users against different backends.

Email clients and servers

[Chapters 7](#) and [8](#) demonstrate Twisted's powerful support for mail clients and servers. [Chapter 7](#) shows how to write clients that send and receive mail using SMTP, POP3, and IMAP. [Chapter 8](#) shows how to build SMTP, POP3, and IMAP servers.

Usenet

[Chapter 9](#) discusses Usenet clients and servers using the NNTP protocol. It shows how to read and post Usenet articles, how to run an NNTP server, and how to use NNTP as an interface for other kinds of messages, such as RSS feeds.

SSH clients and servers

[Chapter 10](#) covers Twisted's support for SSH. It demonstrates how to write your own SSH server to give users remote shell access to your application, and how you can provide a live Python prompt over SSH for administering or debugging a running server. This chapter also shows how to write an SSH client to execute commands on a remote server.

Running and managing Twisted applications

[Chapter 11](#) shows how to use the tools Twisted provides for running and managing applications, which give you the ability to run daemon processes, use *setuid* and *chroot* to limit permissions, and write log files.

[< Day Day Up >](#)

Conventions Used in This Book

This book uses standard typographical conventions to highlight different types of text. You'll see the following font styles used:

Italic

Used for emphasis, to highlight technical terms the first time they appear, and for filenames, directories, and URLs.

Constant width



Used for code samples, and for the names of variables, classes, objects, and functions when they are used within the main text of the book.

Constant width bold

Shows user input at the command line and interactive prompts.

Constant width bold italic

Shows placeholder user input that you should replace with something that makes sense for you.



What You'll Need

This book assumes a familiarity with programming in Python. If you're looking for a good introduction to Python, check out *Learning Python*, by Mark Lutz and David Ascher (O'Reilly), or *Dive Into Python*, by Mark Pilgrim (Apress). You should have a Linux, Mac OS X, or Windows computer with Python version 2.3 or later installed. Python 2.3 is included in Mac OS X 10.3 ("Jaguar") and higher, and in many Linux distributions. If you don't already have Python installed, you can download it for free from <http://www.python.org>.

Using Code Examples

This book is here to help you get your job done. In general, you may use the code in this book in your programs and documentation. You do not need to contact us for permission unless you're reproducing a significant portion of the code. For example, writing a program that uses several chunks of code from this book does not require permission. Selling or distributing a CD-ROM of examples from O'Reilly books does require permission. Answering a question by citing this book and quoting example code does not require permission. Incorporating a significant amount of example code from this book into your product's documentation does require permission.

We appreciate, but do not require, attribution. An attribution usually includes the title, author, publisher, and ISBN. For example: "Twisted Network Programming Essentials by Abe Fettig. Copyright 2006 O'Reilly Media, Inc., 0-596-10032-9."

If you feel your use of code examples falls outside fair use or the permission given here, feel free to contact us at permissions@oreilly.com.

< Day Day Up >



Safari® Enabled When you see a Safari® Enabled icon on the cover of your favorite technology book, it means the book is available online through the O'Reilly Network Safari Bookshelf.

Safari offers a solution that's better than e-books. It's a virtual library that lets you easily search thousands of top technology books, cut and paste code samples, download chapters, and find quick answers when you need the most accurate, current information. Try it for free at <http://safari.oreilly.com>.

< Day Day Up >

How to Contact Us

We have tested and verified the information in this book to the best of our ability, but you may find that features have changed or that we have made mistakes. If so, please notify us by writing to:

O'Reilly Media, Inc.
1005 Gravenstein Highway North
Sebastopol, CA 95472
(800) 998-9938 (in the United States or Canada)
(707) 829-0515 (international or local)
(707) 829-0104 (fax)

You can also send messages electronically. To be put on the mailing list or request a catalog, send email to:

info@oreilly.com

To ask technical questions or comment on the book, send email to:

bookquestions@oreilly.com

We have a web site for this book, where you can find examples and errata (previously reported errors and corrections are available for public view there). You can access this page at:

<http://www.oreilly.com/catalog/twistedadn>

For more information about this book and others, see the O'Reilly web site:

<http://www.oreilly.com>

Acknowledgments

I truly appreciate the work done by all the Twisted developers to make it the amazing framework it is today. Without the efforts of Glyph Lefkowitz, Sean Riley, Allen Short, Christopher Armstrong, Paul Swartz, Jürgen Hermann, Moshe Zadka, Benjamin Bruheim, Travis B. Hartwell, Itamar Shtull-Trauring, Andrew Bennetts, Kevin Turner, Donovan Preston, JP Calderone, Gavin Cooper, Jonathan Lange, Bob Ippolito, Pavel Pergamenshchik, Jonathan D. Simms, Brian Warner, Mary Gardiner, Eric Mangold, Tommi Virtanen, James Y. Knight, and many others, there would have been nothing for me to write about. Thank you all for your contributions to Twisted and open source software. I hope this book helps many more developers to appreciate what you've done in creating Twisted.

While working on this book, I received a great deal of valuable help and guidance from my editor, Jonathan Gennick, and the tech reviewers: Itamar Shtull-Trauring, Valentino Volonghi, and Greg Gennick. Thank you. I'd also like to thank James Y. Knight and Donovan Preston for helping with [Chapter 5](#).

While working on this book I appreciated the support and encouragement of my parents, Mo and Peter Fettig, as well as Garrett Wilkin, Nellie Fettig, Sheri Smith, and many other friends and relatives. My colleagues at JotSpot were understanding when this project was taking its toll on my time and energy. Arabica Coffee in Portland, Maine, provided a great place to work and the world's best espresso. Mike and Jeannine Kertzman let us hide out in their old farmhouse when I needed a change of environment.

For some time, I've noticed that a feature of many acknowledgments sections is the part where the author somewhat guiltily thanks his wife for being so patient while he was working on the book. Now I have a better understanding of why this is the case. Writing a book is a lot of work, much more than I imagined when I began this project. Getting it done required many early mornings, late nights, and Sunday afternoons. Through it all, my wife Hannah was loving and supportive. She kept our schedule and our household on track during a time when I was busier than I had ever been in my life. She made it possible for me to get this book completed without losing my mind or my joy. Hannah, thank you. You're the best.

Chapter 1. Getting Started

Before you can start developing applications using Twisted, you'll need to download and install Twisted and its related packages. This chapter walks you through the installation process on various operating systems. It also shows you how to add the Twisted utilities to your path, familiarize yourself with the Twisted documentation, and get answers to your questions from the Twisted community.

1.1. Installing Twisted

First things first: you need to get Twisted installed on your computer. Downloads and instructions for installing Twisted on various operating systems can be found at <http://twistedmatrix.com/projects/core/>. To enable additional functionality in Twisted, you'll have to install a couple of optional packages as well.

1.1.1. How Do I Do That?

Begin by downloading the latest Twisted release from <http://www.twistedmatrix.com>. Then install PyOpenSSL (a Python wrapper of the popular OpenSSL library), which Twisted uses to make encrypted Secure Socket Layer (SSL) connections. Finally, install PyCrypto, a package containing Python implementations of encryption algorithms used by the Secure Shell (SSH). Locations for these downloads are provided in each of the following platform-specific sections.



You don't need to install PyOpenSSL or PyCrypto in order to use Twisted. Without these packages installed, you won't be able to use Twisted's SSL and SSH features, but everything else will still work.

1.1.1.1. Windows

Go to <http://twistedmatrix.com/projects/core/>. Download the Twisted Windows "Sumo" installer for Python 2.4 (or your Python version). The Sumo binary includes the Twisted core, as well as a number of extra modules to support specific groups of protocols like mail and web. You'll need the full Sumo version of Twisted installed to run most of the examples in this book. Then go to <http://twistedmatrix.com/products/download> and find the section labeled "Twisted Dependencies for Windows." There you'll find links to installers for the latest versions of PyOpenSSL and PyCrypto.



It's possible that some of these packages might move to different pages as the Twisted web site grows and is restructured in the future. If one of these links doesn't work for you, try starting from the Twisted home page at <http://twistedmatrix.com>.

Once you've downloaded all three installers, run the Twisted Setup program. It's a simple installer, and it will automatically detect your existing Python installation. Next, run the PyOpenSSL and PyCrypto installers. These are even simpler than the Twisted installer and take only a few seconds to complete.



When byte-compiling the Twisted modules, the Twisted Setup program will throw up a tiny, floating progress bar that sits in a very tiny window of its own. The unpacking may take several minutes.

Verify that the installation worked by importing the twisted package from an interactive Python prompt:

```
$ python
```

```
Python 2.3 ("help", "copyright", "credits" or "license" for more information.
```

```
>>> import twisted
```

```
>>>
```

If the `import twisted` statement runs with no errors, you have a working Twisted install.

1.1.1.2. Mac OS X, Linux, and BSD

Many Linux distributions and BSD variants, including Debian, Ubuntu, Gentoo Linux, Red Hat Linux, and FreeBSD, have prepackaged versions of Twisted, PyOpenSSL, and PyCrypto available. Check the Twisted download page to see if it mentions your operating system, or search your favorite package repository. If there are packages available, make sure they are for Twisted 2.0 or higher, not the older 1.3 release.

If you can't find a prepackaged version of Twisted for your operating system or platform, refer to the following instructions on installing from source.

[< Day Day Up >](#)

1.2. Installing from Source Files

If you're on an operating system for which no Twisted binary packages are available, you'll need to install from source. Don't worry, though; as source installs go, Python packages are among the easiest you'll find.

1.2.1. How Do I Do That?

First, download the full "Sumo" source package for Twisted (choosing the version with documentation) from <http://twistedmatrix.com/projects/core/>. The Sumo package is the core of Twisted, plus a number of bundled modules from other projects developed under the Twisted umbrella; you'll need the modules in the Sumo package to run most of the examples in this book. Once you've downloaded the package, extract it to a working directory:

```
$ tar -xjvf ~/downloads/TwistedSumo-2005-03-22.tar.bz2
TwistedSumo-2005-03-22/
TwistedSumo-2005-03-22/bin/
...
TwistedSumo-2005-03-22/README
TwistedSumo-2005-03-22/LICENSE
TwistedSumo-2005-03-22/setup.py
TwistedSumo-2005-03-22/ZopeInterface-3.0.1.tgz
```

Next, enter the *TwistedSumo-version* directory. Twisted depends on the `zope.interface` package, which is bundled in the Twisted Sumo distribution. Unzip the ZopeInterface tarball:

```
$ tar -xzvf ZopeInterface-3.0.1.tgz
ZopeInterface-3.0.1/
ZopeInterface-3.0.1/Support/
ZopeInterface-3.0.1/Support/zpkgsetup/
ZopeInterface-3.0.1/Support/zpkgsetup/publication.py
...
ZopeInterface-3.0.1/setup.py
ZopeInterface-3.0.1/setup.cfg
ZopeInterface-3.0.1/MANIFEST
```

Enter the *ZopeInterface- $\langle version \rangle$* directory, and run the command *python setup.py install*. This command will build and install the *zope.interface* package in your python installation's *lib/site-packages/twisted* directory. You'll need to have administrative/root permissions to do this, so use *su* or *sudo* to increase your permission level if necessary:

```
$ cd ZopeInterface-3.0.1
$ python setup.py install
running install
running build
running build_py
running build_ext
building 'zope.interface._zope_interface_coptimizations' extension
...
running install_lib
copying build/lib.linux-i686-2.4/zope/interface/_zope_interface_coptimizations.so ->
/usr/lib/python2.4/site-packages/zope/interface
writing byte-compilation script '/tmp/tmpdY9dA9.py'
/usr/bin/python -O /tmp/tmpdY9dA9.py
removing /tmp/tmpdY9dA9.py
```

Once *zope.interface* is installed, you're ready to install Twisted. In this *TwistedSumo- $\langle version \rangle$* directory, run the command *python setup.py install*. The command will compile the Twisted C modules and install Twisted:

```
$ cd TwistedSumo-2005-03-22
$ python setup.py install
Password:
running install
running build
running build_py
...
running install_data
```



If you have more than one version of Python installed, keep in mind that Twisted will be installed for only the version of Python you're using when you run *setup.py*. The examples in this book require Python 2.3 or higher. To check your Python version, run *python -V*.

Congratulations—you've installed Twisted! You can make sure the installation worked by importing the Twisted package from an interactive Python prompt:

```
$ python
Python 2.3 ("help", "copyright", "credits" or "license" for more information.
>>> import twisted
>>>
```

If the `import twisted` statement runs with no errors, you have a working Twisted install.

Next, download the latest release of PyOpenSSL from <http://pyopenssl.sourceforge.net>. PyOpenSSL works on top of the OpenSSL library, so you'll need to make sure you have OpenSSL installed first. Mac OS X comes with OpenSSL installed, along with its header files, and all Linux and BSD distributions should have a package available (if not installed by default).



If you're using a really obscure operating system that doesn't include OpenSSL, you can download and compile the source package from <http://www.openssl.org>.

To install PyOpenSSL, follow the same steps you did when installing Twisted. First, extract the contents of the downloaded file:

```
$ tar -zxvf pyOpenSSL-0.6.tar.gz
pyOpenSSL-0.6/
pyOpenSSL-0.6/doc/
pyOpenSSL-0.6/doc/html/
...
pyOpenSSL-0.6/_ _init_ _.py
pyOpenSSL-0.6/ChangeLog
pyOpenSSL-0.6/COPYING
pyOpenSSL-0.6/version.py
```

Next, switch to the PyOpenSSL directory and run *python setup.py install* as root or an administrative user:

```
$ cd pyOpenSSL-0.6
$ python setup.py install
running install
running build
running build_py
creating build
...
byte-compiling
/System/Library/Frameworks/Python.framework/Versions/2.3/lib/python2.3/site-packages/
OpenSSL/__init__.py to __init__.pyc
byte-compiling
/System/Library/Frameworks/Python.framework/Versions/2.3/lib/python2.3/site-packages/
OpenSSL/version.py to version.pyc
```

When the installation is complete, test to confirm that the OpenSSL package is now available, and that Twisted is making use of it in its `internet.ssl` module:

```
$ python
Python 2.3 (#1, Sep 13 2003, 00:49:11)
[GCC 3.3 20030304 (Apple Computer, Inc. build 1495)] on darwin
Type "help", "copyright", "credits" or "license" for more information.
>>> import OpenSSL
>>> import twisted.internet.ssl
>>> twisted.internet.ssl.SSL
<module 'OpenSSL.SSL' from
'/System/Library/Frameworks/Python.framework/Versions/2.3/lib/python2.3/site-
packages/OpenSSL/SSL.so'>
```

If you don't see any errors, you've successfully added SSL support to your Twisted installation.

The final package to install is PyCrypto. PyCrypto, the Python Cryptography Toolkit, is a package developed by A. M. Kuchling that contains implementations of many cryptographic functions. Twisted uses PyCrypto to

support SSH connections.

Start by downloading PyCrypto from <http://www.amk.ca/python/code/crypto.html>. Then extract the package:

```
$ tar -xzf pycrypto-2.0.tar.gz
pycrypto-2.0/
pycrypto-2.0/_ _init_ _.py
pycrypto-2.0/ACKS
pycrypto-2.0/ChangeLog
...
pycrypto-2.0/Util/test/prime_speed.py
pycrypto-2.0/Util/test.py
```

Run the now-familiar *python setup.py install* (as root or an administrative user) in the PyCrypto directory:

```
$ cd pycrypto-2.0
$ python setup.py install
running install
running build
running build_py
creating build
...
byte-compiling
/System/Library/Frameworks/Python.framework/Versions/2.3/lib/python2.3/site-packages/
Crypto/Util/RFC1751.py to RFC1751.pyc
byte-compiling
/System/Library/Frameworks/Python.framework/Versions/2.3/lib/python2.3/site-packages/
Crypto/Util/test.py to test.pyc
```

To verify that the package installed correctly, import it from an interactive Python prompt. You can also make sure Twisted's `twisted.conch.ssh.transport` module is now using PyCrypto's RSA implementation:

```
$ python
Python 2.3 (#1, Sep 13 2003, 00:49:11)
```

```
[GCC 3.3 20030304 (Apple Computer, Inc. build 1495)] on darwin
```

```
Type "help", "copyright", "credits" or "license" for more information.
```

```
>>> import Crypto
```

```
>>> import twisted.conch.ssh.transport
```

```
>>> twisted.conch.ssh.transport.RSA
```

```
<module 'Crypto.PublicKey.RSA' from
```

```
'/System/Library/Frameworks/Python.framework/Versions/2.3/lib/python2.3/site-
```

```
packages/Crypto/PublicKey/RSA.pyc'>
```

And that's it! You've installed PyCrypto from source. At this point you have a complete, working Twisted installation, including support for SSL and SSH connections.

[< Day Day Up >](#)

1.3. Adding Twisted Utilities to Your Path

Twisted includes a number of scripts and utilities that you'll need to use. For convenience, you should make sure these are available in your path.

1.3.1. How Do I Do That?

Typically, all you have to do is add Twisted's utility directory to your operating system's command search path. Follow the specific instructions given in the following section for your platform.

1.3.1.1. Windows

Twisted's utilities will be installed in the Python *scripts* directory (typically in a location such as *c:\Python23\scripts*). Twisted includes a helpful Programs menu entry that launches a Windows command prompt with the Python *scripts* directory added to *%PATH%*. It's located under Programs → Twisted (Python [version]) → Twisted Command Prompt. Use this menu entry to launch your command prompt when you need to run the Twisted utilities, or edit your *%PATH%* to include the *scripts* directory.

1.3.1.2. Linux

Twisted's utilities will be installed in the same directory as your *python* binary (probably */usr/bin* or */usr/local/bin*), so you shouldn't need to make any changes to your *\$PATH*.

1.3.1.3. Mac OS X

If you're using the version of Python included with Mac OS X 2.3 "Jaguar" or later, Twisted's utilities will be installed under */System/Library/Frameworks/Python.framework/Versions/Current/bin*. Add this directory to your *\$PATH*:

```
$ set PATH=$PATH:/System/Library/Frameworks/Python.framework/Versions/Current/bin
```


1.4. Using the Twisted Documentation

Twisted includes a few different types of documentation: extensive API documentation, HOWTOs, a tutorial, and sample code. It's a good idea to familiarize yourself with this documentation now, so that you'll be able to refer to it during the development process.

1.4.1. How Do I Do That?

Documentation for Twisted is available online on the Twisted web site. A complete API reference can be found at <http://twistedmatrix.com/documents/current/api>. You'll probably refer to this documentation many times to see which classes a module contains or to see the list of arguments for a specific function. The pages in the API documentation are automatically generated from the source code using *lore*, a custom documentation tool developed as part of Twisted.

Twisted is developed as a set of subprojects, and each project has additional documentation in its section of the Twisted site. For example, documentation on the core modules is at <http://twistedmatrix.com/projects/core/documentation>, and documentation on web modules is at <http://twistedmatrix.com/projects/web/documentation>. There are links to the full list of projects and documentation on the home page.

Within each project's documentation, you'll find the following types of information:

HOWTOs

These documents describe specific features of Twisted and how to use them. The HOWTOs don't cover every part of Twisted, but they can provide a helpful starting point for certain tasks. Included in the HOWTOs is a tutorial called "Twisted From Scratch," which shows how an application can be developed in Twisted, extended to take advantage of some advanced features, and then fully integrated with the Twisted utilities.

Examples

These are examples of short and specific Twisted programs. Like the HOWTOs, these aren't comprehensive but can be an excellent resource when you need a working example of a certain feature.

Manual pages

These are HTML versions of the manpages describing how to use the Twisted utilities.

1.4.2. What About...

...viewing the API documentation without using a browser? If you'd prefer, you can view the API documentation using the standard *pydoc* utility. *pydoc* doesn't understand all of the conventions used in the Twisted internal documentation, but it's still quite usable. [Figure 1-1](#) shows output from the command *pydoc*

twisted.web.http.


Also, when you really want to understand how a part of Twisted works, you can always read the source code. With the exception of a few modules that are written in C for better performance, you don't even need the source distribution—just go to your Python *lib* directory, look under *site-packages/twisted*, and open the appropriate *.py* file in your favorite editor.

[< Day Day Up >](#)

1.5. Finding Answers to Your Questions

Even with this book, and the Twisted documentation, you'll eventually run into a question whose answer you can't figure out on your own. When that happens, it's time to get help from the Twisted community.

Figure 1-1. Using pydoc to view API documentation



```

test@sparky: /home/test
File Edit View Terminal Tabs Help
Help on module twisted.web.http in twisted.web:

NAME
    twisted.web.http - HyperText Transfer Protocol implementation.

FILE
    /usr/lib/python2.3/site-packages/twisted/web/http.py

DESCRIPTION
    This is used by twisted.web.

    API Stability: stable

    Future Plans:
    - HTTP client support will at some point be refactored to support HTTP/1.1.
    - Accept chunked data from clients in server.
    - Other missing HTTP features from the RFC.

    Maintainer: U(Itamar Shtull-Trauring<mailto:twisted@itamarst.org>)

CLASSES
    twisted.protocols.basic.LineReceiver(twisted.internet.protocol.Protocol)
    HTTPChannel(twisted.protocols.basic.LineReceiver, twisted.protocols.poli
:
  
```

1.5.1. How Do I Do That?

There are a few excellent community resources you can look to for help. First, there are the mailing lists. The [twisted-python](#) list is for general discussion of Twisted. The [twisted-web](#) list is dedicated to discussion of web applications. It's good etiquette to use the proper list; if you ask web-related questions on the [twisted-python](#) list, you'll probably be asked to move the discussion to [twisted-web](#). You can sign up for the [twisted-python](#) and [twisted-web](#) mailing lists at <http://twistedmatrix.com/cgi-bin/mailman/listinfo/twisted-python> and <http://twistedmatrix.com/cgi-bin/mailman/listinfo/twisted-web>.

Second, you can talk with Twisted users and developers in the "docLink" target="_blank" href="http://freenode.net">http://freenode.net for a list of servers). These channels feature lively, and often funny, discussion, and give you the unique opportunity to ask questions directly to members of the Twisted development team. Keep in mind, though, that such real-time support is a privilege, not a right. Be polite, and understand that developers might not always have time to answer your questions right at that moment. If you don't get an immediate answer on IRC, try sending a message to the appropriate mailing list. This approach will give the question to a wider audience, and let people answer when they have more

time.

A final resource available to the Twisted community is Planet Twisted . Located at <http://planet.twistedmatrix.com>, this web site aggregates weblog posts made by members of the Twisted development team. It's an excellent way to keep track of what's going on with Twisted development, as well as to get to know the personalities of the Twisted team. Planet Twisted also provides an RSS feed at <http://planet.twistedmatrix.com/rss.xml>.

< Day Day Up >

Chapter 2. Building Simple Clients and Servers

To develop with Twisted, you'll need to learn how to use several new classes and objects. These classes are at the core of Twisted, and you'll use them over and over in your applications. They also represent the steepest part of the Twisted learning curve. Understand how to use them, and the rest of Twisted will be easy; otherwise, you'll struggle (or write lots of unnecessary code).

This chapter shows how to write simple clients and servers with Twisted. Along the way, it introduces Twisted's basic classes, explains how they work, and demonstrates how to use them.

2.1. Starting the Twisted Event Loop

Twisted is an event-driven framework. This means that instead of having the program's functions called in a sequence specified by the program's logic, they are called in response to external actions, or events. For example, a GUI program might have code for responding to the "button pressed" event. The designer of the program can't be sure exactly when such an event will occur; but she writes a function to respond to this event whenever it does happen. Such a function is known as an event handler .

Every event-driven framework includes a special function called an event loop . Once started, an event loop runs indefinitely. While it's running, it waits for events. When an event occurs, the event loop triggers the appropriate event handler function.

Using an event loop requires a different mindset on the part of the programmer than traditional sequential programming. Once you start the event loop, you no longer have the ability to directly instruct your program what to do; it can perform actions only in response to events. Therefore, you need to think in terms of events and event handlers when you design your program. What are the events you want your program to respond to? How do you want it to react when a given event occurs?

In Twisted, there's a special object that implements the event loop. This object is called the `reactor` . You can think of the reactor as the central nervous system of a Twisted application. In addition to being responsible for the event loop, the reactor handles many other important tasks: scheduling, threading, establishing network connections, and listening for connections from other machines. To allow the reactor to do all these things, you must start its event loop, handing off control of your program.

2.1.1. How Do I Do That?

Starting the reactor is easy. Import the `reactor` object from the `twisted.internet` module. Then call `reactor.run()` to start the reactor's event loop. [Example 2-1](#) shows all the code you need.

Example 2-1. `runreactor.py`

```
from twisted.internet import reactor
print "Running the reactor..."
reactor.run( )
print "Reactor stopped."
```

The reactor will continue to run until it's told to stop. Press Ctrl-C to exit the event loop and end the application:

```
$ python runreactor.py
```

```
Running the reactor...
```

```
<ctrl-c>
```

```
^CReactor stopped.
```

That's a pretty boring example. Although the reactor was running, it hadn't been given anything to do.

[Example 2-2](#) provides a more interesting bit of code, which introduces the reactor's `callLater` method.

`reactor.callLater` is used to set up scheduled events. This method is useful when you want to schedule a function to run in the future. (Such a function is still an event handler, with the event in this case being the passage of time.) In [Example 2-2](#), functions are called after a predetermined number of seconds have passed.

Example 2-2. `calllater.py`

```
from twisted.internet import reactor

import time

def printTime( ):
    print "Current time is", time.strftime("%H:%M:%S")

def stopReactor( ):
    print "Stopping reactor"
    reactor.stop( )

reactor.callLater(1, printTime)
reactor.callLater(2, printTime)
reactor.callLater(3, printTime)
reactor.callLater(4, printTime)
reactor.callLater(5, stopReactor)

print "Running the reactor..."
reactor.run( )
print "Reactor stopped."
```

Run this program, and you'll see output like the following:

```

$ python calllater.py

Running the reactor...

Current time is 10:33:44

Current time is 10:33:45

Current time is 10:33:46

Current time is 10:33:47

Stopping reactor

Reactor stopped.

```

2.1.2. How Does That Work?

Example 2-1 simply imports the `reactor` and calls `reactor.run()` to start it. The reactor will keep running (although it hadn't been giving anything to do) until you press Ctrl-C. At that point, the reactor stops, and the program proceeds to the final line of code, which prints out a message informing you that the reactor has been stopped.

The second example uses the `reactor.callLater` function to schedule some function calls. `reactor.callLater` has two required arguments: the number of seconds to wait, and the function to run. After setting up the scheduled function calls, control is handed off to the reactor's event loop using `reactor.run()`.



You can pass additional arguments and keyword arguments to `reactor.callLater`, and they will be used to invoke your function. For example, `reactor.callLater(1, func, True, x="hello")` would result in the function call `func(True, x="hello")`, after a one-second delay.

The first four scheduled function calls were to `printTime()`, which simply printed out the current time. However, the fifth scheduled function, `stopReactor()`, did something interesting. It called `reactor.stop()`, which caused the reactor to exit the event loop. That's why you didn't have to press Ctrl-C to stop the reactor this time. It stopped itself.



You can still manually stop the reactor. Try pressing Ctrl-C halfway through this example and see what happens.

Notice the order in which things happened. First, the reactor was given instructions to run certain functions at specific times. Then the reactor was started, which handed control of the program to the reactor's event loop

and allowed it to manage the scheduled function calls. The reactor continued to run until it was told to stop—this time through a call to `reactor.stop()`. Once the reactor had stopped, the program could proceed with the final line of code, which printed a "Reactor stopped" message.



In real applications, `reactor.callLater` is typically used for timeouts and scheduled events. You might want to set up a function that runs at set intervals to do something like shut down inactive connections or save snapshots of in-memory data to disk.

2.1.3. Establishing a TCP Connection

All networked programs have to start with one basic step: making a connection. Eventually, of course, you'll want to send email, transfer files, and stream live video, but before any of that can happen, a connection between two computers must be established. This section shows how to use the Twisted reactor to open a TCP connection.

2.1.4. How Do I Do That?

Call the `reactor.connectTCP()` method to start a TCP connection, passing a `ClientFactory` object as the third parameter. The `ClientFactory` object waits for the connection to be established, and then creates a `Protocol` object that manages the flow of data back and forth along that connection. [Example 2-3](#) shows how to establish a connection between your computer and a server on the Internet (in this case, www.google.com).

Example 2-3. tcpconnection.py

```
from twisted.internet import reactor, protocol

class QuickDisconnectProtocol(protocol.Protocol):
    def connectionMade(self):
        print "Connected to %s." % self.transport.getPeer().host
        self.transportloseConnection()

class BasicClientFactory(protocol.ClientFactory):
    protocol = QuickDisconnectProtocol

    def clientConnectionLost(self, connector, reason):
        print "Lost connection: %s" % reason.getErrorMessage()
        reactor.stop()
```

```

def clientConnectionFailed(self, connector, reason):
    print "Connection failed: %s" % reason.getMessage( )
    reactor.stop( )

reactor.connectTCP('www.google.com', 80, BasicClientFactory( ))
reactor.run( )

```

When you run this example, you should get the following output:

```

$ python connection.py
Connected to www.google.com.
Lost connection: Connection was closed cleanly.

```

unless, of course, your computer is offline. In that case, you'll see an error message, such as this:

```

$ python connection.py
Connection failed: DNS lookup failed: address 'www.google.com' not found.

```

2.1.5. How Does That Work?

There are two main classes used for working with client connections, `ClientFactory` and `Protocol`. These classes are designed to handle all the potential events that arise when you start working with connections: when a connection is established, when a connection attempt fails, when an existing connection is broken, or when data is received from the other side.

`ClientFactory` and `Protocol` have specific and distinct roles. The `ClientFactory`'s job is to manage connection-related events, and to create a new `Protocol` object for each successful connection. Once the connection is established, the `Protocol` object takes over, and is put in charge of sending and receiving data across the connection and deciding when (if ever) to close the connection.



The name "Factory" in `ClientFactory` comes from the fact that it creates `Protocol` instances on demand, in response to each successful connection.

[Example 2-3](#) defines a custom `Protocol` called `QuickDisconnectProtocol`, which inherits from `protocol.Protocol`. It overrides a single method, `connectionMade`. This method is run as soon as the connection is up and running, just after the reactor has successfully established the connection and the `ClientFactory` has created this instance of `QuickDisconnectProtocol`. True to its name, the `QuickDisconnectProtocol` object quickly closes its connection (after printing the name of the host it's connected to).



`Protocol` objects have an attribute called `TRansport`, which is used for interacting with the current connection.

`BasicClientFactory` is a class inheriting from `protocol.ClientFactory`. It first sets the class-level attribute `protocol` to `QuickDisconnectProtocol`. An instance of this class will be created to manage each successful connection. `BasicClientFactory` overrides two methods of `ClientFactory`, `clientConnectionLost` and `clientConnectionFailed`. These methods are event handlers. `clientConnectionFailed` will be called if the reactor is unable to establish the connection. `clientConnectionLost` will be called when an established connection is closed or broken.

To tell the reactor to establish a TCP connection, [Example 2-3](#) calls `reactor.connectTCP`:

```
reactor.connectTCP('www.google.com', 80, BasicClientFactory( ))
```

This line tells the reactor to attempt a TCP connection to the server www.google.com, port 80, managed by an instance of `BasicClientFactory`.

< Day Day Up >

2.2. Working with Asynchronous Results

After the reactor, `Deferreds` are probably the most important objects used in Twisted. You'll work with `Deferreds` frequently in Twisted applications, so it's essential to understand how they work. `Deferreds` can be a little confusing at first, but their purpose is simple: to keep track of an asynchronous action, and to get the result when the action is completed.

`Deferreds` can be illustrated this way: perhaps you've had the experience of going to one of those restaurants where, if there's going to be a wait for a table, you're given a little pager that will buzz when your table is ready. Having the pager is nice, because it gives you freedom to do other things while you're waiting for your table, instead of standing around the front of the restaurant feeling bored. You can take a walk outside, or even go next door and do some shopping. When a table (finally!) becomes available, the pager buzzes, and you head back inside the restaurant to be seated.

A `Deferred` is like that pager. It gives your program a way of finding out when some asynchronous task is finished, which frees it up to do other things in the meantime. When a function returns a `Deferred` object, it's saying that there's going to be some delay before the final result of the function is available. To control what happens when the result does become available, you can assign event handlers to the `Deferred`.

2.2.1. How Do I Do That?

When writing a function that starts an asynchronous action, return a `Deferred` object. When the action is completed, call the `Deferred`'s `callback` method with the return value. If the action fails, call `Deferred.errback` with an exception. [Example 2-4](#) shows a program that uses an asynchronous action to test connectivity to a given server and port.

When calling a function that returns a `Deferred` object, use the `Deferred.addCallback` method to assign a function to handle the results of the deferred action if it completes successfully. Use the `Deferred.addErrback` method to assign a function to handle the exception if the deferred action fails.

Example 2-4. `connectiontest.py`

```
from twisted.internet import reactor, defer, protocol

class CallbackAndDisconnectProtocol(protocol.Protocol):

    def connectionMade(self):

        self.factory.deferred.callback("Connected!")

        self.transportloseConnection()

class ConnectionTestFactory(protocol.ClientFactory):
```

```

protocol = CallbackAndDisconnectProtocol

def __init__(self):
    self.deferred = defer.Deferred()

def clientConnectionFailed(self, connector, reason):
    self.deferred.errback(reason)

def testConnect(host, port):
    testFactory = ConnectionTestFactory()
    reactor.connectTCP(host, port, testFactory)
    return testFactory.deferred

def handleSuccess(result, port):
    print "Connected to port %i" % port
    reactor.stop()

def handleFailure(failure, port):
    print "Error connecting to port %i: %s" % (
        port, failure.getErrorMessage())
    reactor.stop()

if __name__ == "__main__":
    import sys
    if not len(sys.argv) == 3:
        print "Usage: connectiontest.py host port"
        sys.exit(1)

    host = sys.argv[1]
    port = int(sys.argv[2])
    connecting = testConnect(host, port)
    connecting.addCallback(handleSuccess, port)
    connecting.addErrback(handleFailure, port)

```

```
reactor.run( )
```

Run this script from the command line with two arguments: the name of the server to connect to and the port to connect on. The output will look something like this:

```
$ python connectiontest.py oreilly.com 80
Connection to port 80.
```

Or, if you try to connect to a closed port:

```
$ python connectiontest.py oreilly.com 81
Error connecting to port 81: Connection was refused by other side: 22: Invalid
argument.
```

Or if you try to connect to a server that doesn't really exist:

```
$ python connectiontest.py fakesite 80
Error connecting to port 80: DNS lookup failed: address 'fakesite' not found.
```

2.2.2. How Does That Work?

The `ConnectionTestFactory` is a `ClientFactory` that has a `Deferred` object as an attribute (called, predictably enough, `deferred`). When the connection is completed, the `connectionMade` method of the `CallbackAndDisconnectProtocol` will be called. `connectionMade` then calls `self.factory.deferred.callback` with an arbitrary value to indicate a successful result. If the connection fails, the `ConnectionTestFactory`'s `clientConnectionFailed` method will be called. The second argument to `clientConnectionFailed`, `reason`, is a `twisted.python.failure.Failure` object encapsulating an exception describing why the connection failed. `clientConnectionFailed` passes the `Failure` to `self.deferred.errback` to indicate that the action failed.

The `testConnect` function takes two arguments: `host` and `port`. It creates a `ConnectionTestFactory` called `testFactory`, and passes it to `reactor.connectTCP` along with the `host` and `port`. It then returns a `testFactory.deferred` attribute, which is the `Deferred` object used to track whether the connection attempt succeeds.

[Example 2-4](#) also defines two event handler functions: `handleSuccess` and `handleFailure`. When run from the command line, it takes the arguments for `host` and `port` and uses them to call `testConnect`, assigning the resulting `Deferred` to the variable `connecting`. It then uses `connecting.addCallback` and `connecting.addErrback` to set up the event handler functions. In each case, it passes `port` as an additional argument. Because any extra arguments or keyword arguments given to `addCallback` or `addErrback` will be passed on to the event handler, this has the effect of calling `handleSuccess` or `handleFailure` with the `port` as the second argument.



When your function returns a `Deferred`, you must make sure to eventually call either that `Deferred`'s `callback` or `errback` method. Otherwise, the code that calls your function will be stuck waiting forever for a result.

After calling `testConnect` and setting up the event handlers, control is handed off to the reactor with a call to `reactor.run()`. Depending on the success of `testConnect`, either `handleSuccess` or `handleFailure` will eventually be called, printing a description of what happened and stopping the reactor.

2.2.3. What About...

... keeping track of a bunch of related `Deferred`s? Sometimes you might want to write a program that does many asynchronous tasks at the same time, and then exits when they've all completed. For example, you might want to build a simple port scanner that runs the `testConnect` function from [Example 2-4](#) against a range of ports. To do this, use the `DeferredList` object, as shown in [Example 2-5](#), to manage a group of `Deferred`s.

Example 2-5. portscan.py

```
from twisted.internet import reactor, defer
from connectiontester import testConnect

def handleAllResults(results, ports):
    for port, resultInfo in zip(ports, results):
        success, result = resultInfo
        if success:
            print "Connected to port %i" % port
    reactor.stop()
```

```

import sys

host = sys.argv[1]

ports = range(1, 201)

testers = [testConnect(host, port) for port in ports]

defer.DeferredList(testers, consumeErrors=True).addCallback(
    handleAllResults, ports)

reactor.run( )

```

Run *portscan.py* with a single argument: the host to scan. It will try to connect to that host on ports 1-200 and report on the results:

```

$ python portscan.py localhost

Connected to port 22

Connected to port 23

Connected to port 25

Connected to port 80

Connected to port 110

Connected to port 139

Connected to port 143

```

[Example 2-5](#) uses a Python list comprehension to create a list of `Deferred` objects returned from `testConnect()`. Each call to `testConnect` uses the host provided from the command line, and a port from 1 to 200:

```

testers = [testConnect(host, port) for port in ports]

```

Then [Example 2-5](#) wraps the list of `Deferred` objects in a `DeferredList` object. The `DeferredList` will track the results of all the `Deferreds` in the list passed in as its first argument. When they've all finished, it will call back with a list of tuples in the format (success, result) for each `Deferred` in the list. If the `Deferred` completed successfully, the first value in each tuple will be `True` and the second will contain the results returned by the `Deferred`; if it fails, the first value will be `False` and the second will contain a `Failure` object wrapping an exception. The `consumeErrors` keyword is set to `True` to tell the `DeferredList` to completely absorb any errors in its `Deferreds`. Otherwise, you'd see a bunch of messages about unhandled errors.

When the `DeferredList` is complete, the results are passed to the `handleAllResults` function, along with a list of which ports were scanned. `handleAllResults` uses the `zip` function to match each port with its results. For each port that had a successful connection, it prints a message. Finally, it stops the reactor to end the program.

[< Day Day Up >](#)

2.3. Sending and Receiving Data

Once a TCP connection is established, it can be used for communication. A program can send data to the computer on the other end, or respond to data received from the connection.

2.3.1. How Do I Do That?

Use a subclass of `Protocol` to send and receive data. Override the `dataReceived` method to control what happens when data is received from the connection. Use `self.transport.write` to send data.

[Example 2-6](#) includes a class called `DataForwardingProtocol`, which takes any data received and writes it to `self.output`. This usage makes it possible to create a simple application, similar to the classic utility *netcat*, that passes any data received on standard input to a server, while printing any data received from the server to standard output.

Example 2-6. `dataforward.py`

```
from twisted.internet import stdio, reactor, protocol
from twisted.protocols import basic
import re

class DataForwardingProtocol(protocol.Protocol):
    def __init__(self):
        self.output = None
        self.normalizeNewlines = False

    def dataReceived(self, data):
        if self.normalizeNewlines:
            data = re.sub(r"(\r\n|\n)", "\r\n", data)

        if self.output:
            self.output.write(data)

class StdioProxyProtocol(DataForwardingProtocol):
    def connectionMade(self):
```

```

inputForwarder = DataForwardingProtocol( )
inputForwarder.output = self.transport
inputForwarder.normalizeNewlines = True
stdioWrapper = stdio.StandardIO(inputForwarder)
self.output = stdioWrapper

print "Connected to server.  Press ctrl-C to close connection."

class StdioProxyFactory(protocol.ClientFactory):
    protocol = StdioProxyProtocol

    def clientConnectionLost(self, transport, reason):
        reactor.stop( )

    def clientConnectionFailed(self, transport, reason):
        print reason.getErrorMessage( )
        reactor.stop( )

if __name__ == '__main__':
    import sys
    if not len(sys.argv) == 3:
        print "Usage: %s host port" % __file__
        sys.exit(1)

    reactor.connectTCP(sys.argv[1], int(sys.argv[2]), StdioProxyFactory( ))
    reactor.run( )

```

Run *dataforward.py* with two arguments: the host and port to connect to. Once connected, you can interact with the server from the command line. Anything you type will be sent to the server, and any data received from the server will be printed to your screen. For example, you can do a manual HTTP request to oreilly.com:

```
$ python dataforward.py oreilly.com 80
```

```
Connected to server.  Press ctrl-C to close connection.
```

```

HEAD / HTTP/1.0

Host: oreilly.com

<-- blank line

HTTP/1.1 200 OK

Date: Fri, 17 Dec 2004 06:25:53 GMT

Server: Apache/1.3.33 (Unix) PHP/4.3.9 mod_perl/1.29

P3P: policyref="http://www.oreillynet.com/w3c/p3p.xml",CP="CAO DSP COR CURa ADMa DEVa
TAIa PSAa PSDa IVAa IVDa CONo OUR DELa PUBi OTRa IND PHY ONL UNI PUR COM NAV INT DEM
CNT STA PRE"

Last-Modified: Fri, 17 Dec 2004 00:58:06 GMT

ETag: "8352-de9f-41c22f1e"

Accept-Ranges: bytes

Content-Length: 56991

Content-Type: text/html

X-Cache: MISS from www.oreilly.com

Connection: close

```

2.3.2. How Does That Work?

[Example 2-6](#) starts by defining a class called `DataForwardingProtocol`. Whenever this `Protocol` receives data, it will pass that data along to `self.output` (which can be any object with a `write` method) by calling `self.output.write`. `DataForwardingProtocol` has an attribute called `normalizeNewLines`. If this is set to `true`, it will normalize Unix-style `\n` newlines to the `\r\n` newlines used by most standard network protocols.

A subclass of `DataForwardingProtocol`, `StdioProxyProtocol`, does all the setup work. Once its connection is established, it creates a `DataForwardingProtocol` instance called `inputForwarder` and sets its output to `self.transport`. Then it wraps `inputForwarder` in an instance of the `twisted.internet.stdio.StandardIO` utility class, which hooks `inputForwarder` up to standard I/O instead of a network connection. This step has the effect of forwarding any data received on standard input to the `StdioProxyProtocol`'s network connection. Finally, it sets the `StdioProxyProtocol`'s output attribute to `stdioWrapper`, so that data received from the connection will be forwarded to standard output.

Once these protocols have been defined, it's simply a matter of defining `StdioProxyFactory`, which sets `StdioProxyProtocol` as its `protocol`, and handles stopping the reactor when the connection is closed (or fails). A call to `reactor.connectTCP` kicks off the connection attempt, and then control is given to the reactor with `reactor.run()`.

< Day Day Up >

2.4. Accepting Connections from Clients

The previous labs in this chapter dealt with client connections, where an application initiated a connection to a remote server. However, Twisted can also be used for writing network servers, where the application waits for connections from clients. This lab will show you how to write a Twisted server that accepts connections from clients and interacts with them.

2.4.1. How Do I Do That?

Create a `Protocol` object defining your server's behavior. Create a `ServerFactory` object using the `Protocol`, and pass it to `reactor.listenTCP`. [Example 2-7](#) shows a simple echo server that accepts a client connection and then repeats back all client messages.

Example 2-7. echoserver.py

```
from twisted.internet import reactor, protocol
from twisted.protocols import basic

class EchoProtocol(basic.LineReceiver):
    def lineReceived(self, line):
        if line == 'quit':
            self.sendLine("Goodbye.")
            self.transport.loseConnection()
        else:
            self.sendLine("You said: " + line)

class EchoServerFactory(protocol.ServerFactory):
    protocol = EchoProtocol

if __name__ == "__main__":
    port = 5001
    reactor.listenTCP(port, EchoServerFactory())
    reactor.run()
```

When you run this example, it will listen on port 5001, and report client connections as they are made:

```
$ python echoserver.py
Server running, press ctrl-C to stop.
Connection from 127.0.0.1
Connection from 127.0.0.1
```

In another terminal, use *netcat*, *telnet*, or the *dataforward.py* application from [Example 2-6](#) to connect to the server. It will echo anything you type back to you. Type **quit** to close your connection:

```
$ python dataforward.py localhost 5001
Connected to server. Press ctrl-C to close connection.
hello
You said: hello
twisted is fun
You said: twisted is fun
quit
Goodbye.
$ How does that work?
```

Twisted servers use the same `Protocol` classes as clients. To save some work, the `EchoProtocol` in [Example 2-6](#) inherits from `twisted.protocols.basic.LineReceiver`, which is a slightly higher-level implementation of `Protocol`. `LineReceiver` is a `Protocol` that automatically breaks its input into separate lines, making it easier to process a single line at a time. When `EchoProtocol` receives a line, it will echo it back to the client—unless the line is "quit", in which case it sends a goodbye message and closes the connection.

Next, a class called `EchoServerFactory` is defined. `EchoServerFactory` inherits from `ServerFactory`, the server-side sibling of `ClientFactory`, and sets `EchoProtocol` as its protocol. An instance of `EchoServerFactory` is then passed as the second argument to `reactor.listenTCP`, with the first argument being the port to listen on.

[< Day Day Up >](#)

Chapter 3. Web Clients

The most common way to interact with the Web is through a web browser. But as more data and services are made available on the Web, it's important to be able to write web clients that can communicate with web servers through HTTP. This chapter shows how to use the `twisted.web.client` module to interact with web resources, including downloading pages, using HTTP authentication, uploading files, and working with HTTP headers.

3.1. Downloading a Web Page

The simplest and most common task for a web client application is fetching the contents of a web page. The client connects to the server, sends an HTTP GET request, and receives an HTTP response containing the requested page.

3.1.1. How Do I Do That?

Here's where you can begin to experience the usefulness of Twisted's built-in protocol support. The `twisted.web` package includes a complete HTTP implementation, saving you the work of developing the necessary `Protocol` and `ClientFactory` classes. Furthermore, it includes utility functions that allow you to make an HTTP request with a single function call. To fetch the contents of a web page, use the function `twisted.web.client.getPage`. [Example 3-1](#) is a Python script called `webcat.py`, which fetches a URL that you specify.

Example 3-1. `webcat.py`

```
from twisted.web import client
from twisted.internet import reactor
import sys

def printPage(data):
    print data
    reactor.stop()

def printError(failure):
    print >> sys.stderr, "Error:", failure.getErrorMessage()
    reactor.stop()

if len(sys.argv) == 2:
    url = sys.argv[1]
    client.getPage(url).addCallback(
        printPage).addErrback(
            printError)
    reactor.run()
```

```
else:
```

```
    print "Usage: webcat.py <URL>"
```

Give *webcat.py* a URL as its first argument, and it will fetch and print the contents of the page:

```
$ python webcat.py http://www.oreilly.com/
<!DOCTYPE HTML PUBLIC "-//W3C//DTD HTML 4.01 Transitional//EN">
<html xmlns="http://www.w3.org/1999/xhtml" lang="en-US" xml:lang="en-US">
<head>
<title>oreilly.com -- Welcome to O'Reilly Media, Inc. -- computer books, software
conferences, online publishing</title>
...
```

3.1.2. How Does That Work?

The `printPage` and `printError` functions are simple event handlers that print the downloaded page contents or an error message, respectively. The most important line in [Example 3-1](#) is the call to `client.getPage(url)`. This function returns a `Deferred` object that will be called back with the contents of the page once it has been completely downloaded.

Notice how the callbacks are added to the `Deferred` in a single line. This is possible because `addCallback` and `addErrback` both return a reference to their `Deferred` object. Therefore, the statements:

```
d = deferredFunction( )
d.addCallback(resultHandler)
d.addErrback(errorHandler)
```

can be expressed as:

```
deferredFunction( ).addCallback(resultHandler).addErrback(errorHandler)
```

Which of these two forms is more readable is probably a matter of personal opinion, but the latter is an idiom that appears frequently in Twisted code.

3.1.3. What About...

... writing the page to disk as it's being downloaded? One disadvantage to the *webcat.py* script in [Example 3-1](#) is that it loads the entire contents of the downloading page into memory, which could present a problem if you're downloading a large file. A better approach might be to write the data to a temporary file on disk as it's being downloaded, and then read the contents back from the temp file once the download is complete.

`twisted.web.client` includes `downloadPage`, a function that is similar to `getPage` but that writes data to a file. Call `downloadPage` with a URL as the first argument, and a filename or file object as the second. The script *webcat2.py* in [Example 3-2](#) does this.

Example 3-2. *webcat2.py*

```
from twisted.web import client
import tempfile

def downloadToTempFile(url):
    """
    Given a URL, returns a Deferred that will be called back with
    the name of a temporary file containing the downloaded data.
    """
    tmpfd, tmpfilename = tempfile.mkstemp()
    os.close(tmpfd)
    return client.downloadPage(url, tmpfilename).addCallback(
        returnFilename, tmpfilename)

def returnFilename(result, filename):
    return filename

if __name__ == "__main__":
    import sys, os
    from twisted.internet import reactor
```

```

def printFile(filename):
    for line in file(filename, 'r+b'):
        sys.stdout.write(line)

    os.unlink(filename) # delete file once we're done with it

    reactor.stop( )

def printError(failure):
    print >> sys.stderr, "Error:", failure.getErrorMessage( )

    reactor.stop( )

if len(sys.argv) == 2:
    url = sys.argv[1]

    downloadToTempFile(url).addCallback(
        printFile).addErrback(
            printError)

    reactor.run( )

else:
    print "Usage: %s <URL>" % sys.argv[0]

```

The `downloadToTempFile` function in [Example 3-2](#) returns the `Deferred` that results from calling `twisted.web.client.downloadPage.downloadToTempFile` adds `returnFilename` as a callback to this `Deferred`, with the temp filename as an additional argument. This means that when the result of `downloadToTempFile` comes in, the reactor will call `returnFileName` with the result of `downloadToTempFile` as the first argument and the filename as the second argument.

[Example 3-2](#) registers another callback for the result of `downloadToTempFile`. Remember that the `Deferred` returned from `downloadToTempFile` already has `returnFilename` as a callback handler. Therefore, when the result comes in, `returnFilename` will be called first. The result of this function (the filename) will be used to call `printFile`.

[< Day Day Up >](#)

3.2. Accessing a Password-Protected Page

Web pages can require authentication. If you're developing an HTTP client application, it's a good idea to be prepared to handle this case, and give the user some way of entering his login name and password.

3.2.1. How Do I Do That?

If an HTTP request fails with a 401 status code, authentication is required. Try the request again, this time passing a user-supplied login and password in an `Authorization` header, as shown in the script `webcat3.py` in [Example 3-3](#).

Example 3-3. `webcat3.py`

```
from twisted.web import client, error as weberror
from twisted.internet import reactor
import sys, getpass, base64

def printPage(data):
    print data
    reactor.stop()

def checkHTTPError(failure, url):
    failure.trap(weberror.Error)
    if failure.value.status == '401':
        print >> sys.stderr, failure.getErrorMessage()
        # prompt for user name and password
        username = raw_input("User name: ")
        password = getpass.getpass("Password: ")
        basicAuth = base64.encodestring("%s:%s" % (username, password))
        authHeader = "Basic " + basicAuth.strip()
        # try to fetch the page again with authentication
        return client.getPage(
            url, headers={"Authorization": authHeader})
```

```

else:
    return failure

def printError(failure):
    print >> sys.stderr, "Error:", failure.getErrorMessage( )
    reactor.stop( )

if len(sys.argv) == 2:
    url = sys.argv[1]
    client.getPage(url).addErrback(
        checkHTTPError, url).addCallback(
        printPage).addErrback(
        printError)
    reactor.run( )
else:
    print "Usage: %s <URL>" % sys.argv[0]

```

Run *webcat3.py* with a URL as the first argument, and it will attempt to download and print the page. If it receives a 401 error, it will ask for a username and password and try the request again:

```

$ python webcat3.py http://example.com/protected/page

401 Authorization Required

User name: User

Password: <enter password>

<html>

<title>A Password Protected Page</title>

...

```

3.2.2. How Does That Work?

This example uses an extra error handler, `checkHTTPError`. It is added to the `Deferred` returned from `client.getPage` first, before adding the `printPage` and `printError` handler functions. This gives

`checkHTTPError` the opportunity to handle any errors returned by `client.getPage` before either of the other handler functions is called.

As an errback handler, `checkHTTPError` will be called with a `twisted.python.failure.Failure` object. The `Failure` object encapsulates the exception that was raised, records a traceback at the time of the exception, and adds several useful methods. `checkHTTPError` starts by using the `Failure.trap` method to verify that the exception was of type `twisted.web.error.Error`. If it wasn't, `trap` will reraise the exception, exiting the current function and letting the error pass on to the next errback handler in line, `printError`.

Next, `checkHTTPError` checks the HTTP response status code. `failure.value` is an `Exception` object, and since it's already been verified as type `twisted.web.error.Error`, it's known to have a `status` attribute containing the status code. If the status is not 401, the original failure is simply returned, which again has the effect of letting the error pass through to `printError`.

But if the status is 401, `checkHTTPError` takes action. It prompts the user for his login name and password, and encodes the results into an HTTP `Authorization` header. Then it calls `client.getPage` again, and returns the resulting `Deferred`. This causes something very cool to happen: the reactor waits for the results of this second call to `getPage`, and then calls `printPage` or `printError` with those results. In effect, `checkHTTPError` is saying, "Handling the error resulted in another `Deferred`—wait for the result of that `Deferred` and pass it to the next event handler in line." This technique is very powerful and is used many times in Twisted applications.

The end result is the same as in previous examples: either `printPage` is called with the downloaded page data, or `printError` is called with an error. Of course, if the initial request was successful, and didn't require authentication, `checkHTTPError` is never called at all, and the result passes directly to `printPage`.

[< Day Day Up >](#)

3.3. Uploading a File

From a user's perspective, there's no easier way to upload a file than going to a web page, using an HTML form to select the file, and pressing the submit button. Because of this, many web sites have adopted HTTP as a means of allowing file uploads. There are times, however, when you might need to perform a file upload without using a browser. Perhaps you want to develop an application that can upload image files to a photo-sharing service, or HTML documents to a web-based content management system. This lab shows how to use Twisted's HTTP client support to perform a file upload.

3.3.1. How Do I Do That?

First, encode the field/value pairs and file data that you wish to upload as a `multipart/form-data` MIME document. Neither the Python standard library nor Twisted provides an easy way to do this, but you can do it yourself without too much effort. Then pass the encoded form data as the `formdata` keyword argument to `client.getPage` or `client.downloadPage`, along with `POST` as the HTTP method. You can then work with the results of `getPage` or `downloadPage` as you would any other HTTP response. [Example 3-4](#) shows a script named `validate.py` that uploads a file to the W3C validation service, saves the response to a local file, and then displays it in the user's browser.

Example 3-4. `validate.py`

```
from twisted.web import client

import os, tempfile, webbrowser, random

def encodeForm(inputs):
    """
    Takes a dict of inputs and returns a multipart/form-data string
    containing the utf-8 encoded data. Keys must be strings, values
    can be either strings or file-like objects.
    """
    getRandomChar = lambda: chr(random.choice(range(97, 123)))
    randomChars = [getRandomChar() for x in range(20)]
    boundary = "---%s---" % ''.join(randomChars)
    lines = [boundary]

    for key, val in inputs.items():
        header = 'Content-Disposition: form-data; name="%s"' % key
        if hasattr(val, 'name'):
```

```

        header += '; filename="%s"' % os.path.split(val.name)[1]
    lines.append(header)
    if hasattr(val, 'read'):
        lines.append(val.read( ))
    else:
        lines.append(val.encode('utf-8'))
    lines.append('')
    lines.append(boundary)
return "\r\n".join(lines)

```

```

def showPage(pageData):
    # write data to temp .html file, show file in browser
    tmpfd, tmp = tempfile.mkstemp('.html')
    os.close(tmpfd)
    file(tmp, 'w+b').write(pageData)
    webbrowser.open('file://' + tmp)
    reactor.stop( )

```

```

def handleError(failure):
    print "Error:", failure.getErrorMessage( )
    reactor.stop( )

```

```

if __name__ == "__main__":
    import sys
    from twisted.internet import reactor

    filename = sys.argv[1]
    fileToCheck = file(filename)
    form = encodeForm({'uploaded_file': fileToCheck})
    postRequest = client.getPage(
        'http://validator.w3.org/check',
        method='POST',
        headers={'Content-Type': 'multipart/form-data; charset=utf-8',

```

```
'Content-Length': str(len(form))},  
    postdata=form)  
postRequest.addCallback(showPage).addErrback(handleError)  
reactor.run( )
```

Run *validate.py* with the name of an HTML file as the first argument:

```
$ python validate.py test.html
```

As long as there are no errors, you should get a validation report in your default browser, similar to the report shown in [Figure 3-1](#).

Figure 3-1. Result of running *validate.py*



3.3.2. How Does That Work?

The W3C validate page, <http://validator.w3.org>, contains a form that looks like this:

```
<form method="post" enctype="multipart/form-data" action="check">
  <label title="Choose a Local File to Upload and Validate"
    for="uploaded_file">Local File:
  <input type="file" name="uploaded_file" size="30" /></label>
  <label title="Submit file for validation">
  <input type="submit" value="Check" /></label>
</form>
```

You can build an HTTP client that sends the same data a browser would use when submitting that form. The `encodeForm` function takes a dictionary that maps keys to string values or file-like objects, and returns a string containing the data as a `multipart/form-encoded` MIME document. When `validate.py` runs, it opens the file specified as its first argument and passes it to `encodeForm` as the `'uploaded_file'` value of a dictionary. This returns the data that should be posted to the validator service.

`validate.py` then uses `client.getPage` to post the form data, passing headers to advise the server of the `Content-Length` and `Content-Type` of the data being posted. The `showPage` callback handler takes the data returned from the validator service and writes it to a temporary file. Then it uses Python's `webbrowser` module to open the file in the user's default browser.

[< Day Day Up >](#)

3.4. Checking Whether a Page Has Changed

One popular HTTP application is RSS (Really Simple Syndication) aggregators, which download news items or blog posts in RSS (or Atom) format. RSS aggregators download a new copy of each RSS feed at regular intervals, typically once an hour. This process can end up wasting a lot of bandwidth for the publisher of the RSS feed, though: the contents of the feed may change infrequently, which means that the client will be downloading the same data over and over again.

To prevent this waste of network resources, RSS aggregators (and other applications that request the same page multiple times) are encouraged to use a conditional HTTP GET request. By including conditional HTTP headers with a request, a client instructs the server to return the page data only if certain conditions are met. And, of course, one of those conditions might be whether the page has been modified since it was last checked.

3.4.1. How Do I Do That?

Keep track of the headers returned the first time you download the page. Look for either an `ETag` header, which identifies the unique revision of the page, or the `Last-Modified` header, which gives the page's modification time. The next time you request the page, send the headers `If-None-Match`, with the `ETag` value, and `If-Modified-Since`, with the `Last-Modified` value. If the server supports conditional GET requests, it will return a `304 Unchanged` response if the page has not been modified since the last request.

The `getPage` and `downloadPage` functions provided by `twisted.web.client` are handy, but they don't allow for the level of control necessary to use conditional requests. Therefore, you'll need to use the slightly lower-level `HTTPClientFactory` interface. [Example 3-5](#) demonstrates using `HTTPClientFactory` to test whether a page has been updated.

Example 3-5. `updatecheck.py`

```
from twisted.web import client

class HTTPStatusChecker(client.HTTPClientFactory):

    def __init__(self, url, headers=None):
        client.HTTPClientFactory.__init__(self, url, headers=headers)
        self.status = None
        self.deferred.addCallback(
            lambda data: (data, self.status, self.response_headers))
```

```

def noPage(self, reason): # called for non-200 responses
    if self.status == '304': # Page hadn't changed
        client.HTTPClientFactory.page(self, '')
    else:
        client.HTTPClientFactory.noPage(self, reason)

def checkStatus(url, contextFactory=None, *args, **kwargs):
    scheme, host, port, path = client._parse(url)
    factory = HTTPStatusChecker(url, *args, **kwargs)
    if scheme == 'https':
        from twisted.internet import ssl
        if contextFactory is None:
            contextFactory = ssl.ClientContextFactory( )
        reactor.connectSSL(host, port, factory, contextFactory)
    else:
        reactor.connectTCP(host, port, factory)
    return factory.deferred

def handleFirstResult(result, url):
    data, status, headers = result
    nextRequestHeaders = {}
    eTag = headers.get('etag')
    if eTag:
        nextRequestHeaders['If-None-Match'] = eTag[0]
    modified = headers.get('last-modified')
    if modified:
        nextRequestHeaders['If-Modified-Since'] = modified[0]
    return checkStatus(url, headers=nextRequestHeaders).addCallback(
        handleSecondResult)

def handleSecondResult(result):
    data, status, headers = result
    print 'Second request returned status %s:' % status,
    if status == '200':

```

```

        print 'Page changed (or server does not support conditional requests).'
```

```

elif status == '304':
    print 'Page is unchanged.'
```

```

else:
    print 'Unexpected Response.'
```

```

reactor.stop( )

def handleError(failure):
    print "Error", failure.getErrorMessage( )
    reactor.stop( )

if __name__ == "__main__":
    import sys
    from twisted.internet import reactor

    url = sys.argv[1]
    checkStatus(url).addCallback(
        handleFirstResult, url).addErrback(
        handleError)
    reactor.run( )
```

Run `updatecheck.py` from the command line with a web URL as the first argument. It will download the page once, and then download it again using a conditional GET. It then indicates whether the second response was a 304, indicating that the server understood the conditional headers and indicated that the page had not changed. It's fairly typical for servers to support conditional GET requests for static files, such as RSS feeds, but not dynamically generated content, such as the home page:

```

$ python updatecheck.py http://slashdot.org/slashdot.rss
Second request returned status 304: Page is unchanged

$ python updatecheck.py http://slashdot.org/
Second request returned status 200: Page changed
(or server does not support conditional requests).
```

3.4.2. How Does That Work?

The `HTTPStatusChecker` class is a subclass of `client.HTTPClientFactory`. It does a couple of notable things. During initialization, it adds an additional callback to `self.deferred`, using a lambda function. This anonymous function will catch the result of `self.deferred` before it gets passed to any external callback handlers. It will then replace this result (the downloaded data) with a tuple containing more information: the data, the HTTP status code, and `self.response_headers`, which is a dictionary of the headers returned with the response.

`HTTPStatusChecker` also overrides the `noPage` method, which `HTTPClientFactory` calls to indicate an unsuccessful response code. If the response status is 304 (the Unchanged status code), the `noPage` method calls `HTTPClientFactory.page` instead of the original `noPage` method, which indicates a successful response. In the case of a success, of course, the `noPage` in `HTTPStatusChecker` passes the call on to the overridden `noPage` in `HTTPClientFactory`. In this way, it prevents a 304 response from being considered an error.

The `checkStatus` function takes a URL and parses it using the `twisted.web.client._parse` utility function. It looks at the parts of the URL, gets the hostname it needs to connect to, and whether it's using HTTP (which runs over straight TCP) or HTTPS (which runs over SSL, and establishes the connection using `reactor.connectSSL`). Next, `checkStatus` creates an `HTTPStatusChecker` factory object, and opens the connection. All this code is basically lifted from `twisted.web.client.getPage` and modified to use the `HTTPStatusChecker` factory instead of the vanilla `HTTPClientFactory`.

When `updatecheck.py` runs, it calls `checkStatus`, setting `handleFirstResult` as the callback handler. `handleFirstResult`, in turn, makes a second request using the `If-None-Match` and `If-Modified-Since` conditional headers, setting `handleSecondResult` as the callback handler. The `handleSecondResult` function reports whether the server returned a 304 response, and then stops the reactor.

`handleFirstResult` actually returns the deferred result of `handleSecondResult`. This allows `printError`, the error handler function assigned to the first call to `checkStatus`, to handle any errors that come up in the second call to `checkStatus` as well.

[< Day Day Up >](#)

3.5. Monitoring Download Progress

One potential weakness in the examples presented so far in this chapter is that there hasn't been a way to monitor a download in progress. Sure, it's nice that a `Deferred` will pass you the results of a page once it's completely downloaded, but sometimes what you really need is to keep an eye on the download as it's happening.

3.5.1. How Do I Do That?

Again, the utility functions provided by `twisted.web.client` don't give you quite enough control. Define a subclass of `client.HTTPDownloader`, the factory class used for downloading a web page to a file. By overriding a couple of methods, you can keep track of a download in progress. The `webdownload.py` script in [Example 3-6](#) shows how.

Example 3-6. `webdownload.py`

```
from twisted.web import client

class HTTPProgressDownloader(client.HTTPDownloader):

    def gotHeaders(self, headers):
        if self.status == '200': # page data is on the way
            if headers.has_key('content-length'):
                self.totalLength = int(headers['content-length'][0])
            else:
                self.totalLength = 0
            self.currentLength = 0.0
            print ''
        return client.HTTPDownloader.gotHeaders(self, headers)

    def pagePart(self, data):
        if self.status == '200':
            self.currentLength += len(data)
            if self.totalLength:
                percent = "%i%%" % (
```

```

        (self.currentLength/self.totalLength)*100)

    else:

        percent = '%dK' % (self.currentLength/1000)

        print "\033[1FProgress: " + percent

    return client.HTTPDownloader.pagePart(self, data)

def downloadWithProgress(url, file, contextFactory=None, *args, **kwargs):

    scheme, host, port, path = client._parse(url)

    factory = HTTPProgressDownloader(url, file, *args, **kwargs)

    if scheme == 'https':

        from twisted.internet import ssl

        if contextFactory is None:

            contextFactory = ssl.ClientContextFactory( )

        reactor.connectSSL(host, port, factory, contextFactory)

    else:

        reactor.connectTCP(host, port, factory)

    return factory.deferred

if __name__ == "__main__":

    import sys

    from twisted.internet import reactor

    def downloadComplete(result):

        print "Download Complete."

        reactor.stop( )

    def downloadError(failure):

        print "Error:", failure.getErrorMessage( )

        reactor.stop( )

    url, outputFile = sys.argv[1:]

    downloadWithProgress(url, outputFile).addCallback(

        downloadComplete).addErrback(

```

```
downloadError)
reactor.run( )
```

Run *webdownload.py* with two arguments: the URL of a page to download and a filename in which to save it. As the command works, it will print updates on the download progress:

```
$ python webdownload.py http://www.oreilly.com/ oreilly.html
Progress: 100% <- updated during the download
Download Complete.
```

If the web server doesn't return a `Content-Length` header indicating the total length of the download, it isn't possible to calculate the percentage complete. In this case, *webdownload.py* prints the number of kilobytes downloaded:

```
$ python webdownload.py http://www.slashdot.org/ slashdot.html
Progress: 60K <- updated during the download
Download Complete.
```

3.5.2. How Does That Work?

`HTTPProgressDownloader` is a subclass of `client.HTTPDownloader`. It overrides the `gotHeaders` method to check for a `Content-Length` header that would indicate the total size of the page being downloaded. It also overrides the `pagePart` method, which is called each time a chunk of page data is received, to keep track of the number of bytes downloaded so far.

Each time a chunk of data comes in, `HTTPProgressDownloader` prints out a progress report. The string `\033[1F` is a terminal escape sequence that causes each line of the progress report to be written over the preceding line. This effect makes it look like the progress information is being updated in place.

The `downloadWithProgress` function contains code similar to that in [Example 3-5](#) for parsing the requested URL, creating the `HTTPProgressDownloader` factory object, and initializing the connection. `downloadComplete` and `downloadError` are simple callback and errback handlers that print a message and stop the reactor.

< Day Day Up >

Chapter 4. Web Servers

It's probably safe to say that these days, most new software is being developed in the form of web applications. People spend an increasingly large part of their day in their web browser, not just reading HTML pages but sending email, managing calendars, entering records into databases, updating Wiki pages, and writing weblog posts.

Even if you're not writing an application strictly for the Web, a web interface is often the easiest way to provide a cross-platform UI for things like administration and reporting. The ability to include a lightweight web server inside your app without introducing any additional dependencies is one of the great things about developing with Twisted. This chapter shows you how to run a web server using Twisted, and introduces you to some building blocks for creating web applications. It also offers an example of a custom HTTP proxy server.



This chapter provides some introductory information about the HTTP protocol used by web servers and web clients. There are many additional details of HTTP that you should know if you're serious about building web applications. In fact, there's enough information to write an entire book on the subject, such as *HTTP: The Definitive Guide* by David Gourley and Brian Totty (O'Reilly). There's also no substitute for reading the HTTP spec, RFC 2616 (<http://www.faqs.org/rfcs/rfc2616.html>).

4.1. Responding to HTTP Requests

HTTP is, on its surface, a simple protocol. A client sends a request, the server sends a response, the connection closes. You can experiment with HTTP by writing your own `Protocol` that accepts a connection, reads the request, and sends back an HTTP-formatted response.

4.1.1. How Do I Do That?

Every HTTP request starts with a single line containing the HTTP method, a partial Uniform Resource Identifier (URI), and the HTTP version. Following this line are an arbitrary number of header lines. A blank line indicates the end of the headers. The header section is optionally followed by additional data called the body of the request, such as data being posted from an HTML form.

Here's an example of a minimal HTTP request. This request asks the server to perform the method `GET` on the resource www.example.com/temp0081.html, preferably using HTTP version 1.1:

```
GET /temp0081.html HTTP/1.1
Host: www.example.com
```

The first line of the server's response tells the client the HTTP version being used for the response and the HTTP status code. Like the request, the response also contains header lines followed by a blank line and the message body. Here's a minimal HTTP response:

```
HTTP/1.1 200 OK
Content-Type: text/plain
Content-Length: 17
Connection: Close

Hello HTTP world!
```

To set up a very basic HTTP server, write a `Protocol` that accepts input from the client. Look for the blank line that identifies the end of the headers. Then send an HTTP response. [Example 4-1](#) shows a simple HTTP implementation that echoes each request back to the client.

Example 4-1. webecho.py

```

from twisted.protocols import basic
from twisted.internet import protocol, reactor

class HttpEchoProtocol(basic.LineReceiver):

    def __init__(self):
        self.lines = []
        self.gotRequest = False

    def lineReceived(self, line):
        self.lines.append(line)

        if not line and not self.gotRequest:
            self.sendResponse( )
            self.gotRequest = True

    def sendResponse(self):
        responseBody = "You said:\r\n\r\n" + "\r\n".join(self.lines)
        self.sendLine("HTTP
/1.0 200 OK")

        self.sendLine("Content-Type: text/plain")
        self.sendLine("Content-Length: %i" % len(responseBody))
        self.sendLine("")
        self.transport.write(responseBody)
        self.transportloseConnection( )


f = protocol.ServerFactory( )
f.protocol = HttpEchoProtocol
reactor.listenTCP(8000, f)
reactor.run( )

```

Run *webecho.py* to start the server. You can see the server in action by pointing your web browser to

<http://localhost:8000>. You'll get a response echoing the request your browser sends to the server, as shown in Figure 4-1.

Figure 4-1. Viewing the response from `webecho.py`



4.1.2. How Does That Work?

`HTTPEchoProtocol` understands just enough about HTTP to return a response to each request. As data is received from the client, it appends each incoming line to `self.lines`. When it sees a blank line, it knows that it has come to the end of the headers. It then sends back an HTTP response. The first line contains the HTTP version and status code; in this case, 200 for OK (the string "OK" is a human-readable version of the status code; it could just as easily be another phrase with the same meaning, like "No problem!"). The next couple of lines are the `Content-Type` and `Content-Length` headers, which tell the client the format and length of the body. `HTTPEchoProtocol` sends a blank line to indicate the end of the headers, and then the body itself, which in this case is just an echo of the request sent by the client.

< Day Day Up >

4.2. Parsing HTTP Requests

The `HTTPEchoProtocol` class in [Example 4-1](#) provides an interesting glimpse into HTTP in action, but it's a long way from being ready for use in a real web server. It doesn't even parse the request to figure out what resource the client is trying to access, or what HTTP method she's using. Before you try to build a real web application, you need a better way to parse and respond to requests. This lab shows you how.

4.2.1. How Do I Do That?

Write a subclass of `twisted.web.http.Request` with a `process` method that processes the current request. The `Request` object will already contain all the important information about an HTTP request when `process` is called, so all you have to do is decide how to respond. [Example 4-2](#) demonstrates how to run an HTTP server based on a subclass of `http.Request`.

Example 4-2. requesthandler.py

```
from twisted.web import http

class MyRequestHandler(http.Request):
    pages = {
        '/': '<h1>Home</h1>Home page',
        '/test': '<h1>Test</h1>Test page',
    }


    def process(self):
        if self.pages.has_key(self.path):
            self.write(self.pages[self.path])
        else:
            self.setResponseCode(http.NOT_FOUND)
            self.write("<h1>Not Found</h1>Sorry, no such page.")
        self.finish( )

class MyHttp(http.HTTPChannel):
    requestFactory = MyRequestHandler
```

```
class MyHttpFactory(http.HTTPFactory):  
    protocol = MyHttp  
  
if __name__ == "__main__":  
    from twisted.internet import reactor  
    reactor.listenTCP(8000, MyHttpFactory())  
    reactor.run()
```


Run *requesthandler.py* and it will start up a web server on port 8000. You should be able to view both the home page (<http://localhost:8000/>) and the page /test (<http://localhost:8000/test>) in your browser. [Figure 4-2](#) shows you how the page /test will look in your browser.

Figure 4-2. A page generated by the requesthandler.py web server



If you attempt to load any other page, you should get an error message, as shown in [Figure 4-3](#).

Figure 4-3. The requesthandler.py 404 page



4.2.2. How Does That Work?

The `http.Request` class parses an incoming HTTP request and provides an interface for working with the request and generating a response. In [Example 4-2](#), `MyRequestHandler` is a subclass of `http.Request` that provides a custom `process` method. The `process` method will be called after the request has been completely received. It is responsible for generating a response and then calling `self.finish()` to indicate that the response is complete. `MyRequestHandler` uses the `path` property to find out which path is being requested, and attempts to find a matching path in the `pages` dictionary. If a matching page is found, `MyRequestHandler` uses the `write` method to send back the text of the page as the response.

Note that `write` is used only to write the body portion of the response, not to generate the raw HTTP response itself. The `setResponseCode` method can be used to change the HTTP status code. The `twisted.web.http` module provides constants for all the status codes defined by HTTP, so you can write `http.NOT_FOUND` instead of 404.



`Request.setResponseCode` takes an optional second argument, a human-readable status message. You can feel free to leave this out—the `twisted.web.http` module includes a built-in list of descriptions for common status codes, which it will use by default.

The `Request` class also provides a `setHeader` method for adding headers to the response. `MyRequestHandler` uses `setHeader` to set the `Content-Type` header to `text/html`; this setting tells the browser that the response body is in HTML format.

The `twisted.web.http` module provides two additional classes that you'll need to turn your subclass of `Request` into a functioning web server. The `HTTPChannel` class is a `Protocol` that creates `Request` objects for each connection. To make the `HTTPChannel` use your subclass of `Request`, override the `requestFactory` class attribute. `HTTPFactory` is a `ServerFactory` that adds some extra features, including a `log` method that takes a `Request` object and generates a log message in the standard Combined log format used by Apache and other web servers.

[< Day Day Up >](#)

4.3. Working with POST Data from HTML Forms

The previous lab showed how to take a request from a client and return a response containing static HTML. This lab shows how you could write code to control how each response is generated, and act on data submitted from an HTML form.

4.3.1. How Do I Do That?

Write functions that take a `Request` object and work with it to generate a response. Set up a dictionary to map each available path in your web site to a function that will handle requests for that path. Use the `Request.args` dictionary to access data submitted from an HTML form. [Example 4-3](#) shows a web server that generates one page containing an HTML form, and another page that processes the form and displays the results.

Example 4-3. formhandler.py

```
from twisted.web import http

def renderHomePage(request):
    colors = 'red', 'blue', 'green'
    flavors = 'vanilla', 'chocolate', 'strawberry', 'coffee'
    request.write("""
<html>
<head>
    <title>Form Test</html>
</head>
<body>
    <form action='posthandler' method='post'>
        Your name:
        <p>
            <input type='text' name='name'>
        </p>
        What's your favorite color?
        <p>
    """)
```

```

for color in colors:
    request.write(
        "<input type='radio' name='color' value='%s'>%s<br />" % (
            color, color.capitalize( ))
request.write("""
    </p>
    What kinds of ice cream do you like?
    <p>
    """)
for flavor in flavors:
    request.write(
        "<input type='checkbox' name='flavor' value='%s'>%s<br />" % (
            flavor, flavor.capitalize( ))
request.write("""
    </p>
    <input type='submit' />
</form>
</body>
</html>
""")
request.finish( )

```

```

def handlePost(request):
    request.write("""
<html>
    <head>
        <title>Posted Form Data</title>
    </head>
    <body>
        <h1>Form Data</h1>
    """)

    for key, values in request.args.items( ):

```

```

request.write("<h2>%s</h2>" % key)

request.write("<ul>")

for value in values:
    request.write("<li>%s</li>" % value)

request.write("</ul>")

request.write("""
    </body>
</html>
""")

request.finish( )

class FunctionHandledRequest(http.Request):
    pageHandlers = {
        '/': renderHomePage,
        '/posthandler': handlePost,
    }

    def process(self):
        self.setHeader('Content-Type', 'text/html')

        if self.pageHandlers.has_key(self.path):
            handler = self.pageHandlers[self.path]
            handler(self)

        else:
            self.setResponseCode(http.NOT_FOUND)

            self.write("<h1>Not Found</h1>Sorry, no such page.")

            self.finish( )

class MyHttp(http.HTTPChannel):
    requestFactory = FunctionHandledRequest

class MyHttpFactory(http.HTTPFactory):
    protocol = MyHttp

```

```

if __name__ == "__main__":
    from twisted.internet import reactor

    reactor.listenTCP(8000, MyHttpFactory( ))

    reactor.run( )

```

Run *formhandler.py*. It will start a web server on port 8000. Go to <http://localhost:8000/> and fill out the form on the home page. [Figure 4-4](#) shows the home page with some fields already filled in.

Figure 4-4. Filling out the form generated by *formhandler.py*

The screenshot shows a Mozilla Firefox browser window titled "Form Test - Mozilla Firefox". The address bar shows "http://localhost:8000/". The form content is as follows:

Your name:


What's your favorite color?
 Red
 Blue
 Green

What kinds of ice cream do you like?
 Vanilla
 Chocolate
 Strawberry
 Coffee

Done

When you click the Submit button, your browser will send the form data to the page *formhandler* using an HTTP POST request. When it receives the form data, *formhandler* will show you the fields and values that were submitted, as shown in [Figure 4-5](#).

Figure 4-5. Displaying data submitted from a form



4.3.2. How Does That Work?

[Example 4-3](#) defines two different functions for handling requests, `renderHomePage` and `handlePost`. `FunctionHandledRequest` is a subclass of `Request` with an attribute called `pageHandlers` that maps paths to functions. The `process` method looks at the path this particular request is using and tries to find a matching path in `pageHandlers`. If a match is found, the `FunctionHandledRequest` passes itself to the matching function, which is free to process the request however it likes; if no match is found, it generates a 404 "Not Found" response.

The `renderHomePage` function is set as the handler for `/`, the root page of the site. It generates an HTML form that will submit data to the page `/formhandler`. The handler function for `/formhandler` is `handlePost`, which responds with a page listing the posted data. `handlePost` iterates through the keys and values in `Request.args`, which is a dictionary representing all the form data sent with the request.



In this case, the form data is sent as the body of an HTTP POST request. When a request is sent using HTTP GET, `Request.args` will contain values taken from the query portion of the request URI. You can verify this behavior by changing the `method` attribute of the form generated by `renderHomePage` from `post` to `get`, restarting the server, and resubmitting the form.

An HTML form can have multiple fields with the same name. For example, the form in [Example 4-3](#) lets you check off multiple checkboxes, all which have the name of a `flavor`. Unlike many other web frameworks, `http.Request` doesn't hide this from you: instead of a mapping each field name to a string, `Request.args` maps each field name to a list. If you know there's going to be one value for a particular field, just grab the first value from the list.

[< Day Day Up >](#)

4.4. Managing a Hierarchy of Resources

The paths in a web application usually imply a hierarchy of resources. For example, look at these URIs:

```
http://example.com/people
http://example.com/people/charles
http://example.com/people/charles/contact
```

It's easy to see the hierarchy here. The page */people/charles* is a child of */people*, and the page */people/charles/contact* is a child of */people/charles*. Each page in the hierarchy is more specific: */people/charles* is one specific person, and */people/charles/contact* is one specific type of data (in this case, contact information) related to *charles*.

The default behavior for most web servers is to map request paths to a hierarchy of files and folders on disk. Each time a client requests the resource at a certain path, the web server tries to find a file at the corresponding path on disk, and responds with either the content of the file itself or (as in the case of a CGI script) the output created by executing the file. But in web applications, it can be artificially constraining to have to have a file on disk for every path that might be requested. For example, the data in your application might not be stored on disk, but in a relational database in another server. Or you might want to create resources on demand when they are requested. In cases like this, it's useful to be able to write your own logic for navigating a hierarchy of resources.

Writing your own logic for managing resources can also help you to manage security. Rather than opening up an entire directory to web access, you can selectively control which files are made available.

4.4.1. How Do I Do That?

The `twisted.web.resource`, `twisted.web.static`, and `twisted.web.server` modules provide classes for working with requests at a higher level than `twisted.web.http.Resource`, which you can use to set up a web server that combines several different kinds of resources into a logical hierarchy. [Example 4-4](#) uses these classes to build an application for testing hexadecimal color codes. Request the resource `/colors/hex`, where `hex` is a hexadecimal color code, and you'll get a page with the background color `#hex`. Rather than trying to generate a page for every possible color in advance, this server creates resources on demand.

Example 4-4. `resourcetree.py`

```
from twisted.web import resource, static, server

class ColorPage(resource.Resource):
```

```

def __init__(self, color):
    self.color = color

def render(self, request):
    return """
<html>
<head>
    <title>Color: %s</title>
    <link type='text/css' href='/styles.css' rel='Stylesheet' />
</head>
<body style='background-color: #%s'>
    <h1>This is #%s.</h1>
    <p style='background-color: white'>
        <a href='/color/'>Back</a>
    </p>
</body>
</html>
""" % (self.color, self.color, self.color)

```

```

class ColorRoot(resource.Resource):
    def __init__(self):
        resource.Resource.__init__(self)
        self.requestedColors = []
        self.putChild('/', ColorIndexPage(self.requestedColors))

    def render(self, request):
        # redirect /color -> /color/
        request.redirect(request.path + '/')
        return "Please use /colors/ instead."

    def getChild(self, path, request):
        if path not in self.requestedColors:
            self.requestedColors.append(path)

```

```

return ColorPage(path)

class ColorIndexPage(resource.Resource):
    def __init__(self, requestedColorsList):
        resource.Resource.__init__(self)
        self.requestedColors = requestedColorsList

    def render(self, request):
        request.write("""
<html>
<head>
    <title>Colors</title>
    <link type='text/css' href='/styles.css' rel='Stylesheet' />
</head>
<body>
<h1>Colors</h1>
To see a color, enter a url like
<a href='/color/ff0000'>/color/ff0000</a>. <br />
Colors viewed so far:
<ul>""")
        for color in self.requestedColors:
            request.write(
                "<li><a href='%s' style='color: #s'>%s</a></li>" % (
                    color, color, color))
        request.write("""
</ul>
</body>
</html>
""")
        return ""

class HomePage(resource.Resource):
    def render(self, request):
        return ""

```

```

<html>

<head>

  <title>Colors</title>

  <link type='text/css' href='/styles.css' rel='Stylesheet' />

</head>

<body>

<h1>Colors Demo</h1>

What's here:

<ul>

  <li><a href='/color'>Color viewer</a></li>

</ul>

</body>

</html>

"""

```

```

if __name__ == "__main__":
    from twisted.internet import reactor
    root = resource.Resource( )
    root.putChild('', HomePage( ))
    root.putChild('color', ColorRoot( ))
    root.putChild('styles.css', static.File('styles.css'))
    site = server.Site(root)
    reactor.listenTCP(8000, site)
    reactor.run( )

```

Example 4-4 requires one static file, a CSS stylesheet. Create a file in the same directory as *resourcetree.py* called *styles.css*, with the content shown in **Example 4-5**.

Example 4-5. styles.css

```

body {
    font-family: Georgia, Times, serif;
    font-size: 11pt;

```

```

}

h1 {
    margin: 10px 0;
    padding: 5px;
    background-color: black;
    color: white;
}

a {
    font-family: monospace;
}

p {
    padding: 10px;
}

```

Run *resourcetree.py* to start a web server on port 8000. Here's a complete list of resources that the server provides:

/	Home page
/css	Virtual resource for holding CSS stylesheets
/css/styles.css	The static file <i>styles.css</i>
/colors/	Index of colors people have viewed so far
/colors/hexcolor	A page with the background color #hexcolor


Try going to the URI <http://localhost:8000/colors/00abef>, and you'll see the page in [Figure 4-6](#) with the background color #00abef (which may not look like much printed in monochrome, but in real life is a bright shade of blue).

Figure 4-6. Viewing a hexadecimal color



Feel free to try other colors as well. You can also go to the page <http://localhost:8000/colors/>, shown in [Figure 4-7](#), to see a list of the colors you've viewed so far.

Figure 4-7. The `/colors/` page showing a list of viewed colors



4.4.2. How Does That Work?

[Example 4-4](#) introduces several new classes from the `twisted.web` package: `resource.Resource`, `static.File`, and `server.Site`. Each `resource.Resource` object does two things. First, it defines how requests for that resource should be handled. Second, it defines which `Resource` objects should be used for requests for child resources — resources whose path puts them below this resource in the hierarchy.

For example, take a look at the class `ColorRoot` in [Example 4-4](#). An instance of this class will later be inserted into the resource hierarchy at the path `/colors`. When initialized, `ColorRoot` uses the `putChild` method to insert a `ColorIndexPage` `Resource` as the child resource `' '`. What does that mean? It means that requests for `/colors/` (the path of `ColorRoot` plus a trailing slash) should be handled by the `ColorIndexPage` object.



You might think of them as being equivalent, but the URIs <http://example.com/stuff> and <http://example.com/stuff/> (note the trailing slash) are not the same. They are different URIs identifying different resources. Browsers will expand relative links differently depending on whether the trailing slash is part of the URI. In the first example, a link to "otherpage" will expand to <http://example.com/otherpage>; in the second example, it will expand to <http://example.com/stuff/otherpage>.

If you're not explicit in your server code, this problem can come back to bite you. It's a good idea to decide whether you want to have trailing slashes in your URIs, and redirect requests from one form to the other. The `Resource` class makes this easy to do. If you set the attribute `addSlash` to `true`, a `Resource` will automatically add a trailing slash to any requests that don't already have them and redirect those requests to the updated URI.

The `render` method defines what happens after a `Resource` has been found that matches the path of a request. `Resource.render` works basically the same way as the request handler methods in [Example 4-3](#): it takes a `Request` object as its only argument, and is responsible for handing the request and sending a response to the client. `Resource.render` has a few caveats that you'll need to keep in mind, however. First, it expects you to return a string. This is a useful shortcut in many cases: you can just return the data you want to send as the body of the response, and the `Resource` will send it to the client and end the response. But even when you choose to use `request.write` to write the response body yourself, `render` still expects you to return a string. You can return an empty string to make it happy without adding anything to the response.

At times, you might want to start a deferred operation inside a `render` method. In this case, you won't be ready to write the response until your `Deferred` calls back. You might wonder, "Can I just return a `Deferred` that calls back with a string?" Well, sadly, you can't. (This is one of many deficiencies in the `Resource` object; see the note at the end of this lab for a discussion of why you shouldn't use the classes discussed here for major web development projects.) Instead, you return the magic value `twisted.web.server.NOT_DONE_YET`, which tells the `Resource` that you've started something asynchronous and aren't done with this request yet, so it shouldn't call `request.finish()`. Then you can call `request.finish()` yourself later after you're done writing the response. (See [Example 4-5](#) for an example of this technique.)

The `ColorRoot` `Resource` will be used to render requests for the path `/colors`. In reality, though, `ColorRoot` is just a container for child resources. `ColorRoot.render` calls `request.redirect`, a helper function that sets the HTTP status code of the response to 302 ("Moved Temporarily") and writes a `Location:` header directing the client to request a page from another location, in this case `/colors/` (with a trailing slash). Note that even though it's told the client to go somewhere else, `render` still has to return a string.



`Resource` offers an alternative to the `render` method. You can write separate methods to handle different HTTP methods: `render_GET`, `render_POST`, and so on. This approach is discussed in detail in [Example 5-1](#) in [Chapter 5](#).

`ColorRoot` has one more method, `getChild`. Here the possibilities for doing interesting things with resource hierarchies start to expand. The `getChild` method is designed for dynamically managing child resources. A `Resource`'s `getChild` method is called when the client has sent a request for a path beneath the `Resource` in the hierarchy, and no matching path has been registered using `putChild`. By default, `getChild` will send a 404 ("Not Found") response. But you can override it, as `ColorRoot` does. `ColorRoot`'s `getChild` method takes the child path and uses it to initialize a `ColorPage` object. The

`ColorPage` can then respond to the request, using the last part of the path as a hexadecimal color code.

The `static.File` class is a subclass of `Resource` that serves the contents of a file or directory on disk. Initialize a `static.File` object with a filename as an argument. Using `static.File` is better than loading files from disk yourself because `static.File` is smart about handling large files: it won't take up too much memory, and it won't cause your entire server process to become unresponsive while it reads data from disk. If you initialize a `static.File` with the path of a directory, it will serve all the files and subdirectories under that directory.



Even if you're not using `server.Site` and a tree of `Resource` objects to manage your web server, you can still use a `static.File` object to handle a request. You can use a temporary `static.File` to push the contents of a file as the response to a request like this:

```
static.File('file.txt').render(request)
```

You can change the MIME type `static.File` uses when serving files by making changes to the `contentType` attribute. That attribute functions as a dictionary for the purpose of mapping file extensions (such as `.png`) to MIME types.

The `server.Site` class is a `Factory` that you initialize with a `Resource` object. It will handle HTTP requests by splitting the requested path into segments and then walking the tree of `Resource` objects to find the `Resource` that it should use to handle the request.

[< Day Day Up >](#)

4.5. Storing Web Data in an SQL Database

Lots of web applications use an SQL backend for data storage. With a Twisted application, though, you wouldn't want to use a regular Python SQL library. Standard SQL libraries have blocking function calls: every time you run a query, the query function will pause your application until the server returns a result. This can take a long time, especially if the query requires a lot of processing, or if the network connection to the server is slow. To use an SQL database with Twisted, you need a way to run queries using `Deferreds`, allowing your app to continue doing other things while it's waiting for the results.

Twisted provides such an SQL library in the `twisted.enterprise` package. `twisted.enterprise` doesn't actually include SQL drivers; it would be far too much work to support every database you might potentially want to use. Instead, `twisted.enterprise` provides an asynchronous API on top of the standard DB-API interface used by many Python database modules. When necessary, it uses threads to prevent database queries from blocking. You can use `twisted.enterprise` to work with any SQL database, as long as you have a DB-API compatible Python module for that database installed.

The Future of Twisted Web Development

The classes in `twisted.web.resource` and `twisted.web.server` are, as of this writing, widely considered to be past their prime. They have some serious shortcomings, especially their lack of support for `Deferred` results in `Resource.render` and `Resource.getChild`. Both are scheduled to be deprecated in the future in favor of improved classes provided by a next-generation web package known as `twisted.web2`. Unfortunately, `twisted.web2` is under such heavy development at this time that any examples included in this book would probably stop working soon after it went to press. While `twisted.web2` will have a different API, it will continue to use the concepts introduced here of a hierarchy of objects rendering requests.

Since `twisted.web.resource` and `twisted.web.server` will eventually be deprecated, you should avoid depending on them too heavily in your code. For a simple web server, you can take the approach in [Example 4-3](#) and use a subclass of `twisted.http.Request`. `twisted.web2` will also provide a backward-compatible interface for `Resource` objects, so you should be able to port code such as that in [Examples 4-5](#) and [4-6](#) with little to no effort.

If you're building a major web application with Twisted, you should use the Nevow (pronounced "nouveau") web server framework, which you can download from <http://www.nevow.com>. Nevow gives you more than just classes for working with HTTP requests: it provides many of the goodies you'd expect in a modern web application framework, including an XML templating system. It also includes some unique features like `livepage`, which gives you a way to send JavaScript code to the browser through a persistent connection. Nevow is designed from the ground up for Twisted, which means you can use `Deferreds` everywhere, and it's released under an extremely liberal open source license.

Like `twisted.web2`, Nevow hasn't yet reached the point where it has stable APIs that can be documented here. But it is mature enough that people are already using it for production web sites. You can find up-to-date documentation and examples at <http://www.nevow.com>.

4.5.1. How Do I Do That?

First, make sure you have a DB-API compatible Python module installed for your particular database. Then create a `twisted.enterprise.adbapi.ConnectionPool` object using your database driver and connection information. [Example 4-6](#) uses the `MySQLdb` module (which you can download from <http://sourceforge.net/projects/mysql-python>) to connect to a MySQL database. It runs a minimal weblog application that stores posts in a database table.

Example 4-6. databaseblog.py

```
from twisted.web import resource, static, server, http
from twisted.enterprise import adbapi, util as dbutil

DB_DRIVER = "MySQLdb"

DB_ARGS = {
    'db': 'test',
    'user': 'your_user_here',
    'passwd': 'your_pass_here',
}

class HomePage(resource.Resource):
    def __init__(self, dbConnection):
        self.db = dbConnection
        resource.Resource.__init__(self)

    def render(self, request):
        query = "select title, body from posts order by post_id desc"
        self.db.runQuery(query).addCallback(
            self._gotPosts, request).addErrback(
            self._dbError, request)
        return server.NOT_DONE_YET
```

```

def _gotPosts(self, results, request):
    request.write("""
    <html>
    <head><title>MicroBlog</title></head>
    <body>
        <h1>MicroBlog</h1>
        <i>Like a blog, but less useful</i>
        <p><a href='/new'>New Post</a></p>
    """)

    for title, body in results:
        request.write("<h2>%s</h2>" % title)
        request.write(body)

    request.write("""
    </body>
    </html>
    """)
    request.finish( )

def _dbError(self, failure, request):
    request.setResponseCode(http.INTERNAL_SERVER_ERROR)
    request.write("Error fetching posts: %s" % failure.getErrorMessage( ))
    request.finish( )

class NewPage(resource.Resource):
    def render(self, request):
        return """
        <html>
        <head><title>New Post</title></head>
        <body>
            <h1>New Post</h1>
            <form action='save' method='post'>
            Title: <input type='text' name='title' /> <br />

```

```

    Body: <br />
    <textarea cols='70' name='body'></textarea> <br />
    <input type='submit' value='Save' />
    </form>
</body>
</html>
"""

```

```

class SavePage(resource.Resource):

    def __init__(self, dbConnection):
        self.db = dbConnection
        resource.Resource.__init__(self)

    def render(self, request):
        title = request.args['title'][0]
        body = request.args['body'][0]
        query = """
        Insert into posts (title, body) values (%s, %s)
        """ % (dbutil.quote(title, "char"),
              dbutil.quote(body, "text"))
        self.db.runQuery(query).addCallback(
            self._saved, request).addErrback(
            self._saveFailed, request)
        return server.NOT_DONE_YET

    def _saved(self, result, request):
        request.redirect("/")
        request.finish( )

    def _saveFailed(self, failure, request):
        request.setResponseCode(http.INTERNAL_SERVER_ERROR)
        request.write("Error saving record: %s" % (
            failure.getErrorMessage( )))

```

```

        request.finish( )

class RootResource(resource.Resource):
    def __init__(self, dbConnection):
        resource.Resource.__init__(self)
        self.putChild('/', HomePage(dbConnection))
        self.putChild('new', NewPage( ))
        self.putChild('save', SavePage(dbConnection))

if __name__ == "__main__":
    from twisted.internet import reactor
    dbConnection = adbapi.ConnectionPool(DB_DRIVER, **DB_ARGS)
    f = server.Site(RootResource(dbConnection))
    reactor.listenTCP(8000, f)
    reactor.run( )

```

[Example 4-6](#)'s code uses a simple SQL table called `posts`. You can create it by running the following SQL statement in a MySQL database:

```

CREATE TABLE posts (
    post_id int NOT NULL auto_increment,
    title varchar(255) NOT NULL,
    body text,
    PRIMARY KEY (post_id)
)

```

Then run `databaseblog.py` to start the server on port 8000. You should be able to view the home page in your browser. If you get this far without any errors, the database connection is working correctly. Try clicking the New Post link and composing a blog entry, as shown in [Figure 4-8](#).

Figure 4-8. Composing a weblog post



Submit the form, and you'll be taken back to the main page. You should see your post, which is now saved in the database. See [Figure 4-9](#).

4.5.2. How Does That Work?

[Example 4-6](#) uses three Resource classes: `HomePage`, `NewPage`, and `SavePage`. `HomePage` connects to the database and displays the current posts in reverse order. `NewPage` provides a form for entering new posts. `SavePage` processes the form and inserts a new record in the database.

Figure 4-9. Displaying a post from the database



First, the `databaseblog.py` script creates a `twisted.enterprise.adbapi.ConnectionPool` object. A `ConnectionPool` represents a managed group of one or more database connections that you can use to send queries to an SQL database. Initialize a `ConnectionPool` with the name of the database driver module as the first argument. Any additional arguments or keyword arguments will be passed along to the driver when it is initialized.

After the `ConnectionPool` object in [Example 4-6](#) is created, it gets passed to the `HomePage` and `SavePage` classes so that they can run database queries. In order to run these queries, `HomePage` and `SavePage` have to process requests asynchronously. They start by using the `ConnectionPool.runQuery` method to run a database query. This returns a `Deferred`. [Example 4-6](#) shows how to set up callback and errback handlers for the `Deferred` so that a response is sent to the client once each query is complete. In each case, the `render` method returns the special value `server.NOT_DONE_YET` to indicate that the response is being processed asynchronously.

[< Day Day Up >](#)

4.6. Running an HTTP Proxy Server

Besides HTTP servers and clients, `twisted.web` includes support for writing HTTP proxies. A proxy is a client and server in one: it accepts requests from clients (acting as a server) and forwards them to servers (acting as a client). Then it sends the response back to the client who originally sent the request. HTTP proxies are useful mostly for the additional services they can provide, such as caching, filtering, and usage reporting. This lab shows how to build an HTTP proxy using Twisted.

4.6.1. How Do I Do That?

The `twisted.web` package includes `twisted.web.proxy`, a module with classes for building HTTP proxies. [Example 4-7](#) shows how easy it is to set up a basic proxy.

Example 4-7. `simpleproxy.py`

```
from twisted.web import proxy, http
from twisted.internet import reactor
from twisted.python import log
import sys
log.startLogging(sys.stdout)

class ProxyFactory(http.HTTPFactory):
    protocol = proxy.Proxy

reactor.listenTCP(8001, ProxyFactory())
reactor.run()
```

Run `simpleproxy.py` from the command line and you'll have an HTTP proxy running on [localhost](#) port 8001. Set up a web browser to use this proxy and try surfing some web pages. The call to `log.startLogging` prints all HTTP log messages to stdout so you can watch the proxy at work:

```
$ python simpleproxy.py
```

```

2005/06/13 00:22 EDT [-] Log opened.

2005/06/13 00:22 EDT [-] _ _main_ _.ProxyFactory starting on 8001

2005/06/13 00:22 EDT [-] Starting factory <_ _main_ _.ProxyFactory instance
at 0xb7d9d10c>

2005/06/13 00:23 EDT [Proxy,0,127.0.0.1] Starting factory <twisted.web.proxy.
ProxyClientFactory instance at 0xb78a99ac>

2005/06/13 00:23 EDT [-] Enabling Multithreading.

2005/06/13 00:23 EDT [Proxy,1,127.0.0.1] Starting factory <twisted.web.proxy.
ProxyClientFactory instance at 0xb781ee8c>

2005/06/13 00:23 EDT [Proxy,2,127.0.0.1] Starting factory <twisted.web.proxy.
ProxyClientFactory instance at 0xb782534c>

...

```

That gives you a working proxy, but not one that does anything useful. [Example 4-8](#) dives deeper into the `twisted.web.proxy` module to build a proxy that keeps track of the most frequently used words in the HTML documents being browsed.

Example 4-8. wordcountproxy.py

```

import sgmllib, re

from twisted.web import proxy, http

import sys

from twisted.python import log

log.startLogging(sys.stdout)

WEB_PORT = 8000

PROXY_PORT = 8001

class WordParser(sgmllib.SGMLParser):

    def __init__(self):

        sgmllib.SGMLParser.__init__(self)

        self.chardata = []

        self.inBody = False

```

```

def start_body(self, attrs):
    self.inBody = True

def end_body(self):
    self.inBody = False

def handle_data(self, data):
    if self.inBody:
        self.chardata.append(data)

def getWords(self):
    # extract words
    wordFinder = re.compile(r'\w*')
    words = wordFinder.findall("".join(self.chardata))
    words = filter(lambda word: word.strip(), words)
    print "WORDS ARE", words
    return words

class WordCounter(object):
    ignoredWords = "the a of in from to this that and or but is was be can could i you
they we at".split()

    def __init__(self):
        self.words = {}

    def addWords(self, words):
        for word in words:
            word = word.lower()
            if not word in self.ignoredWords:
                currentCount = self.words.get(word, 0)
                self.words[word] = currentCount + 1

class WordCountProxyClient(proxy.ProxyClient):
    def handleHeader(self, key, value):

```

```

proxy.ProxyClient.handleHeader(self, key, value)
if key.lower( ) == "content-type":
    if value.split(';')[0] == 'text/html':
        self.parser = WordParser( )

```

```

def handleResponsePart(self, data):
    proxy.ProxyClient.handleResponsePart(self, data)
    if hasattr(self, 'parser'): self.parser.feed(data)

```

```

def handleResponseEnd(self):
    proxy.ProxyClient.handleResponseEnd(self)
    if hasattr(self, 'parser'):
        self.parser.close( )
        self.father.wordCounter.addWords(self.parser.getWords( ))
        del(self.parser)

```

```

class WordCountProxyClientFactory(proxy.ProxyClientFactory):
    def buildProtocol(self, addr):
        client = proxy.ProxyClientFactory.buildProtocol(self, addr)
        # upgrade proxy.proxyClient object to WordCountProxyClient
        client.__class__ = WordCountProxyClient
        return client

```

```

class WordCountProxyRequest(proxy.ProxyRequest):
    protocols = {'http': WordCountProxyClientFactory}

    def __init__(self, wordCounter, *args):
        self.wordCounter = wordCounter
        proxy.ProxyRequest.__init__(self, *args)

```

```

class WordCountProxy(proxy.Proxy):

```

```

def __init__(self, wordCounter):
    self.wordCounter = wordCounter
    proxy.Proxy.__init__(self)

def requestFactory(self, *args):
    return WordCountProxyRequest(self.wordCounter, *args)

class WordCountProxyFactory(http.HTTPFactory):
    def __init__(self, wordCounter):
        self.wordCounter = wordCounter
        http.HTTPFactory.__init__(self)

    def buildProtocol(self, addr):
        protocol = WordCountProxy(self.wordCounter)
        return protocol

# classes for web reporting interface
class WebReportRequest(http.Request):
    def __init__(self, wordCounter, *args):
        self.wordCounter = wordCounter
        http.Request.__init__(self, *args)

    def process(self):
        self.setHeader("Content-Type", "text/html")
        words = self.wordCounter.words.items()
        words.sort(lambda (w1, c1), (w2, c2): cmp(c2, c1))
        for word, count in words:
            self.write("<li>%s %s</li>" % (word, count))
        self.finish()

class WebReportChannel(http.HTTPChannel):
    def __init__(self, wordCounter):
        self.wordCounter = wordCounter
        http.HTTPChannel.__init__(self)

```

```

def requestFactory(self, *args):
    return WebReportRequest(self.wordCounter, *args)

class WebReportFactory(http.HTTPFactory):
    def __init__(self, wordCounter):
        self.wordCounter = wordCounter
        http.HTTPFactory.__init__(self)


    def buildProtocol(self, addr):
        return WebReportChannel(self.wordCounter)

if __name__ == "__main__":
    from twisted.internet import reactor
    counter = WordCounter()
    prox = WordCountProxyFactory(counter)
    reactor.listenTCP(PROXY_PORT, prox)
    reactor.listenTCP(WEB_PORT, WebReportFactory(counter))
    reactor.run()

```

Run `wordcountproxy.py` and set your browser to use the proxy server localhost port 8001. Browse to a couple of sites to test the proxy. Then go to <http://localhost:8000/> to see a report of word frequency in the sites you've visited. [Figure 4-10](#) shows what your browser might look like after visiting <http://www.twistedmatrix.com>.

Figure 4-10. List of the most common words in proxied web pages



4.6.2. How Does That Work?

There are a lot of classes in [Example 4-8](#), but the majority of them are just glue. Only a few are doing real work. The first two classes, `WordParser` and `WordCounter`, do the work of extracting words from the text of HTML documents and counting their frequency. The third class, `WordCountProxy` client, contains the code that looks for HTML documents and runs them through a `WordParser` as it comes back from the server. That's it for code specific to the problem of counting words.

Because a proxy acts as both a client and server, it uses a lot of classes. There's a `ProxyClientFactory` and `ProxyClient`, which provide the `Factory/Protocol` pair for client connections to other servers. To accept connections from clients, the proxy module provides the class `ProxyRequest`, a subclass of `http.Request`, and `Proxy`, a subclass of `http.HTTPChannel`. These are used the same way as they would be in a regular HTTP server: an `HTTPFactory` uses `Proxy` for its `Protocol`, and the `Proxy` `HTTPChannel` uses `ProxyRequest` as its `RequestFactory`. Here's the sequence of events when a client sends a request for a web page:

1. The client establishes a connection to the proxy server. This connection is handled by the `HTTPFactory`.
2. The `HTTPFactory.buildProtocol` creates a `Proxy` object to send and receive data over the client connection.
3. When the client sends a request over the connection, the `Proxy` creates a `ProxyRequest` to handle it.
4. The `ProxyRequest` looks at the request to see what server the client is trying to connect to. It creates a `ProxyClientFactory` and calls `reactor.connectTCP` to connect the factory to the server.
5. Once the `ProxyClientFactory` is connected to the server, it creates a `ProxyClient` `Protocol` object to send and receive data over the connection.
6. `ProxyClient` sends the original request to the server. As it receives the reply, it sends it back to the client that sent the request. This is done by calling `self.father.transport.write:` `self.father` is the `Proxy` object that is managing the client's connection.

With such a long chain of classes, it becomes a lot of work to pass an object from one end of the chain to the other. But it is possible, as [Example 4-8](#) demonstrates. By creating a subclass of each class provided by the `proxy` module, you can have complete control over every step of the process.

At only one step in [Example 4-8](#) is it necessary to resort to a bit of a hack. The `ProxyClientFactory` class has a `buildProtocol` method that's hardcoded to use `ProxyClient` as the protocol. It doesn't give you any easy way to substitute your own subclass of `ProxyClient` instead. The solution is to use the special Python `__class__` attribute to do an in-place upgrade of the `ProxyClient` object returned by `ProxyClientFactory.buildProtocol`, which changes the object from a `ProxyClient` to a `WordCountProxyClient`.

In addition to the proxy server, [Example 4-8](#) runs a regular web server on port 8000, which displays the current word count data from the proxy server. The ability to include a lightweight embedded HTTP server in your application is extremely handy, and can be used in any Twisted application where you want to provide a way to view status information remotely.

< Day Day Up >

Chapter 5. Web Services and RPC

When you write a networked application, you make information or services accessible over a computer network. Sometimes this is done with the goal of letting people use your program remotely. But more often it's done to enable other applications to communicate with yours. Providing a way for other programs to communicate with your application makes it more flexible and more valuable. It allows other developers to use your application's data and services in new ways—possibly even to write new features that you might not have the time or expertise to write yourself.

The concept of one program calling a function in another program over a network is called RPC, or Remote Procedure Calls. RPC can be done in any number of ways, but these days the most common way is to make functions available through the Web. Programmatic interfaces that are available on the Web, meant for use by other applications instead of by a user with a web browser, are known as web services .

This chapter shows how to use web services and RPC in your applications. It demonstrates how to make services available across the network, and how to write client applications that use these services. It discusses four different ways to do this using Twisted: REST, XML-RPC, SOAP, and Twisted's own Perspective Broker.

5.1. Using the REST Architecture for Web Services

In 2000, Roy Thomas Fielding published the paper "Architectural Styles and the Design of Network-based Software Architectures" (<http://www.ics.uci.edu/~fielding/pubs/dissertation/top.htm>). This paper described a software architecture style called REST (short for "Representational State Transfer") and explained how this architecture could be seen in the design of the Web. REST isn't tied to any particular technology or data formats. Instead, it offers a set of principles for designing web applications that take advantage of the fundamental design of the Web.

Applications that use the REST architectural style use the Web the way it was designed to be used. Instead of struggling to overcome the limitations of the Web, REST embraces those constraints to give developers an elegant, powerful approach to designing and thinking about web applications.

5.1.1. How Do I Do That?

Design your web application in terms of resources. Every URI on the Web identifies a resource. A resource may be any information or service, including a document, an image, or a web service that takes input data and performs some action. What information and services is your application going to provide? Each should be available through the Web at a logical URI. HTTP defines four actions that can be taken on resources: GET, POST, PUT, and DELETE. Web browsers generally support only two of these: GET, for retrieving the representation of a resource, and POST, for submitting data to a service for processing. But when designing services meant for use by non-browser clients you can take advantage of PUT and DELETE as well.

[Example 5-1](#) shows how you can use the REST architecture to design a web application that's usable through both a web browser and web services. In this case, the application is a Wiki, a simple set of user-editable linked web pages.

Example 5-1. wiki.py

```
import re, pickle, os

from twisted.web import server, resource, http

reWikiWord = re.compile(r"\b(([A-Z][a-z]+){2,})\b")

class WikiData(object):

    "class for managing Wiki data"

    def __init__(self, filename):
```

```

self.filename = filename

if os.path.exists(filename):
    self.pages = pickle.load(file(filename, 'r+b'))
else:
    self.pages = {'WikiHome': 'This is your Wiki home page.'}

def save(self):
    pickle.dump(self.pages, file(self.filename, 'w+b'))

def hasPage(self, path):
    return self.pages.has_key(path)

def listPages(self):
    return self.pages.keys( )

def getPage(self, path):
    return self.pages.get(path, '')

def getRenderedPage(self, path):
    pageData = self.getPage(path)

    "get content with linked WikiWords"
    wikiWords = [match[0] for match in reWikiWord.findall(pageData)]
    for word in wikiWords:
        pageData = pageData.replace(
            word, "<a href='%s'>%s</a>" % (word, word))
    return pageData

def setPage(self, path, content):
    self.pages[path] = content
    self.save( )

def deletePage(self, path):
    del(self.pages[path])

```

```

class RootResource(resource.Resource):
    def __init__(self, wikiData):
        self.wikiData = wikiData
        resource.Resource.__init__(self)
        self.putChild('edit', EditFactory(self.wikiData))
        self.putChild('save', SavePage(self.wikiData))
        self.putChild('index', IndexPage(self.wikiData))

    def getChild(self, path, request):
        return WikiPage(self.wikiData, path or 'WikiHome')

```

```

class EditFactory(resource.Resource):
    def __init__(self, wikiData):
        self.wikiData = wikiData
        resource.Resource.__init__(self)

    def getChild(self, path, request):
        return EditPage(self.wikiData, path)

```

```

class EditPage(resource.Resource):
    def __init__(self, wikiData, path):
        self.wikiData = wikiData
        self.path = path
        resource.Resource.__init__(self)

    def render(self, request):
        return """
<html>
<head><title>Editing: %(path)s</title></head>
<body>
Editing: %(path)s
<form method='post' action='/save'>
<input type='hidden' name='path' value='%(path)s'>

```

```

<textarea name='data' rows='30' cols='80'>%(data)s</textarea>

<br />

<input type='submit' value='Save'>

</form>

</body>

</html>

""" % {'path':self.path,
      'data':self.wikiData.getPage(self.path)}

```

```

class SavePage(resource.Resource):

    def __init__(self, wikiData):
        self.wikiData = wikiData
        resource.Resource.__init__(self)

    def render_POST(self, request):
        data = request.args['data'][0]
        path = request.args['path'][0]
        self.wikiData.setPage(path, data)
        request.redirect('/') + path
        return ""

    def render_GET(self, request):
        return """
        To add a page to the Wiki, send data to this page using
        HTTP POST. Arguments:
        <ul>
        <li><code>path</code>: the name of a Wiki page</li>
        <li><code>data</code>: the content to use for that page</li>
        </ul>
        """

class WikiPage(resource.Resource):

    def __init__(self, wikiData, path):
        self.wikiData = wikiData

```

```

self.path = path

resource.Resource.__init__(self)

def render_GET(self, request):

    if self.wikiData.hasPage(self.path):

        return """

        <html>

        <head><title>%s</title></head>

        <body>

        <p>

        <a href='/edit/%s'>Edit Page</a>

        <a href='/index'>Index</a>

        <a href='/'>Home</a>

        </p>

        %s

        </body>

        </html>

        """ % (self.path, self.path,

                self.wikiData.getRenderedPage(self.path))

    else:

        request.redirect('/edit/%s' % self.path)

        return ""

def render_PUT(self, request):

    "accept a PUT request to set the contents of this page"

    if not self.wikiData.hasPage(self.path):

        request.setResponseCode(http.CREATED, "Created new page")

    else:

        request.setResponseCode(http.OK, "Modified existing page")

    request.content.seek(0)

    self.wikiData.setPage(self.path, request.content.read( ))

    return ""

```

```

def render_DELETE(self, request):
    "accept a DELETE request to remove this page"
    if self.wikiData.hasPage(self.path):
        self.wikiData.deletePage(self.path)
        return "Deleted."
    else:
        request.setResponseCode(http.NOT_FOUND)
        return "No such page."

class IndexPage(resource.Resource):
    def __init__(self, wikiData):
        self.wikiData = wikiData
        resource.Resource.__init__(self)

    def render(self, request):
        pages = self.wikiData.listPages( )
        pages.sort( )
        links = ["<li><a href='%s'%>s</a></li>" % (p, p)
                for p in pages]
        return """
<html>
<head><title>Wiki Index</title></head>
<a href='/'>Home</a>
<h1>Index</h1>
<body>
<ul>
%s
</ul>
</body>
""" % "".join(links)

if __name__ == "__main__":
    import sys
    from twisted.internet import reactor

```

```
wikiData = WikiData(sys.argv[1])

reactor.listenTCP(8082, server.Site(RootResource(wikiData)))

reactor.run( )
```

Run *wiki.py* with a single argument, the name of a file to use for data storage:

```
$ python wiki.py wiki.dat
```

The script starts up a web server on port 8082. Go to <http://localhost:8082/>, and you'll be able to view and edit pages in the Wiki. WikiWords will automatically be converted into links. [Figure 5-1](#) shows the default Wiki home page. [Figure 5-2](#) shows the Edit Page form.

Figure 5-1. Browsing the Wiki






Figure 5-2. Editing a Wiki page



You're not limited to using a web browser to update the Wiki, however. For example, you can use command-line tools like *wget* or *curl* to create pages by posting data to the resource */save* at <http://localhost:8082/save>:

```
$ wget -q --post-data="path=WgetTest&data=Hello%20from%20wget" \
--output-document=- http://localhost:8082/save

$ curl -d "path=CurlTest&data=Hello%20from%20curl" \
http://localhost:8082/save
```



5.1.2. How Does That Work?

The *wiki.py* application in [Example 5-1](#) uses a class called `WikiData` to manage a dictionary of Wiki pages. Then it defines a series of resources, makes them available through a `twisted.web.server.Server`, and starts the server on port 8082. All the resource classes inherit from `twisted.web.resource.Resource` (for the basics on the `resource.Resource` class, see [Chapter 4](#)).

The `WikiPage` class represents a single page in the Wiki. In keeping with the REST architectural style, the class provides a two-way mechanism for transferring a representation of the page. When a client sends a GET request, `WikiPage` will return a rendered HTML version of the page, suitable for viewing in the browser. To update the page, a client can send an HTTP PUT request containing the new version of the page. PUT is an oft-neglected part of HTTP that allows a client to send the server data that should be used to create or replace the resource at a given URI. `WikiPage` also supports the HTTP DELETE method, which will completely remove the page. The separate functions `render_GET`, `render_PUT`, and `render_DELETE` take advantage of a built-in feature of the `resource.Resource` class: if these methods are defined separately, then `resource.Resource` will use a method matching the HTTP method used in the incoming request (and return an HTTP 405 "Method not Allowed" response if none is defined).

Unfortunately, most modern browsers don't provide a nice way to use PUT, so the server needs to offer an alternative means to create and update pages. The `PageSaverResource` class accepts a POST request with two arguments: the path of a page, and the page data. It will set the contents of the page at the given path, and then redirect the client so he can view it. `PageSaverResource` is purely a service, meant to accept input in the form of a POST request. Still, it responds to a GET request with the closest thing to a representation of itself: documentation describing how the service should be used.

The `EditPage` class generates an HTML form for posting to the `PageSaverResource`. `EditPage` objects are dynamically created in the `getChild` method of `EditPageFactory`, so you can get an edit form for any page by requesting the resource `/edit/PageName`. In traditional script-based web programming, this same thing might have been done using a URI with an appended query, something like

`edit.php?path=PageName`. Twisted's web server gives you more control, so you can design a URI that looks nicer and isn't so closely tied to the underlying technology.

For convenience, `WikiPage` will respond to a request for a page that doesn't exist by returning a 302 response that redirects the client to the URI of the corresponding `EditPage`. This response makes it possible to link to pages in the Wiki whether or not they currently exist; if they don't, the server will do the right thing and prompt the client to create the page.

A final class, `IndexPage`, renders an HTML list of all the pages in the Wiki. Working together, these classes make up a web application that follows the principles of REST. It invites the client to view the application as a set of resources whose state can be retrieved or set through HTTP requests. These resources provide an HTML interface that can be used by a web browser, but they simultaneously define an API for web services. The next example shows how you can write a Twisted client to work with these resources.

[< Day Day Up >](#)

5.2. Using a Web Client to Update Resources Through REST

The Web itself is an example of REST architecture. You can look at any web site as a set of resources whose state can be retrieved and updated using HTTP methods like `GET` and `POST`. Thus a web application doesn't have to support special web service protocols like XML-RPC or SOAP for you to be able to work with it from a client program: straight HTTP is all you need.

5.2.1. How Do I Do That?

Use the `twisted.web.client.getPage` function to send HTTP requests to web resources. Despite its name, `getPage` supports HTTP methods beyond `GET`, as demonstrated in [Example 5-2](#).

Example 5-2. `rest_client.py`

```
from twisted.web import client
import urllib

class RestResource(object):
    def __init__(self, uri):
        self.uri = uri

    def get(self):
        return self._sendRequest('GET')

    def post(self, **kwargs):
        postData = urllib.urlencode(kwargs)
        mimeType = 'application/x-www-form-urlencoded'
        return self._sendRequest('POST', postData, mimeType)

    def put(self, data, mimeType):
        return self._sendRequest('PUT', data, mimeType)

    def delete(self):
        return self._sendRequest('DELETE')
```

```

def _sendRequest(self, method, data="", mimeType=None):
    headers = {}
    if mimeType:
        headers['Content-Type'] = mimeType
    if data:
        headers['Content-Length'] = str(len(data))
    return client.getPage(
        self.uri, method=method, postdata=data, headers=headers)

```

```

class RestWikiTester(object):
    def __init__(self, baseUri):
        self.baseUri = baseUri

    def test(self):
        return self.createPage("RestTestTmp").addCallback(
            lambda _: self.deletePage("RestTestTmp")).addCallback(
            lambda _: self.createPage("RestTest")).addCallback(
            lambda _: self.getPage("RestTest")).addErrback(
            self.handleFailure)

    def createPage(self, page):
        print "Creating page %s..." % page
        return RestResource(self.baseUri + page).put(
            "Created using HttpPut!", "text/html")

    def deletePage(self, page):
        print "Deleting page %s..." % page
        return RestResource(self.baseUri + page).delete( )

    def getPage(self, page):
        uri = self.baseUri + page
        return RestResource(uri).get( ).addCallback(

```

```

        self._gotPage, uri)

def _gotPage(self, pageData, uri):
    print "Got representation of %s:" % uri
    print pageData

def handleFailure(self, failure):
    print "Error:", failure.getErrorMessage( )

if __name__ == "__main__":
    from twisted.internet import reactor
    tester = RestWikiTester('http://localhost:8082/')
    tester.test( ).addCallback(lambda _: reactor.stop( ))
    reactor.run( )

```

When you run *rest_client.py*, it creates and deletes a page called *RestTestTmp*, creates a page called *RestTest*, and then displays the contents of *RestTest* as rendered by the server:

```

$ python rest_client.py
Creating page RestTestTmp...
Deleting page RestTestTmp...
Creating page RestTest...
Got representation of http://localhost:8082/RestTest:

    <html>
    <head><title>RestTest</title></head>
    <body>
    <p>
    <a href='/edit/RestTest'>Edit Page</a>
    <a href='/index'>Index</a>
    <a href='/'>Home</a>
    </p>
    Created using <a href='HttpPut'>HttpPut</a>!

```

```
</body>
```

```
</html>
```

5.2.2. How Does That Work?

The `RestResource` class takes a URI and provides methods for sending HTTP GET, PUT, POST, and DELETE requests to that resource. All of these use `twisted.web.client.getPage` to send the request. The `post` method will take an arbitrary number of keyword arguments, URL-encode them, and use the resulting string as the body of the request sent to the server. The `put` method will take arbitrary data representing the new state of the resource, along with a MIME type identifying the data format. The other methods, `get` and `delete`, don't need to pass any additional information.

The `RestWikiTester` class has a `test` method that chains together a series of tests to be run on the server. While not a comprehensive test, it demonstrates the use of the GET, PUT, and DELETE methods on the Wiki application from [Example 5-1](#).

< Day Day Up >

5.3. Enabling Web Services Using XML-RPC

XML-RPC is a system for making function calls through HTTP using XML message formats. XML-RPC is very different from the REST style of architecture; while both can be elegant solutions in the right hands, they have almost opposite design principles. Where REST invites you to think about the nature of the web and design your application accordingly, XML-RPC tries to make web services fit into the way most developers already think about programming: you call functions and get back results.

In XML-RPC, a function call is encoded as XML and sent to the server using an HTTP `POST` request. The server then replies with an XML document containing the result of the function call. Here's an example XML-RPC request, calling the function `echo` with the string argument `'cheese'`:

```
POST /RPC2 HTTP/1.0

Host: localhost

Content-Type: text/xml

Content-length: 190

<?xml version="1.0"?>
<methodCall>
  <methodName>echo</methodName>
  <params>
    <param>
      <value>
        <string>cheese</string>
      </value>
    </param>
  </params>
</methodCall>
```

And here's the response sent back from the server:

```
HTTP/1.1 200 OK

Connection: close
```

Content-Length: 158

Content-Type: text/xml

Date: Mon, 6 Jun 2005 12:55:00 GMT

```
<?xml version="1.0"?>
<methodResponse>
  <params>
    <param>
      <value>
        <string>You said: cheese</string>
      </value>
    </param>
  </params>
</methodResponse>
```

The XML format is simple and uses a limited set of common data types. For more information on XML-RPC, see the book *Programming Web Services with XML-RPC*, by Simon St.Laurent, Joe Johnston, and Edd Dumbill (O'Reilly).

XML-RPC has the advantage of being extremely easy to learn and use. Its limited set of supported data types makes it easy to implement, so you can find XML-RPC modules for almost any programming language. The `twisted.web` package supports XML-RPC out of the box, making it very easy to support XML-RPC web services in your application.

5.3.1. How Do I Do That?

The `twisted.web.xmlrpc.XMLRPC` class is a subclass of `twisted.web.resource.Resource` that does just about all the work of handling XML-RPC. All you have to do is define methods beginning with `xmlrpc_`, and it will make them available as XML-RPC functions. The script in [Example 5-3](#) imports the `wiki.py` Wiki server from [Example 5-1](#) and adds an XML-RPC interface.

Example 5-3. `xmlrpc_server.py`

```
import wiki

from twisted.web import server, xmlrpc

class WikiXmlRpc(xmlrpc.XMLRPC):
```

```

def __init__(self, wikiData):
    self.wikiData = wikiData

def xmlrpc_hasPage(self, path):
    return self.wikiData.hasPage(path)

def xmlrpc_listPages(self):
    return self.wikiData.listPages( )

def xmlrpc_getPage(self, path):
    return self.wikiData.getPage(path)

def xmlrpc_getRenderedPage(self, path):
    return self.wikiData.getRenderedPage(path)

def xmlrpc_setPage(self, path, data):
    self.wikiData.setPage(path, data)
    # wikiData.setPage returns None, which has no xmlrpc
    # representation, so you have to return something else
    return path

if __name__ == "__main__":
    import sys
    from twisted.internet import reactor
    datafile = sys.argv[1]
    wikiData = wiki.WikiData(datafile)
    siteRoot = rest_wiki.RootResource(wikiData)
    siteRoot.putChild('RPC2', WikiXmlRpc(wikiData))
    reactor.listenTCP(8082, server.Site(siteRoot))
    reactor.run( )

```

Run *xmlrpc_server.py* with a single argument, the name of your Wiki data file:

```
python xmlrpc_server.py
```

This command runs a web server on port 8082 that works just like *wiki.py* from [Example 5-1](#), but with the addition of a resource providing XML-RPC access at */RPC2* (which is somewhat of a standard location for XML-RPC services).

You can test the XML-RPC interface using the `xmlrpclib` module in the Python standard library:

```
$ python
Python 2.4.1 (#2, Apr 14 2005, 09:13:52)
[GCC 4.0.0 20050413 (prerelease) (Debian 4.0-0pre11)] on linux2
Type "help", "copyright", "credits" or "license" for more information.
>>> import xmlrpclib
>>> wiki = xmlrpclib.ServerProxy('http://localhost:8082/RPC2')
>>> wiki.listPages( )
['WikiHome', 'CurlTest', 'WgetTest', 'RestTest']
>>> wiki.setPage('PythonXmlRpcTest', 'Creating this through XmlRpc!')
'PythonXmlRpcTest'
>>> wiki.getRenderedPage('PythonXmlRpcTest')
"Creating this through <a href='XmlRpc'>XmlRpc</a>!"
>>> wiki.listPages( )
['WikiHome', 'CurlTest', 'WgetTest', 'PythonXmlRpcTest', 'RestTest']
```

5.3.2. How Does That Work?

The `xmlrpc.XMLRPC` class is a `Resource` designed to handle XML-RPC requests. When it receives a POST request, it parses the incoming XML to extract the name of the function being called and the arguments. Then it looks for a matching method with an `xmlrpc_` prefix and calls it with the arguments provided by the client. This function can return a `Deferred` result or a direct value. The `XMLRPC` class encodes the result as XML and returns it to the client.

XML-RPC has a limited set of data types. You can return strings, integers, floating-point numbers, Booleans, dictionaries, tuples, or lists, and they will be converted automatically to their XML-RPC representations. To send a date value, wrap a date tuple such as the result of `time.localtime()` in an `xmlrpc.DateTime` object. To send binary data, wrap a binary string in an `xmlrpc.Binary` object. Other data types, including `None`, have no equivalent in XML-RPC. Attempting to return an unsupported

data type will result in an error, so make sure that you limit your return values to the supported types.

[< Day Day Up >](#)

5.4. Calling XML-RPC Functions

The `twisted.web.xmlrpc` module includes client support for sending XML-RPC method calls to a server. Unlike the `xmlrpclib` module in the Python standard library, Twisted's XML-RPC client doesn't try to hide the fact that you're making a function call over the network (for one thing, method calls return a `Deferred`, so that your program can do other things while it's waiting for a response from the server). But it's still very easy to use.

5.4.1. How Do I Do That?

Create a `twisted.web.xmlrpc.Proxy` object pointing to the URI of your XML-RPC service. Use the `callRemote` method to call XML-RPC functions. [Example 5-4](#) demonstrates a client that uses the XML-RPC services from [Example 5-3](#).

Example 5-4. `xmlrpc_client.py`

```
from twisted.web import xmlrpc
from twisted.internet import reactor

class WikiTester(object):
    def __init__(self):
        self.wiki = xmlrpc.Proxy('http://localhost:8082/RPC2')

    def runTests(self):
        self.listPages().addCallback(
            lambda _:self.createTestPage()).addCallback(
            lambda _: self.getTestPage()).addErrback(
            self._catchFailure).addCallback(
            lambda _: reactor.stop())

    def listPages(self):
        print "Getting page list..."
        return self.wiki.callRemote('listPages').addCallback(
            self._gotList)

    def _gotList(self, pages):
```

```

    print "Got page list:", pages

def createTestPage(self):
    print "Creating test page XmlRpcTest..."
    pageData = "This is a test of XmlRpc"
    return self.wiki.callRemote('setPage', 'XmlRpcTest', pageData)

def getTestPage(self):
    print "Getting test page content..."
    return self.wiki.callRemote(
        'getRenderedPage', 'XmlRpcTest').addCallback(
            self._gotTestPage)

def _gotTestPage(self, content):
    print "Got page content:"
    print content
    return self.listPages( )

def _catchFailure(self, failure):
    print "Error:", failure.getErrorMessage( )

w = WikiTester( )
w.runTests( )
reactor.run( )

```

Run *xmlrpc_client.py*, and it will run a few commands over XML-RPC:

```

$ python xmlrpc_client.py
Getting page list...
Got page list: ['WikiHome', 'CurlTest', 'WgetTest', 'RestTest', 'PythonXmlRpcTest']
Creating test page XmlRpcTest...
Getting test page content...

```

```
Got page content:
```

```
This is a test of <a href='XmlRpc'>XmlRpc</a>
```

```
Getting page list...
```

```
Got page list: ['WikiHome', 'CurlTest', 'XmlRpcTest', 'WgetTest', 'RestTest',  
'PythonXmlRpcTest']
```

5.4.2. How Does That Work?

The `callRemote` method of `xmlrpc.Proxy` takes the name of the function to be called as the first argument, followed by an arbitrary number of additional arguments that will be passed to the function. When you use `callRemote`, the `Proxy` encodes your function call as XML, sends it to the server using an HTTP POST, and returns a `Deferred`. When the server responds, the `Proxy` decodes the XML and calls back the `Deferred` with the returned value.

[< Day Day Up >](#)

5.5. Installing SOAP Libraries

SOAP (for Simple Object Access Protocol) is another way to make remote function calls using XML over HTTP. SOAP and XML-RPC were both developed as part of the same project; XML-RPC is basically an early working version of what eventually became SOAP. While XML-RPC was intentionally kept simple, SOAP grew to become more powerful and more complicated.

Here's an example of the SOAP XML format, calling the function `echo` with the string argument `'cheese'`:

```
<?xml version="1.0" encoding="UTF-8"?>
<SOAP-ENV:Envelope
  SOAP-ENV:encodingStyle="http://schemas.xmlsoap.org/soap/encoding/"
  xmlns:SOAP-ENC="http://schemas.xmlsoap.org/soap/encoding/"
  xmlns:xsi="http://www.w3.org/1999/XMLSchema-instance"
  xmlns:SOAP-ENV="http://schemas.xmlsoap.org/soap/envelope/"
  xmlns:xsd="http://www.w3.org/1999/XMLSchema">
  <SOAP-ENV:Body>
    <echo SOAP-ENC:root="1">
      <v1 xsi:type="xsd:string">cheese</v1>
    </echo>
  </SOAP-ENV:Body>
</SOAP-ENV:Envelope>
```

And here's the XML returned from the server:

```
<?xml version="1.0" encoding="UTF-8"?>
<SOAP-ENV:Envelope
  SOAP-ENV:encodingStyle="http://schemas.xmlsoap.org/soap/encoding/"
  xmlns:SOAP-ENC="http://schemas.xmlsoap.org/soap/encoding/"
  xmlns:xsi="http://www.w3.org/1999/XMLSchema-instance"
  xmlns:SOAP-ENV="http://schemas.xmlsoap.org/soap/envelope/"
```

```

xmlns:xsd="http://www.w3.org/1999/XMLSchema">

<SOAP-ENV:Body>

  <echoResponse SOAP-ENC:root="1">

    <Result xsi:type="xsd:string">You said: cheese</Result>

  </echoResponse>

</SOAP-ENV:Body>

</SOAP-ENV:Envelope>

```

Twisted uses an external library called SOAPpy to create and parse SOAP messages. You'll have to install SOAPpy to run the next two examples. SOAPpy also requires two additional libraries to be installed: PyXML and fpconst.

To install PyXML, download the package for your platform from <http://pyxml.sourceforge.net>. If there is an installer available, use it to install PyXML. Otherwise, you can install from the source by extracting the package, entering the package directory, and running the command `python setup.py install`. You can test to make sure PyXML is installed correctly by importing it in a Python shell:

```

$ python

Python 2.4.1 ("help", "copyright", "credits" or "license" for more information.

>>> import xml

>>> xml.__version__

'0.8.4'

```

The `xml.__version__` property should be the same as the PyXML package you installed.

The next prerequisite for SOAPpy is fpconst—a Python library for working with floating-point special values. fpconst doesn't have installer packages available, so you'll have to install from the source. Download and extract the latest version. In the directory containing the extracted files, run the command `python setup.py install`. Once the install is completed, you can verify that fpconst is correctly installed by importing it in a Python shell:

```

$ python

Python 2.4.1 (#2, Apr 14 2005, 09:13:52)

[GCC 4.0.0 20050413 (prerelease) (Debian 4.0-0pre11)] on linux2

Type "help", "copyright", "credits" or "license" for more information.

>>> import fpconst

>>> fpconst.__version__

```

```
'0.6.0'
```

Now that the dependencies are installed, you can install SOAPpy. Like `fpconst`, it's available only as a source package. Download the latest release from <http://pywebsvcs.sourceforge.net/> and extract it. In the directory containing the extracted files, run the command `python setup.py install` to install SOAPpy. Again, it's a good idea to make sure the install was successful by importing the module:

```
$ python
Python 2.4.1 (#2, Apr 14 2005, 09:13:52)
[GCC 4.0.0 20050413 (prerelease) (Debian 4.0-0pre11)] on linux2
Type "help", "copyright", "credits" or "license" for more information.
>>> import SOAPpy
>>> SOAPpy.__version__
'0.11.3'
```



For more information on installing SOAPpy, see the file README in the SOAPpy package.

< Day Day Up >

5.6. Sharing Web Services with SOAP

Once you have SOAPpy installed, you can write a Twisted server that provides web services through SOAP.

5.6.1. How Do I Do That?

Because SOAP is based on HTTP, you enable SOAP web services by adding a special type of `Resource` to a twisted web server. Write a class that inherits from `soap.SOAPPublisher` and has methods starting with `soap_`. Make your class available as a web resource, as shown in [Example 5-5](#), and you're ready to handle SOAP requests.

Example 5-5. `soap_server.py`

```
import wiki, rest_wiki

from twisted.web import server, soap

class WikiSoap(soap.SOAPPublisher):

    def __init__(self, wikiData):

        self.wikiData = wikiData

    def soap_hasPage(self, path):

        return self.wikiData.hasPage(path)

    def soap_listPages(self):

        return self.wikiData.listPages( )

    def soap_getPage(self, path):

        return self.wikiData.getPage(path)

    def soap_getRenderedPage(self, path):

        return self.wikiData.getRenderedPage(path)

    def soap_setPage(self, path, data):
```

```

        self.wikiData.setPage(path, data)

if __name__ == "__main__":
    import sys

    from twisted.internet import reactor

    datafile = sys.argv[1]

    wikiData = wiki.WikiData(datafile)

    siteRoot = rest_wiki.RootResource(wikiData)

    siteRoot.putChild('SOAP
', WikiSoap(wikiData))

    reactor.listenTCP(8082, server.Site(siteRoot))

    reactor.run( )

```

Run `soap_server.py` from the command line with the name of your Wiki datafile as an argument:

```
$ python soap_server.py wiki.dat
```

Once again, it will start up a web server on port 8082, but this time it will listen for SOAP requests at <http://localhost:8082/SOAP>. You should be able to test this using a SOAP library in any language; the next lab shows how to do so using a Twisted SOAP client.

5.6.2. How Does That Work?

The `soap .SOAPPublisher` class is the SOAP equivalent of the `xmlrpc .XMLRPC` class in [Example 5-3](#). It's a subclass of `Resource` that parses the SOAP message in an incoming HTTP POST, runs the requested function, and then returns the SOAP-formatted result. Note that unlike XML-RPC, SOAP supports null values, so you don't have to avoid returning `None` from your methods.

[< Day Day Up >](#)

5.7. Calling SOAP Web Services

The `twisted.web.soap` module contains a soap client. You can use it to communicate with the SOAP Wiki service defined in [Example 5-5](#).

5.7.1. How Do I Do That?

The `twisted.web.soap.Proxy` class provides the same `callRemote` method as `twisted.web.xmlrpc.Proxy`. Use `callRemote` to call a SOAP method and get a `Deferred` result. [Example 5-6](#) demonstrates a SOAP client that communicates with the SOAP Wiki service from [Example 5-5](#).

Example 5-6. `soap_client.py`

```
from twisted.web import soap
from twisted.internet import reactor

class WikiTester(object):
    def __init__(self):
        self.wiki = soap.Proxy('http://localhost:8082/SOAP')

    def runTests(self):
        self.listPages().addCallback(
            lambda _:self.createTestPage()).addCallback(
            lambda _: self.getTestPage()).addErrback(
            self._catchFailure).addCallback(
            lambda _: reactor.stop())

    def listPages(self):
        print "Getting page list..."
        return self.wiki.callRemote('listPages').addCallback(
            self._gotList)

    def _gotList(self, pages):
        print "Got page list:", pages
```

```

def createTestPage(self):
    print "Creating test page SoapTest..."
    pageData = "This is a test of SoapRpc"
    return self.wiki.callRemote('setPage', 'SoapTest', pageData)

def getTestPage(self):
    print "Getting test page content..."
    return self.wiki.callRemote(
        'getRenderedPage', 'SoapTest').addCallback(
            self._gotTestPage)

def _gotTestPage(self, content):
    print "Got page content:"
    print content
    return self.listPages( )

def _catchFailure(self, failure):
    print "Error:", failure.getErrorMessage( )

w = WikiTester( )
w.runTests( )
reactor.run( )

```

Run *soap_client.py*, and it will test calling some methods through SOAP:

```

$ python soap_client.py
Getting page list...
Got page list: <SOAPpy.Types.typedArrayType Result at -1226273460>:
['WikiHome', 'CurlTest', 'XmlRpcTest', 'WgetTest', 'RestTest', 'PythonXmlRpcTest']
Creating test page SoapTest...
Getting test page content...
Got page content:

```

```
This is a test of <a href='SoapRpc'>SoapRpc</a>

Getting page list...

Got page list: <SOAPpy.Types.typedArrayType Result at -1226245012>:

['WikiHome', 'CurlTest', 'SoapTest', 'XmlRpcTest', 'WgetTest', 'RestTest',
'PythonXmlRpcTest']
```

5.7.2. How Does That Work?

The `callRemote` method of `soap.Proxy` takes the name of a function as the first argument, followed by any number of additional arguments that will be passed to the function. You can use keyword arguments instead, if the SOAP service you're using supports named arguments. When you use `callRemote`, the `Proxy` encodes your function call as a SOAP XML document, sends it to the server using an `HTTP POST` request, and returns a `Deferred`. When the server responds, the `Proxy` parses the result using `SOAPpy` and calls back the `Deferred` with the returned value.

[< Day Day Up >](#)

5.8. Sharing Python Objects with Perspective Broker

XML-RPC and SOAP both transfer data using XML, which makes them language- and platform-neutral. This is an advantage most of the time. But what if you want to communicate between two Twisted applications without having to interoperate with anything else? In that case, the cross-platform advantages of XML could introduce a lot of work, as you have to convert your objects into formats that can be serialized as XML elements. A better approach might be to use Twisted Spread , a system for RPC that uses serialized Python objects.

5.8.1. How Do I Do That?

The core of Twisted Spread is Perspective Broker, which manages connections and handles calls to and from remote objects. The Perspective Broker module is named `pb`, which has resulted in a large number of peanut-butter-sandwich-related puns and module names (two of the other modules in Spread are `banana` and `jelly`).

Perspective Broker is conservative about what it exposes to the network. To avoid security holes, you have to specify exactly which objects should be able to be accessed remotely, and which methods you want to make available over the network. The `pb` module contains several different classes that you can inherit from to provide remotely accessible objects and methods. It also provides a `PBServerFactory` class for managing a Perspective Broker server. [Example 5-7](#) shows how to run a server that shares Wiki data using Perspective Broker.

Example 5-7. `pb_wiki.py`

```
from twisted.spread import pb

import wiki

class WikiPerspective(pb.Root):
    def __init__(self, wikiData):
        self.wikiData = wikiData

    def remote_hasPage(self, path):
        return self.wikiData.hasPage(path)

    def remote_listPages(self):
        return self.wikiData.listPages()
```

```

def remote_getPage(self, path):
    return self.wikiData.getPage(path)

def remote_getRenderedPage(self, path):
    return self.wikiData.getRenderedPage(path)

def remote_setPage(self, path, data):
    self.wikiData.setPage(path, data)

def remote_getReporter(self):
    return RemoteWikiReporter(self.wikiData)

class WikiReporter(pb.Referenceable):
    "I do simple reporting tasks in the wiki"
    def __init__(self, wikiData):
        self.wikiData = wikiData

    def listNeededPages(self):
        "return a list of pages that are linked to but don't exist yet"
        allPages = [self.wikiData.getPage(p)
                     for p in self.wikiData.listPages( )]
        neededPages = []
        for page in allPages:
            wikiWords = [match[0]
                         for match in wiki.reWikiWord.findall(page)]
            for pageName in wikiWords:
                if not self.wikiData.hasPage(pageName):
                    neededPages.append(pageName)
        return neededPages

if __name__ == "__main__":
    import sys
    from twisted.internet import reactor
    datafile = sys.argv[1]

```

```
wikiData = wiki.WikiData(datafile)
wikiPerspective = WikiPerspective(wikiData)
reactor.listenTCP(8789, pb.PBServerFactory(wikiPerspective))
reactor.run( )
```

Run *pb_server.py* with one argument, the name of the Wiki datafile:

```
$ python pb_server.py wiki.dat
```

Now you need a client to connect to the server. [Example 5-8](#) shows a basic Perspective Broker client.

Example 5-8. pb_client.py

```
from twisted.spread import pb
from twisted.internet import reactor

class PbTester(object):
    def __init__(self):
        self.wiki = None

    def runTests(self):
        self.connect( ).addCallback(
            lambda _: self.listPages( ).addCallback(
                lambda _: self.createTestPage( ).addCallback(
                    lambda _: self.getTestPage( ).addCallback(
                        lambda _: self.runReports( ).addErrback(
                            self._catchFailure).addCallback(
                                lambda _: reactor.stop( ))

    def connect(self):
```

```

factory = pb.PBClientFactory( )

reactor.connectTCP("localhost", 8789, factory)

return factory.getRootObject( ).addCallback(self._connected)

def _connected(self, rootObj):

    self.wiki = rootObj

def listPages(self):

    print "Getting page list..."

    return self.wiki.callRemote('listPages').addCallback(

        self._gotList)

def _gotList(self, pages):

    print "Got page list:", pages

def createTestPage(self):

    print "Creating test page PbTest..."

    pageData = "This is a test of PerspectiveBroker"

    return self.wiki.callRemote('setPage', 'PbTest', pageData)

def getTestPage(self):

    print "Getting test page content..."

    return self.wiki.callRemote(

        'getRenderedPage', 'PbTest').addCallback(

        self._gotTestPage)

def _gotTestPage(self, content):

    print "Got page content:"

    print content

    return self.listPages( )

def runReports(self):

    print "Running report..."

    return self.wiki.callRemote('getReporter').addCallback(

```

```

        self._gotReporter)

def _gotReporter(self, reporter):
    print "Got remote reporter object"
    return reporter.callRemote('listNeededPages').addCallback(
        self._gotNeededPages)

def _gotNeededPages(self, pages):
    print "These pages are needed:", pages

def _catchFailure(self, failure):
    print "Error:", failure.getErrorMessage( )

t = PbTester( )
t.runTests( )
reactor.run( )

```

Run *pb_client.py*, and it will call functions on the server using the Perspective Broker protocol:

```

$ python pb_client.py
Getting page list...
Got page list: ['WikiHome', 'CurlTest', 'SoapTest', 'XmlRpcTest', 'WgetTest',
'RestTest', 'PythonXmlRpcTest']
Creating test page PbTest...
Getting test page content...
Got page content:
This is a test of <a href='PerspectiveBroker'>PerspectiveBroker</a>
Getting page list...
Got page list: ['WikiHome', 'CurlTest', 'SoapTest', 'XmlRpcTest', 'WgetTest',
'RestTest', 'PbTest', 'PythonXmlRpcTest']
Running report...
Got remote reporter object

```

```
These pages are needed: ['AnotherWikiPage', 'SoapRpc', 'XmlRpc', 'HttpPut',
'PerspectiveBroker', 'XmlRpc']
```

5.8.2. How Does That Work?

The *pb_server.py* server creates subclasses of classes in the `twisted.spread.pb` module. `WikiPerspective` is a subclass of `pb.Root`, and `WikiReporter` is a subclass of `pb.Referenceable`. Inheriting from these special classes tells Perspective Broker that these objects should be made available for remote access. Methods that should be available remotely must be named with a `remote_` prefix.

`WikiPerspective` inherits from `pb.Root`, and is passed to the `PBServerFactory` when it gets created. This makes a `WikiPerspective` instance available to any client that establishes a connection.

The `WikiReporter` class in [Example 5-7](#) is an example of how you could expose a second object through Perspective Broker. To make this object available over the network, it inherits from `pb.Referenceable`. `WikiReporter` has one method, `remote_listNeededPages`, which crawls through the Wiki data and returns a list of pages that are mentioned in other pages but have yet to be created.

On the client side, *pb_client.py* opens a connection to the server. The first thing it has to do is call `getRootObject` on a `PBClientFactory`. This returns a `Deferred` that will call back with a reference to the root object on the remote server once the connection has been established. Once you have the root object, you can call remote methods with the same `callRemote` syntax used in the XML-RPC and SOAP clients earlier in this chapter.

The server method `remote_getReporter` is interesting because instead of returning a simple Python type it returns a `WikiReporter` object. Since `WikiReporter` inherits from `pb.Referenceable`, the server knows to give the client a reference to the server-side object. Once it receives this reference, the client can use its `callRemote` method to call methods on the `WikiReporter` object that was created on the server.



[Example 5-7](#) doesn't require authentication, and makes no distinction between different users who might be connecting to the server. To learn how to manage authentication and user permissions in Perspective Broker, see [Example 6-5](#).

Chapter 6. Authentication

A requirement in almost any server application is a system for managing authentication . You need to be able to verify the identity of every user who attempts to access your server, based on their password or some other credentials. Once you allow a user to log in, you need to manage his permissions, controlling what he can and cannot do. The `twisted.cred` package is designed to facilitate these kinds of tasks.

Many parts of Twisted rely on `twisted.cred`, including the POP3, IMAP, SSH, and FTP servers. You can also use `twisted.cred` to add authentication to a web application, an SMTP server, a Perspective Broker server, or your own custom protocol. This chapter explains how `twisted.cred` works, and how to use it in your applications.

6.1. Using Authentication in a Twisted Server

There are quite a few different classes and interfaces used in `twisted.cred`. These classes and interfaces work together to form a flexible authentication system. This lab introduces the individual pieces of `twisted.cred` and shows how to tie them together to add authentication to a server.

6.1.1. How Do I Do That?

Set up a `portal.Portal` object that takes the username and password provided by a user, verifies her identity, and returns an object representing the actions and data available to that user. To do this you'll need to implement a few different `twisted.cred` interfaces. [Example 6-1](#) demonstrates how to do this, adding authentication to a simple line-based server protocol.

Example 6-1. `simplecred.py`

```
from twisted.cred import portal, checkers, credentials, error as credError
from twisted.protocols import basic
from twisted.internet import protocol, reactor, defer
from zope.interface import Interface, implements

class PasswordDictChecker(object):
    implements(checkers.ICredentialsChecker)
    credentialInterfaces = (credentials.IUsernamePassword,)

    def __init__(self, passwords):
        "passwords: a dict-like object mapping usernames to passwords"
        self.passwords = passwords

    def requestAvatarId(self, credentials):
        username = credentials.username
        if self.passwords.has_key(username):
            if credentials.password == self.passwords[username]:
                return defer.succeed(username)
        else:
```

```

        return defer.fail(
            credError.UnauthorizedLogin("Bad password"))
    else:
        return defer.fail(
            credError.UnauthorizedLogin("No such user"))

class INamedUserAvatar(Interface):
    "should have attributes username and fullname"

class NamedUserAvatar:
    implements(INamedUserAvatar)
    def __init__(self, username, fullname):
        self.username = username
        self.fullname = fullname

class TestRealm:
    implements(portal.IRealm)

    def __init__(self, users):
        self.users = users

    def requestAvatar(self, avatarId, mind, *interfaces):
        if INamedUserAvatar in interfaces:
            fullname = self.users[avatarId]
            logout = lambda: None
            return (INamedUserAvatar,
                    NamedUserAvatar(avatarId, fullname),
                    logout)
        else:
            raise KeyError("None of the requested interfaces is supported")

class LoginTestProtocol(basic.LineReceiver):
    def lineReceived(self, line):

```

```

cmd = getattr(self, 'handle_' + self.currentCommand)

cmd(line.strip( ))

def connectionMade(self):

    self.transport.write("User Name: ")

    self.currentCommand = 'user'

def handle_user(self, username):

    self.username = username

    self.transport.write("Password: ")

    self.currentCommand = 'pass'

def handle_pass(self, password):

    creds = credentials.UsernamePassword(self.username, password)

    self.factory.portal.login(creds, None, INamedUserAvatar).addCallback(

        self._loginSucceeded).addErrback(

            self._loginFailed)

def _loginSucceeded(self, avatarInfo):

    avatarInterface, avatar, logout = avatarInfo

    self.transport.write("Welcome %s!\r\n" % avatar.fullname)

    defer.maybeDeferred(logout).addBoth(self._logoutFinished)

def _logoutFinished(self, result):

    self.transport.loseConnection( )

def _loginFailed(self, failure):

    self.transport.write("Denied: %s.\r\n" % failure.getErrorMessage( ))

    self.transport.loseConnection( )

class LoginTestFactory(protocol.ServerFactory):

    protocol = LoginTestProtocol

```

```

def __init__(self, portal):
    self.portal = portal

users = {
    'admin': 'Admin User',
    'user1': 'Joe Smith',
    'user2': 'Bob King',
}

passwords = {
    'admin': 'aaa',
    'user1': 'bbb',
    'user2': 'ccc'
}

if __name__ == "__main__":
    p = portal.Portal(TestRealm(users))
    p.registerChecker(PasswordDictChecker(passwords))
    factory = LoginTestFactory(p)
    reactor.listenTCP(2323, factory)
    reactor.run( )

```

When you run *simplecred.py*, it will start up a server on port 2323. You can then communicate with the server using *Telnet*. Each time you make a connection, it will ask for your username and password, attempt to log you in, and then disconnect:

```

$ telnet localhost 2323

Trying 127.0.0.1...

Connected to sparky.

Escape character is '^]'.

User Name: admin

Password: aaa

```

```
Welcome Admin User!
Connection closed by foreign host.
```

```
$ telnet localhost 2323
```

```
Trying 127.0.0.1...
Connected to sparky.
Escape character is '^]'.
User Name: admin
Password: 123
```

```
Denied: Bad password.
Connection closed by foreign host.
```

```
$ telnet localhost 2323
```

```
Trying 127.0.0.1...
Connected to sparky.
Escape character is '^]'.
User Name: someotherguy
Password: pass
```

```
Denied: No such user.
Connection closed by foreign host.
```

6.1.2. How Does That Work?

Before you try to understand how all the classes in [Example 6-1](#) work, you should familiarize yourself with the vocabulary `twisted.cred` uses to talk about users and authentication. Here are some of the terms you'll see in [Example 6-1](#), and other applications using `twisted.cred`:

Credentials

Information used to identify and authenticate a user. This is typically a username and password, but it can be any data or object used to prove a user's identity. Objects that provide credentials will implement `twisted.cred.credentials.ICredentials`.

Avatar

An object on the server that does things on behalf of a user. The concept of an avatar can seem a little fuzzy at first. Don't think of an avatar as representing a user: think of it as representing actions and data available to a user inside your application.

Avatar ID

A string that identifies a specific user, used to get the appropriate Avatar for that user. This is often the login username, but it could be any unique identifier. Examples could be "Joe Smith", "joe@localhost", or "user926344".

Credentials Checker

An object that takes credentials and attempts to verify them. If the credentials correctly identify a user, the credentials checker will return an avatar ID. Credential checker objects implement the interface `twisted.cred.checker.ICredentialsChecker`.

Realm


An object that provides access to all the possible avatars in an application. A realm will take an avatar ID identifying a specific user and return an avatar object that will work on behalf of that user. A realm can support multiple types of avatar, allowing the same user to work with different services provided by the server. Realm objects implement the interface `twisted.cred.portal.IRealm`.

Portal

A `twisted.cred.portal.Portal` object, which unites a realm with a set of credential checkers. Inside a portal, the credential checker objects check incoming credentials, returning an avatar ID if the credentials are valid. The avatar ID is then passed to the realm to create an avatar object that can work on behalf of the user.

Figure 6-1 shows how a portal, realm, and credentials checkers work together.

Figure 6-1. Interaction between a portal, realm, and credentials checkers



It might take you a little while to understand all the classes and interfaces in `twisted.cred`, and at first you might wonder why it's necessary to have a system with so many moving parts. The answer is that this system is designed to be extremely flexible. The code that verifies credentials is kept separate from the code that creates Avatar objects, so you can switch your authentication backend from a password file to a database

table or LDAP server without having to touch the rest of your application. If you originally design your system to use plain-text passwords, and later decide to support hashed passwords, all you have to do is plug in a new `CredentialsChecker` object. If you write a mail server that supports POP3 now, you can later add IMAP4 access, or a web interface, and you won't have to rewrite your authentication code. Your initial investment in understanding `twisted.cred` now will pay off in flexible, maintainable code later.

In [Example 6-1](#), `PasswordDictChecker` implements `checkers.ICredentialsChecker` to check usernames and passwords. The `requestAvatarId` method will be called when a user tries to log in. `requestAvatarId` takes a `credentials` object that implements one of the interfaces listed in `credentialsInterfaces`, which in this case is limited to `credentials.IUsernamePassword`. If `PasswordDictChecker` was capable of accepting credentials other than a plain-text username and password, it would advertise this by including additional interfaces in the `credentialsInterfaces` list.

If the username and password supplied by the user matches a username and password in the database, `requestAvatarId` returns a `Deferred` that will be called back with a value identifying the user, who at that point has been successfully authenticated. Otherwise, it returns a `Deferred` that fails with a `twisted.cred.error.UnauthorizedLogin` exception.

The second half of the authentication backend in [Example 6-1](#) is `TestRealm`, which implements `twisted.cred.portal.IRealm`. This class does the work of taking the avatar ID of an authenticated user and returning an avatar capable of doing certain tasks on behalf of that user.

`TestRealm.requestAvatar` takes three or more arguments: `avatarID`, `mind`, and one or more interfaces. The first argument, `avatarID`, is a string identifying the user for whom an avatar should be returned. The second argument, `mind`, is supposed to represent the actual user on the other end of the connection. In practice, though, `mind` is used only by `Perspective Broker` servers. For other applications, you can feel free to ignore it. The `interfaces` list passed to `requestAvatar` tell the realm what interface the avatar needs to support. (If there is more than one interface argument, it means that the application calling `requestAvatar` is capable of working with multiple interfaces. See [Example 6-3](#).) It returns a tuple containing three values: the interface that the avatar supports, the avatar itself, and a logout function that can be called to shut down the avatar when the user is done with the session.

The `TestRealm` class in [Example 6-1](#) provides access to a single type of avatar, `NamedUserAvatar`, which implements the interface `INamedUser`. `NamedUserAvatar` doesn't do a whole lot: it provides two attributes, `username` and `fullname`, that can be used to get some basic information about the user.

`TestRealm.requestAvatar` first checks to make sure that at least one of the interfaces requested by the client is `INamedUser`, the only interface which it supports. Then it looks up the full name of the user in its list of users, and uses the full name to construct a `NamedUserAvatar` object. Then it returns a tuple containing three values: the matching avatar interface (in this case always `INamedUser`), the avatar object itself, and a logout function. As the server in [Example 6-1](#) isn't even keeping track of the current avatars, it doesn't have to take any action when a user is logged out. So it uses an anonymous logout function that doesn't do anything.

A `Portal` object combines a realm with credentials checkers to form a complete authentication system. When you initialize a `Portal`, pass it an object that implements `IRealm`. Then call `registerChecker` with an object that implements `credentials.ICredentialsChecker`. You can call `registerChecker` multiple times if you have separate credentials checkers for handling different credentials interfaces.

`Portal` provides a single method, `login`, that encapsulates the whole authentication process. `Portal.login` takes a set of credentials as the first argument, a `mind` object as the second argument (which is rarely used, and usually just the value `None`), and one or more interfaces as the third and following arguments. It looks through its available set of `ICredentialsChecker` objects (which were added with

registerChecker) and finds one that can handle the provided type of credentials. Then it calls the checker's requestAvatarId method to authenticate the user. Next, the Portal takes the avatar ID returned by the credentials checker and the list of interfaces passed to login and uses them to call its realm's requestAvatar method. The resulting tuple of avatar interface, avatar, and logout function gets called back as the result of login.

When you connect to the server in [Example 6-1](#), LoginTestProtocol asks for a username and password. When these are provided, it wraps them in a credentials.UsernamePassword object and passes it to self.factory.portal.login along with None (a placeholder for the mind argument) and INamedUserAvatar, which specifies the kind of avatar LoginTestProtocol wants to get back. If login is successful, it will call back with a NamedUserAvatar object; otherwise, it will errback with an error describing why the login failed.

< Day Day Up >

6.2. Authenticating Against a Database Table

The design of `twisted.cred` makes it easy to swap out various parts of your authentication system. This example demonstrates how to replace the dictionaries of usernames and passwords used in [Example 6-1](#) with a SQL database table.

6.2.1. How Do I Do That?

To check usernames and passwords against a database table, write a new class implementing `checkers.ICredentialsChecker`. To create avatars based on database records, write a new class implementing `portal.IRealm`. [Example 6-2](#) demonstrates how to modify the server from [Example 6-1](#) to use a MySQL database for authentication.

Example 6-2. `dbcred.py`

```
from twisted.enterprise import adbapi, util as dbutil
from twisted.cred import credentials, portal, checkers, error as credError
from twisted.internet import reactor, defer
from zope.interface import implements
import simplecred

class DbPasswordChecker(object):
    implements(checkers.ICredentialsChecker)
    credentialInterfaces = (credentials.IUsernamePassword,
                           credentials.IUsernameHashedPassword)

    def __init__(self, dbconn):
        self.dbconn = dbconn

    def requestAvatarId(self, credentials):
        query = "select userid, password from user where username = %s" % (
            dbutil.quote(credentials.username, "char"))
        return self.dbconn.runQuery(query).addCallback(
```

```
self._gotQueryResults, credentials)
```

```
def _gotQueryResults(self, rows, userCredentials):
```

```
    if rows:
```

```
        userid, password = rows[0]
```

```
        return defer.maybeDeferred(
```

```
            userCredentials.checkPassword, password).addCallback(
```

```
            self._checkedPassword, userid)
```

```
    else:
```

```
        raise credError.UnauthorizedLogin, "No such user"
```

```
def _checkedPassword(self, matched, userid):
```

```
    if matched:
```

```
        return userid
```

```
    else:
```

```
        raise credError.UnauthorizedLogin("Bad password")
```

```
class DbRealm:
```

```
    implements(portal.IRealm)
```

```
def __init__(self, dbconn):
```

```
    self.dbconn = dbconn
```

```
def requestAvatar(self, avatarId, mind, *interfaces):
```

```
    if simplecred.INamedUserAvatar in interfaces:
```

```
        userQuery = """
```

```
            select username, firstname, lastname
```

```
            from user where userid = %s
```

```
        """ % dbutil.quote(avatarId, "int")
```

```
        return self.dbconn.runQuery(userQuery).addCallback(
```

```
            self._gotQueryResults)
```

```
    else:
```

```
        raise KeyError("None of the requested interfaces is supported")
```

```

def _gotQueryResults(self, rows):
    username, firstname, lastname = rows[0]
    fullname = "%s %s" % (firstname, lastname)
    return (simplecred.INamedUserAvatar,
            simplecred.NamedUserAvatar(username, fullname),

            lambda: None) # null logout function

DB_DRIVER = "MySQLdb"

DB_ARGS = {
    'db': 'your_db',
    'user': 'your_db_username',
    'passwd': 'your_db_password',
}

if __name__ == "__main__":
    connection = adbapi.ConnectionPool(DB_DRIVER, **DB_ARGS)
    p = portal.Portal(DbRealm(connection))
    p.registerChecker(DbPasswordChecker(connection))
    factory = simplecred.LoginTestFactory(p)
    reactor.listenTCP(2323, factory)
    reactor.run( )

```

Before you run *dbcred.py*, create a MySQL database table called `user`, and insert some records for testing:

```

CREATE TABLE user (
    userid int NOT NULL PRIMARY KEY,
    username varchar(20) NOT NULL,
    password varchar(50) NOT NULL,
    firstname varchar(100),
    lastname varchar(100),
);

```

```
INSERT INTO user VALUES (1, 'admin', 'aaa', 'Admin', 'User');
INSERT INTO user VALUES (2, 'test1', 'bbb', 'Joe', 'Smith');
INSERT INTO user VALUES (3, 'test2', 'ccc', 'Bob', 'King');
```

dbcred.py works exactly the same way as *simplecred.py* from [Example 6-1](#). It has a new authentication backend, but from the user's, perspective nothing has changed:

```
$ telnet localhost 2323
Trying 127.0.0.1...
Connected to sparky.
Escape character is '^]'.
User Name: admin
Password: aaa

Welcome Admin User!
Connection closed by foreign host.
```

```
$ telnet localhost 2323
Trying 127.0.0.1...
Connected to sparky.
Escape character is '^]'.
User Name: admin
Password: 123

Denied: Bad password.
Connection closed by foreign host.
```

```
$ telnet localhost 2323
Trying 127.0.0.1...
Connected to sparky.
Escape character is '^]'.
User Name: someotherguy
Password: pass
```

```
Denied: No such user.
```

```
Connection closed by foreign host.
```

6.2.2. How Does That Work?

The class `DbPasswordChecker` in [Example 6-2](#) checks usernames and passwords against a database table. The `requestAvatarId` function takes the provided username and runs a database query to look for a matching record. The `_gotQueryResults` function handles the results of the query. If there were no records, it raises a `twisted.cred.error.UnauthorizedLogin` exception. (Because `_gotQueryResults` is running as the callback handler of a `Deferred` that was returned from `requestAvatarId`, this exception will be caught by that `Deferred` and eventually passed back to the error handler for `Portal.login`.)

If there was a matching record in the database, `_gotQueryResults` checks to see whether the password supplied by the user matches the database password. It does this in an indirect way, calling `userCredentials.checkPassword`, a method supplied by the `credentials.IUsernamePassword` interface. `checkPassword` can return either a `Boolean` value or a `Deferred`; wrapping the call in `defer.maybeDeferred` lets you treat the result as a `Deferred` in either case.



Using the `IUsernamePassword.checkPassword` method instead of comparing the passwords yourself gives the server-side protocol that created the credentials object more flexibility: it could use a custom implementation of `IUsernamePassword` that compared the passwords in a case-insensitive way, or asynchronously. Moreover, using the `checkPassword` method allows `DbPasswordChecker` to accept a second credentials interface—`IUsernameHashedPassword`. If the protocol being used here involved hashed passwords, it wouldn't be possible to do a direct comparison of the hash sent by the user and the plain-text password in our database. The `checkPassword` method lets the credentials object compare the two using the proper hashing algorithm. This isn't necessary in [Example 6-2](#), since it uses plain-text passwords, but writing your code this way makes it easier to reuse `DbPasswordChecker` for other services in the future.

The `_checkedPassword` method handles the `Boolean` result of `checkPassword`. If the password matched, it returns the value of the field `userid` from the database: this is the final result of `requestAvatarId`. Note that this is a different type of avatar ID than in [Example 6-1](#). In [Example 6-1](#), the avatar ID was equal to the username; this time, it's an integer identifying the database record. This works because the avatar ID is used only by the realm, and [Example 6-2](#) has a new realm as well. `DbRealm.requestAvatar` takes the avatar ID returned by `DbConnector.requestAvatarId` and uses it to fetch the full user record from the database. Then it uses the results to construct a `NamedUserAvatar` object.

[Example 6-2](#) creates a `Portal` object that uses `DbRealm` as its realm and registers `DbPasswordChecker` as a credentials checker. Then the `Portal` is passed to a `LoginTestFactory`. This factory and its

protocol come directly from the `simplecred` module in [Example 6-1](#). They are able to function exactly as they did before without any changes, as the `Portal` hides the implementation details.

< Day Day Up >

6.3. Representing Users with Different Capabilities

It can often be useful to authenticate against an external service. You can avoid making users maintain an additional username and password by using a credentials checker that tries to log into a POP mail server, a web application, or some other service where you know your users will already have accounts. However, this approach creates a potential problem. Your realm is going to be asked for avatars after users have been authenticated by the credentials checker. But since the credentials checker is using an external service, rather than a local data source, for authentication, the realm may not have any information about the avatars it's asked for. While you might be able to spontaneously create accounts based on the avatar ID, you will frequently need additional information before users can start using their accounts.

You can handle this scenario by taking advantage of the way `twisted.cred` supports multiple avatar interfaces. Your realm can use different types of avatars to represent users with different capabilities. One interface can identify users from whom you need additional information, and another interface can identify users who have already provided the necessary information and are ready to use your application.

6.3.1. How Do I Do That?

Write a class implementing `portal.IRealm` that accepts two different avatar interfaces in `requestAvatar`. Use one avatar interface for users who need to supply additional information before they can start using your service. This interface should provide a way for users to submit the required information. Use a second avatar interface to provide the normal user actions and data. [Example 6-3](#) demonstrates this technique.

Example 6-3. multiavatar.py

```
from twisted.cred import portal, checkers, credentials, error as credError
from twisted.protocols import basic
from twisted.internet import protocol, reactor, defer
from zope.interface import Interface, implements

class INamedUserAvatar(Interface):
    "should have attributes username and fullname"

class NamedUserAvatar:
    implements(INamedUserAvatar)

    def __init__(self, username, fullname):
```

```

self.username = username

self.fullname = fullname

```

```

class INewUserAvatar(Interface):

    "should have username attribute only"

    def setName(self, fullname):

        raise NotImplementedError

class NewUserAvatar:

    implements(INewUserAvatar)

    def __init__(self, username, userDb):

        self.username = username

        self.userDb = userDb

    def setName(self, fullname):

        self.userDb[self.username] = fullname

        return NamedUserAvatar(self.username, fullname)

class MultiAvatarRealm:

    implements(portal.IRealm)

    def __init__(self, users):

        self.users = users

    def requestAvatar(self, avatarId, mind, *interfaces):

        logout = lambda: None

        if INamedUserAvatar in interfaces and self.users.has_key(avatarId):

            fullname = self.users[avatarId]

            return (INamedUserAvatar,

                    NamedUserAvatar(avatarId, fullname),

                    logout)

        elif INewUserAvatar in interfaces:

            avatar = NewUserAvatar(avatarId, self.users)

```

```

        return (INewUserAvatar, avatar, logout)

    else:

        raise KeyError("None of the requested interfaces is supported")

class PasswordDictChecker(object):

    implements(checkers.ICredentialsChecker)

    credentialInterfaces = (credentials.IUsernamePassword,)

    def __init__(self, passwords):

        "passwords: a dict-like object mapping usernames to passwords"

        self.passwords = passwords

    def requestAvatarId(self, credentials):

        username = credentials.username

        if self.passwords.has_key(username):

            if credentials.password == self.passwords[username]:

                return defer.succeed(username)

            else:

                return defer.fail(

                    credError.UnauthorizedLogin("Bad password"))

        else:

            return defer.fail(

                credError.UnauthorizedLogin("No such user"))

class NamedUserLoginProtocol(basic.LineReceiver):

    def lineReceived(self, line):

        cmd = getattr(self, 'handle_' + self.currentCommand)

        cmd(line.strip( ))

    def connectionMade(self):

        self.transport.write("User Name: ")

        self.currentCommand = 'user'

```

```

def handle_user(self, username):
    self.username = username
    self.transport.write("Password: ")
    self.currentCommand = 'pass'

def handle_pass(self, password):
    creds = credentials.UsernamePassword(self.username, password)
    avatarInterfaces = (INamedUserAvatar, INewUserAvatar)
    self.factory.portal.login(creds, None, *avatarInterfaces).addCallback(
        self._loginSucceeded).addErrback(
        self._loginFailed)

def _loginSucceeded(self, avatarInfo):
    avatar, avatarInterface, self.logout = avatarInfo
    if avatarInterface == INewUserAvatar:
        self.transport.write("What's your full name? ")
        self.currentCommand = "fullname"
        self.avatar = avatar
    else:
        self._gotNamedUser(avatar)

def handle_fullname(self, fullname):
    namedUserAvatar = self.avatar.setName(fullname)
    self._gotNamedUser(namedUserAvatar)

def _gotNamedUser(self, avatar):
    self.transport.write("Welcome %s!\r\n" % avatar.fullname)
    defer.maybeDeferred(self.logout).addBoth(self._logoutFinished)

def _logoutFinished(self, result):
    self.transportloseConnection( )

def _loginFailed(self, failure):
    self.transport.write("Denied: %s.\r\n" % failure.getErrorMessage( ))

```

```

        self.transport.loseConnection( )

class NamedUserLoginFactory(protocol.ServerFactory):
    protocol = NamedUserLoginProtocol

    def __init__(self, portal):
        self.portal = portal

users = {
    'admin': 'Admin User',
}

passwords = {
    'admin': 'aaa',
    'user1': 'bbb',
    'user2': 'ccc'
}

portal = portal.Portal(MultiAvatarRealm(users))
portal.registerChecker(PasswordDictChecker(passwords))
factory = NamedUserLoginFactory(portal)
reactor.listenTCP(2323, factory)
reactor.run( )

```

When you run `multiavatar.py`, it will start up a server on port 2323. This server uses the same simple protocol as the previous examples in this chapter, but with one addition: if you log in as a user who it hasn't seen before, it will ask you for your full name. This information won't be required for subsequent logins, as it will remember the name you entered the first time:

```

$ telnet localhost 2323
Trying 127.0.0.1...
Connected to sparky.
Escape character is '^]'.

```

```
User Name: user1
Password: bbb
What's your full name? Abe Fettig
Welcome Abe Fettig!
Connection closed by foreign host.
```

```
$ telnet localhost 2323
Trying 127.0.0.1...
Connected to sparky.
Escape character is '^]'.
User Name: user1
Password: bbb
Welcome Abe Fettig!
Connection closed by foreign host.
```

6.3.2. How Does That Work?

The server protocol and realm in [Example 6-3](#) are both aware that this realm uses two different types of avatar. When the `MultiAvatarRealm.requestAvatar` method is called, it checks to see whether the avatar is listed in `self.users`, the dictionary of users it knows about. If it finds the user information, it returns a tuple containing `INamedUserAvatar`, a `NamedUserAvatar` object for that user, and a logout function. So far, this is identical to the behavior of `TestRealm` in [Example 6-1](#) at the beginning of this chapter.

If `requestAvatar` is called with an unknown avatar ID, though, `MultiAvatarRealm` returns a different type of avatar. The `INewUserAvatar` interface and `NewUserAvatar` class represent the actions available to users from whom the server needs more information. Unlike the regular `NamedUserAvatar` object, `NewUserAvatar` doesn't provide a `fullname` attribute: the server doesn't know this user's name. Instead it provides the `setName` method, providing a way to store the user's name. As a convenience, `setName` returns a `NamedUserAvatar`. This step makes it possible to take a `NewUserAvatar` object and upgrade to a `NamedUserAvatar` by supplying the user's full name.

The `NamedUserProtocol` in [Example 6-3](#) calls `portal.login` with the user's credentials and two interface arguments, `INamedUserAvatar` and `INewUserAvatar`. When it gets the results, it checks the first item in the tuple to see which interface is being used. If it is `INewUserAvatar`, the server asks the client for his full name, and calls the avatar's `setName` method. In this case, that's all the information that was missing. The `NewUserAvatar` stores the user's name for future use, and the server can proceed with the rest of the session (brief as it is).

[< Day Day Up >](#)

6.4. Using Authentication with Perspective Broker

[Example 5-8](#) in [Chapter 5](#) demonstrated Perspective Broker without any authentication in place. In the real world, though, you probably don't want to give just anyone remote access to objects in your application. You usually need to have an authentication layer in place to control who gets in, and what they're allowed to do.

Perspective Broker lets you perform authentication by integrating with `twisted.cred`. Adding authentication makes Perspective Broker live up to its name: it can provide different perspectives to different users, hiding or exposing objects and methods depending on the user's permissions.

6.4.1. How Do I Do That?

Create a realm that returns `pb.Avatar` objects. Each avatar should have methods prefixed with `perspective_` that the user of that avatar will be allowed to run. Connect the realm to a `Portal`, add credentials checkers, and pass the `Portal` to a `pb.PBServerFactory`. [Example 6-4](#) demonstrates a Perspective Broker server with authentication.

Example 6-4. `pbcred.py`

```
from twisted.spread import pb

from twisted.cred import checkers, portal

from zope.interface import implements

class TodoList:

    def __init__(self):

        self.items = []

    def listItems(self):

        return self.items[:] # return copy of list

    def addItem(self, item):

        self.items.append(item)

        return len(self.items) - 1

    def deleteItem(self, index):
```

```
del(self.items[index])
```

```
class UserPerspective(pb.Avatar):
```

```
    def __init__(self, todoList):
```

```
        self.todoList = todoList
```

```
    def perspective_listItems(self):
```

```
        return self.todoList.listItems( )
```

```
class AdminPerspective(UserPerspective):
```

```
    def __init__(self, todoList):
```

```
        self.todoList = todoList
```

```
    def perspective_addItem(self, item):
```

```
        return self.todoList.addItem(item)
```

```
    def perspective_deleteItem(self, index):
```

```
        return self.todoList.deleteItem(index)
```

```
class TestRealm(object):
```

```
    implements(portal.IRealm)
```

```
    def __init__(self, todoList):
```

```
        self.todoList = todoList
```

```
    def requestAvatar(self, avatarId, mind, *interfaces):
```

```
        if not pb.IPerspective in interfaces:
```

```
            raise NotImplementedError, "No supported avatar interface."
```

```
        else:
```

```
            if avatarId == 'admin':
```

```
                avatar = AdminPerspective(self.todoList)
```

```
            else:
```

```
                avatar = UserPerspective(self.todoList)
```

```
            return pb.IPerspective, avatar, lambda: None
```

```

if __name__ == "__main__":
    import sys

    from twisted.internet import reactor

    p = portal.Portal(TestRealm(ToDoList( )))

    p.registerChecker(
        checkers.InMemoryUsernamePasswordDatabaseDontUse(
            admin='aaa',
            guest='bbb'))

    reactor.listenTCP(8789, pb.PBServerFactory(p))

    reactor.run( )

```

To test this server, write a Perspective Broker client that supports authentication. Create a `PBClientFactory` and call `login` (instead of `getRootObject`) with your user's credentials as the only argument. [Example 6-5](#) is a pb client that uses a username and password for authentication.

Example 6-5. `pbcred_client.py`

```

from twisted.spread import pb

from twisted.internet import reactor

from twisted.cred import credentials

class PbAuthTester(object):
    def __init__(self, credentials):
        self.credentials = credentials

        self.server = None

    def runTests(self):
        self.connect( ).addCallback(
            lambda _: self.listItems( ).addCallback(
                lambda _: self.addItem( ).addErrback(
                    self._catchFailure).addCallback(
                        lambda _: reactor.stop( ))

```

```

def connect(self):
    factory = pb.PBClientFactory( )
    reactor.connectTCP("localhost", 8789, factory)
    return factory.login(self.credentials).addCallback(self._connected)

def _connected(self, rootObj):
    self.server = rootObj

def listItems(self):
    return self.server.callRemote("listItems").addCallback(self._gotList)

def _gotList(self, list):
    print "%i items in TODO list." % (len(list))

def addItem(self):
    return self.server.callRemote(
        "addItem", "Buy groceries").addCallback(
        self._addedItem)

def _addedItem(self, result):
    print "Added 1 item."

def _catchFailure(self, failure):
    print "Error:", failure.getErrorMessage( )

if __name__ == "__main__":
    import sys
    username, password = sys.argv[1:3]
    creds = credentials.UsernamePassword(username, password)
    tester = PbAuthTester(creds)
    tester.runTests( )
    reactor.run( )

```

Run *pbcred.py* to start the server. *pbcred_client.py* takes a username and password as arguments. Try it with the name and password **admin** and **aaa**. It will list the number of current items on the server, and then add an item:

```
$ python pbcred_client.py admin aaa
Getting item list...
0 items in list.
Adding new item...
Added 1 item.
```

Then try again using the username **guest** and password **bbb**. You'll be able to get the item count, but you'll get an error trying to add an item:

```
$ python pbcred_client.py guest bbb
Getting item list...
1 items in list.
Adding new item...
Error: UserPerspective instance has no attribute 'perspective_addItem'
```

This is because the `guest` user does not get the same perspective as `admin`. The `guest` user's perspective is read-only, and doesn't include methods for adding or deleting items.

6.4.2. How Does That Work?

The server provides the four standard objects needed for Twisted authentication: avatars, a realm, a portal, and credentials checkers. The `TestRealm` returns either a `UserPerspective` avatar or a `AdminPerspective` avatar, depending on the user's name. The `admin` user will get an `AdminPerspective` avatar, which includes the additional methods `perspective_addItem` and `perspective_deleteItem`. `UserPerspective` and `AdminPerspective` both inherit from `pb.Avatar`, and provide methods prefixed with `perspective_`. `pb.Avatar` objects implement the `pb.IPerspective` interface; the Perspective Broker server will pass this interface to `Portal.login` to request a `pb.Avatar`.

For the sake of simplicity, [Example 6-5](#) uses the `InMemoryPasswordDatabaseDontUse` credentials checker class, which is included in `twisted.cred.checkers` for use in test programs only. In production, you'd use a real credentials checker that authenticated usernames and passwords against a file,

database, or another service.

To use authentication, the client calls `PBClient.login` instead of calling `PBClient.getRootObject` directly. The `login` function attempts to log in using a set of credentials and then returns a reference to a `pb.Avatar` object on the server representing that user's perspective.

[< Day Day Up >](#)

Chapter 7. Mail Clients

You're probably reading this chapter because you want to write a mail client, or to extend an existing application to work with email. This is a common desire. In fact, as Jamie Zawinski put it in his Law of Software Envelopment:

Every program attempts to expand until it can read mail. Those programs which cannot so expand are replaced by ones which can.

That statement was probably made somewhat tongue-in-cheek, but it does make a point about the importance of email. Email is ubiquitous. Reading and writing email is a vital part of many people's communication, both at work and in their personal lives. In addition, users and administrators have come to expect emailing as an interface to communicate with their applications. When an application needs to remind users of lost passwords, provide a simple way to update a bug-tracking system, or allow for uploading pictures from mobile phones, email integration becomes a requirement.

Twisted provides support for working with email through all of the standard protocols commonly used today: SMTP, POP3, and IMAP.

7.1. Downloading Mail from a POP3 Server

One of the most widely used email protocols is the Post Office Protocol version 3 (POP3). POP3 does one thing, and does it well: it allows a user to log into a mail server and download her messages, optionally deleting the copies on the server afterwards. POP3 is a simple enough protocol that you can talk to a server manually, through *Telnet*, as shown in [Example 7-1](#).

Example 7-1. Communicating with a POP3 server using Telnet

```
$ telnet pop.myisp.com 110
Connected to pop.myisp.com.
Escape character is '^]'.
+OK dovecot ready.
user myusername
+OK
pass mypassword
+OK Logged in.
list
+OK 2 messages:
1 1385
2 100
.
retr 2
+OK 100 octets
From: somebody@example.com
To: abe@fettig.net
Subject: Hello

How's the weather up there in Maine?
.
quit
+OK Logging out.
```

Connection closed by foreign host.

But even with such a simple protocol, it's nice to be saved the effort of writing your own implementation from scratch. Twisted comes with a `Protocol` class that implements POP3:

`twisted.mail.pop3client.POP3Client`. You can use it in your programs to download mail from a POP3 server.

7.1.1. How Do I Do That?

Create a subclass of `POP3Client`. Use the methods `login`, `listSize`, `listUidl`, `retrieve`, and `quit` to send commands to the server and get `Deferreds` that will be called back with the server's response. [Example 7-2](#) demonstrates a POP3 client that logs into a server, retrieves the list of available messages, and then downloads each message to an mbox file.

Example 7-2. `pop3download.py`

```
from twisted.mail import pop3client
from twisted.internet import reactor, protocol, defer
from cStringIO import StringIO
import email

class POP3DownloadProtocol(pop3client.POP3Client):
    # permit logging without encryption
    allowInsecureLogin = True

    def serverGreeting(self, greeting):
        pop3client.POP3Client.serverGreeting(self, greeting)
        login = self.login(self.factory.username, self.factory.password)
        login.addCallback(self._loggedIn)
        login.chainDeferred(self.factory.deferred)

    def _loggedIn(self, result):
        return self.listSize().addCallback(self._gotMessageSizes)

    def _gotMessageSizes(self, sizes):
```

```

    retrievers = []

    for i in range(len(sizes)):
        retrievers.append(self.retrieve(i).addCallback(
            self._gotMessageLines))

    return defer.DeferredList(retrievers).addCallback(
        self._finished)

def _gotMessageLines(self, messageLines):
    self.factory.handleMessage("\r\n".join(messageLines))

def _finished(self, downloadResults)
    return self.quit( )

class POP3DownloadFactory(protocol.ClientFactory):
    protocol = POP3DownloadProtocol

    def __init__(self, username, password, output):
        self.username = username
        self.password = password
        self.output = output
        self.deferred = defer.Deferred( )

    def handleMessage(self, messageData):
        parsedMessage = email.message_from_string(messageData)
        self.output.write(parsedMessage.as_string(unixfrom=True))
        self.output.write('\r\n')

    def clientConnectionFailed(self, connection, reason):
        self.deferred.errback(reason)

import sys, getpass

def handleError(error):

```

```

print error

print >> sys.stderr, "Error:", error.getMessage( )

reactor.stop( )

if __name__ == "__main__":

    if len(sys.argv) != 4:

        print "Usage: %s server username output.mbox" % sys.argv[0]

        sys.exit(1)

    else:

        server, username, outputfile = sys.argv[1:]

        password = getpass.getpass("Password: ")

        f = POP3DownloadFactory(username, password, file(outputfile, 'w+b'))

        f.deferred.addCallback(

            lambda _: reactor.stop( )).addErrback(

                handleError)

        reactor.connectTCP(server, 110, f)

        reactor.run( )

```

Run *pop3download.py* with three arguments: the server, the login username, and the output filename. It will prompt you for your password, log in to the server, download all the messages, and write them to the output file in the Unix-standard *mbox* format:

```
$ python pop3download.py pop.myisp.com mylogin pop-messages.mbox
```

```
Password:
```

```
Downloading message 1 of 31
```

```
Downloading message 2 of 31
```

```
Downloading message 3 of 31
```

```
...
```

```
Downloading message 30 of 31
```

```
Downloading message 31 of 31
```



Note that the contents of your output file will be overwritten every time you run `pop3download.py`—be careful not to clobber any important messages!

7.1.2. How Does That Work?

There are two main classes in `pop3download.py`: `POP3DownloadProtocol` and `POP3DownloadFactory`. As a standard factory, a `POP3DownloadFactory` will create a `POP3DownloadProtocol` object when a connection to the server is established. The two classes then work together. The `POP3DownloadProtocol` communicates with the server, and passes each downloaded message to the `POP3DownloadFactory` by calling `self.factory.handleMessage`. The `POP3DownloadFactory` then writes the message data to the output file. The `POP3DownloadProtocol` will also call either `callback` or `errback` on the `POP3DownloadFactory`'s deferred object, to indicate that the process of downloading all messages has completed successfully, or failed with an error.



Example 7-2 uses the `POP3Client` class from `twisted.mail.pop3client`. There's another `POP3Client` in `twisted.mail.pop3`, but this is an old, deprecated class with a much less friendly API. Use the `twisted.mail.pop3client` version instead.

`POP3Client`, which `POP3DownloadProtocol` inherits from, provides high-level methods for sending POP3 commands, such as `login`, `listSize`, `listUidl`, `retrieve`, `delete`, and `quit`. The action in `POP3DownloadProtocol` starts in `serverGreeting`, which is called when the server sends the POP3 WELCOME message. `POP3Client.login` is an intelligent method that logs in to the server using the best available login technique. If the server supports APOP authentication, which doesn't send the password in plain text, `login` will use APOP; otherwise, it will log in using the plain-text username and password. `POP3DownloadProtocol` adds `self._loggedIn` as the callback handler for `login`, and then uses `chainDeferred` to connect the result of logging in to `self.factory.deferred`.

The `self._loggedIn` method responds to the successful login by calling `POP3Client.listSize`. This returns a `Deferred` that will be called back with a list of message sizes. Notice that `_loggedIn` returns this `Deferred` result, which keeps everything happening in the context of the `Deferred` from `self.login`, which is chained to `self.factory.deferred`. Therefore the result of `listSize`, or any exception that might occur, will be passed up to `self.factory.deferred`.

The callback handler for `listSize`, `self._gotMessageSizes`, requests each message from the server by calling `POP3Client.retrieve` with the message index number. You can send many retrieve requests at once, as `POP3DownloadClient` does, and `POP3Client` will automatically queue them up and send them one at a time. `_gotMessageSizes` keeps a list of all the calls it's made to retrieve, and then returns a `defer.DeferredList` wrapping the list. The `DeferredList` will call back after all the messages have been downloaded. Once again, `_gotMessageSizes` returns a `Deferred`, which keeps everything happening inside the callback chain of the original call to `self.login`.

The `_gotMessageLines` function is the callback handler used for each call to `retrieve`. It takes a list of the lines received from the server, joins them into a single string, and passes the message to `self.factory.handleMessage`.

Note that messages aren't being deleted from the server, which means they will still be available the next time you connect. If you wanted to delete the server's copy of a message, send the POP3 `DELETE` command by calling `self.delete(messageNumber)` for each message you want to delete. The POP3 `DELETE` command doesn't delete messages instantly; it queues up the list of messages to delete and then processes them after you quit. So if you send `delete` for several messages, and then something happens to your connection before you call `quit`, the messages will remain on the server.

The `POP3DownloadFactory` used in [Example 7-2](#) takes three arguments at initialization: the username, the password, and the output file to use for the downloaded messages. Its `handleMessage` function uses Python's `email` module to parse the message and write it to the output file in `mbox` format.



The `unixfrom=True` argument that you see in `handleMessage`, in the call to `parsedMessage.as_string`, starts the message with a line in the form "From emailaddress timestamp," which the `mbox` format uses to determine where one message ends and a new message begins. Including that argument is key to generating an `mbox` file .

7.1.3. What About...

... using SSL (the Secure Socket Layer) for encrypted connections? Many POP servers support SSL as a secure alternative to regular TCP connections. By encrypting all the data passing between client and server, SSL keeps your password and email protected from anyone who might be snooping on your network connection.

To use POP3 over SSL , just replace `reactor.connectTCP` with `reactor.connectSSL`, and connect to port 995 instead of 110:

```
from twisted.internet import ssl

reactor.connectSSL(server, 995, factory, ssl.ClientContextFactory( ))
```

`reactor.connectSSL` takes one additional argument, a `twisted.internet.ssl.ClientContextFactory` object. (The `ClientContextFactory` object can be used for advanced SSL tasks, like using custom certificates, but in most situations you just need to create it and pass it to `reactor.connectSSL`.)

[< Day Day Up >](#)

7.2. Sending Mail Using SMTP

The standard protocol for sending mail on the Internet is the Simple Mail Transfer Protocol (SMTP). SMTP allows one computer to transfer email messages to another computer using a standard set of commands. Mail clients use SMTP to send outgoing messages, and mail servers use SMTP to forward messages to their final destination. The current specification for SMTP is defined in RFC 2821 (<http://www.faqs.org/rfcs/rfc2821.html>).

Twisted supports SMTP, using the `twisted.protocols.smtp` module. In addition to SMTP Protocol classes, this module has handy functions for sending mail. Combined with the `email` module in the Python standard library, you can create and send messages (even complex MIME messages with attachments) with only a few lines of code.

7.2.1. How Do I Do That?

Create your message using Python's email package. Then use the `twisted.protocols.smtp.sendmail` function to send the message using SMTP, as demonstrated in [Example 7-3](#).

Example 7-3. `smtpsend.py`

```
from twisted.protocols import smtp
from twisted.internet import reactor, defer
from email.MIMEBase import MIMEBase
from email.MIMEMultipart import MIMEMultipart
from email import Encoders
import sys, mimetypes, os

def buildMessage(fromaddr, toaddr, subject, body, filenames):
    message = MIMEMultipart( )
    message['From'] = fromaddr
    message['To'] = toaddr
    message['Subject'] = subject
    textPart = MIMEBase('text', 'plain')
    textPart.set_payload(body)
    message.attach(textPart)
    for filename in filenames:
```

```

    # guess the mimetype
    mimetype = mimetypes.guess_type(filename)[0]

    if not mimetype: mimetype = 'application/octet-stream'
    maintype, subtype = mimetype.split('/')
    attachment = MIMEBase(maintype, subtype)

    attachment.set_payload(file(filename).read( ))

    # base64 encode for safety
    Encoders.encode_base64(attachment)

    # include filename info
    attachment.add_header('Content-Disposition', 'attachment',
                          filename=os.path.split(filename)[1])

    message.attach(attachment)

return message

def sendComplete(result):
    print "Message sent."
    reactor.stop( )

def handleError(error):
    print >> sys.stderr, "Error", error.getErrorMessag( )
    reactor.stop( )

if __name__ == "__main__":
    if len(sys.argv) < 5:
        print "Usage: %s smtp host fromaddr toaddr file1 [file2, ...]" % (
            sys.argv[0])
        sys.exit(1)

    smtp host = sys.argv[1]
    fromaddr = sys.argv[2]
    toaddr = sys.argv[3]
    filenames = sys.argv[4:]
    subject = raw_input("Subject: ")

```

```

body = raw_input("Message (one line): ")

message = buildMessage(fromaddr, toaddr, subject, body, filenames)

messageData = message.as_string(unixfrom=False)

sending = smtp.sendmail(smtpost, fromaddr, [toaddr], messageData)

sending.addCallback(sendComplete).addErrback(handleError)

reactor.run( )

```

Run `smtpsend.py` from the command line with four or more arguments: the name of your SMTP server, the address the message is from, the address it should be delivered to, and one or more files to attach. It will ask you for a subject line and single-line message body, and then create and send the email:

```

$ python smtpsend.py smtp.myisp.com me@myisp.com \
> user@otherisp.com logo.png homepage.html

Subject: Project Files

Message (one line): Here are those files I was talking about.

Message sent.

```

7.2.2. How Does That Work?

The `twisted.protocols.smtp.sendmail` function is a simple, handy way to send email using Twisted. It encapsulates all the work of connecting to the SMTP server, telling it the address the message is coming from and the address it should be delivered to, and transferring the message data. Call the `sendmail` function with four arguments: the SMTP server hostname, the address the message is coming from, a list of addresses it should be delivered to, and the message data itself (either as a string or a file-like object). It returns a `Deferred` that will call back when the transfer is complete.

There's one potentially tricky thing about `smtp.sendmail` that you should be aware of: if you're sending a message to multiple recipients, a successful callback means that the server accepted the message for delivery to at least one of them. If you're sending the message to more than one address, therefore, be sure to check the return value passed to your callback function. This value will be a tuple in the form `(numberDelivered, addressInfo)`, where `numberDelivered` is a count of the number of recipients for which the server accepted the message, and `addressInfo` is a list of tuples in the format `(address, responseCode, responseMessage)`. If you're sending a message to a single address, as in [Example 7-3](#), you don't have to check the return value; the callback itself indicates that the message was accepted for the single recipient it was addressed to.



The `twisted.protocols.smtp` module provides lower-level classes that can be used in SMTP clients, including SMTP-specific `Protocol` and `Factory` objects. But in most cases, the `sendmail` function will do everything you need in one line of code.

Because the `sendmail` function handles all the SMTP work, most of the code in `smtpsend.py` is involved with constructing the email message that will be sent. The Python `email` package contains modules for constructing messages of various types, and the `buildMessage` function uses two of them: `MIMEMultipart`, which creates a message of type `multipart/mixed` (suitable for storing a message body and attachments), and `MIMEBase`, which can hold any type of message data. The `buildMessage` function creates an `email.MIMEMultipart.MIMEMultipart` object called `message`. Then it iterates through the list of filenames and creates a `MIMEBase` object for each one containing the file's data. It uses the Python `mimetypes` module to guess the file type (based on the filename's extension). In addition, it Base64-encodes the attachment contents, which allows binary data to be represented as ASCII text (a requirement for passing through most mail servers).

Once the attachments have been added, the message is ready to be sent. `smtpsend.py` passes the message data to `smtp.sendmail`, along with the hostname of the SMTP server and the sender and recipient addresses. It sets up the callback and errback functions, and it hands off control to the reactor.

[< Day Day Up >](#)

7.3. Looking Up the SMTP Server for a Domain

Typically, users configure their mail programs to send all mail through a single SMTP server set up by the network administrator. This server is sometimes referred to as a smart host because it has the ability to look at an email address, query the Domain Name System (DNS) enough to find out which mail server handles mail for that domain, and then deliver the message.

The server that accepts mail for a domain is sometimes at an obvious location, like mail.domain.com, but it can be any server, even one in a different domain. Domain administrators list their mail servers in their public DNS information by adding MX (short for Mail Exchange) records that list the SMTP servers that will accept mail addressed to that domain. For example, the DNS records for oreilly.com list two MX records, `smtp1.oreilly.com` and `smtp2.oreilly.com`. So when you want to send an email to somebody@oreilly.com, it must be delivered to one of those two servers.

Typically, programs that send mail using SMTP are configured to use a smart host. The hostname of the outgoing SMTP server is stored in a configuration file, and all mail, regardless of the domain, is sent through that server. However, there are times when you might want to write a program that doesn't rely on a smart host. For example, you might want your application to be able to move between networks without having to be told where the local SMTP server is. Or you could actually be developing your own mail server. (For much more on mail servers, see [Chapter 8](#).) In these cases, you'll need to query the DNS system to find the appropriate server to use for each address.

7.3.1. How Do I Do That?

Create a `twisted.mail.relaymanager.MXCalculator` object. Use its `getMX` method to look up the appropriate mail server for each address to which you need to deliver mail, as shown in [Example 7-4](#).

Example 7-4. `smtplookup.py`

```
from twisted.mail import relaymanager

mxCalc = relaymanager.MXCalculator()

def getSMTPServer(emailAddress):
    username, domain = emailAddress.split("@")
    return mxCalc.getMX(domain).addCallback(_gotMXRecord)

def _gotMXRecord(mxRecord):
```

```

    return mxRecord.exchange

if __name__ == "__main__":
    from twisted.internet import reactor
    import sys
    address = sys.argv[1]

    def printServer(server):
        print server
        reactor.stop( )

    def handleError(error):
        print >> sys.stderr, error.getErrorMessage( )
        reactor.stop( )

    getSMTPServer(address).addCallback(printServer).addErrback(handleError)
    reactor.run( )

```

Run `smtplookup.py` with an email address as its only argument. It will print out the name of a server that accepts mail for the address's domain:

```

$ python smtplookup.py user@oreilly.com
smtp1.oreilly.com

$ python smtplookup.py abe@fettig.net
barclay.textdrive.com

```

7.3.2. How Does That Work?

`smtplookup.py` creates a `twisted.mail.relaymanager.MXCalculator` object called `mxCalc`. Note that it is created at the module level, instead of inside the `getSMTPServer` function; this will allow for the `MXCalculator` to use cached results if the same domain is looked up more than once.

The `getSMTPServer` function extracts the domain from the email address, and then returns the `Deferred` result of `mxCalc.getMX(domain)`, while adding `_gotMXRecord` as a callback handler. The `_gotMXRecord` function does some simple filtering on the result of `getMX`, taking the result (a `twisted.protocols.dns.Record_MX` object) and returning just the `exchange` attribute, which contains the hostname of the mail server. This technique of adding an extra callback handler up front can be quite useful, enabling you to process or transform the result of a deferred function.

[< Day Day Up >](#)

7.4. Listing Mailboxes on an IMAP Server

The Internet Message Access Protocol (IMAP) was designed to allow for remote access, storage, and management of email messages. This ability to store messages on a central server is useful for a couple of reasons. First, it makes email available in more than one place. If your mail is on an IMAP server, you can switch between your desktop and your laptop and still access your mail. Second, it makes it easier to administer email for workgroups and corporations. Instead of having to track and back up email across hundreds of hard drives, it can be managed in a single, central place.

The specification for the current version of IMAP (Version 4, Revision 1) is defined in RFC 3501 (<http://www.faqs.org/rfcs/rfc3501.html>). IMAP is a powerful but complicated protocol, and the RFC takes up more than 100 pages. It's the kind of protocol that would be a ton of work to implement yourself. Fortunately, the Twisted developers have written a complete IMAP implementation, which provides a nice API for working with IMAP servers. This lab demonstrates how to log in to an IMAP server and get a list of available mailboxes.

7.4.1. How Do I Do That?

Use a subclass of `imap4.IMAP4Client` as your `Protocol`. In the `serverGreeting` function, call `self.login` with a username and password. Once successfully logged in, call `self.list` to get a list of the available mailboxes (see [Example 7-5](#)).

Example 7-5. `imapfolders.py`

```
from twisted.protocols import imap4
from twisted.internet import protocol, defer

class IMAPFolderListProtocol(imap4.IMAP4Client):

    def serverGreeting(self, capabilities):
        login = self.login(self.factory.username, self.factory.password)
        login.addCallback(self._ _loggedIn)
        login.chainDeferred(self.factory.deferred)

    def _ _loggedIn(self, results):
        return self.list("", "*").addCallback(self._ _gotMailboxList)

    def _ _gotMailboxList(self, list):
```

```

    return [boxInfo[2] for boxInfo in list]

def connectionLost(self, reason):
    if not self.factory.deferred.called:
        # connection was lost unexpectedly!
        self.factory.deferred.errback(reason)

class IMAPFolderListFactory(protocol.ClientFactory):
    protocol = IMAPFolderListProtocol

    def __init__(self, username, password):
        self.username = username
        self.password = password
        self.deferred = defer.Deferred()

    def clientConnectionFailed(self, connection, reason):
        self.deferred.errback(reason)

if __name__ == "__main__":
    from twisted.internet import reactor
    import sys, getpass

    def printMailboxList(list):
        list.sort()
        for box in list:
            print box
        reactor.stop()

    def handleError(error):
        print >> sys.stderr, "Error:", error.getErrorMessage()
        reactor.stop()

    if not len(sys.argv) == 3:

```

```

    print "Usage: %s server login" % sys.argv[0]

    sys.exit(1)

server = sys.argv[1]
user = sys.argv[2]
password = getpass.getpass("Password: ")
factory = IMAPFolderListFactory(user, password)
factory.deferred.addCallback(
    printMailboxList).addErrback(
    handleError)
reactor.connectTCP(server, 143, factory)
reactor.run( )

```

Run *imapfolders.py* with two arguments: the IMAP server and your login username. It will prompt you for your password, log you in to the server, and then download and print a list of your mailboxes:

```

$ python imapfolders.py imap.myisp.com mylogin

Password:
INBOX
Archive
Drafts
Mailing Lists
Mailing Lists/Twisted
Mailing Lists/Twisted Web
Sent
Spam
Trash

```

7.4.2. How Does That Work?

imapfolders.py uses the familiar pattern of a `ClientFactory` and `Protocol` working together. The `Protocol` communicates with the server, and the `ClientFactory` provides a `Deferred` that the

program uses to track the success or failure of the task at hand.

The `IMAPFolderListProtocol` class in `imapfolders.py` inherits from `IMAP4Client`, which provides a nice `Deferred`-based interface. Every IMAP command returns a `Deferred` that will be called back with the reply received from the server. The use of `Deferred`s makes it easy to run a series of commands, one after the other: have the callback handler for each command run the next command and return its `Deferred`.

There's one `Deferred` method used in `imapfolders.py` that hadn't been used in any of the previous examples: `chainDeferred`. The `chainDeferred` method is used when you want to take the results of one `Deferred` and pass them to another `Deferred`. The line `deferredOne.chainDeferred(deferredTwo)` is equivalent to:

```
deferredOne.addCallback(deferredTwo.callback)

deferredOne.addErrback(deferredTwo.errback)
```

The `IMAPFolderListProtocol` in `imapfolders.py` has its `serverGreeting` method called when the connection to the server is established and the server has indicated that it's ready to accept commands. In response to `serverGreeting`, it calls `self.login`, and sets up a callback to `self._loggedIn`. Then it uses `chainDeferred` to send the eventual results of `self.login` back to `self.factory.deferred`. The order of these steps is important. Because the callback to `self._loggedIn` is added before the call to `chainDeferred`, `self.factory.deferred` won't receive the direct result of `self.login`, but the result returned by `self._loggedIn`. As it turns out, `self._loggedIn` returns another `Deferred`, the result of `self.list`, which will be run through `self._gotMailboxList` to extract the mailbox names from the full response returned by the server. So `self.factory.deferred` is called back with the value that `IMAPFolderListProtocol` is supposed to provide: a list of mailbox names.

One of the most useful things about using `Deferred`s in this way is error handling. Remember how in [Example 7-2](#), the `POP3DownloadProtocol` had to check the results of every command, and call a function to let the factory know there was an error? There's none of that here. Since `self.list` is called as part of the event handler for `self.login`, and `self.login` is chained to `self.factory.deferred`, `self.factory.deferred` will receive any error that occurs in either of these steps.

[< Day Day Up >](#)

7.5. Downloading Messages from an IMAP Mailbox

This lab demonstrates how to download copies of all the messages in an IMAP mailbox. You can do this using three methods of `IMAP4Client`: `select`, `fetchUID`, and `fetchMessage`.

7.5.1. How Do I Do That?

Create a subclass of `twisted.protocols.imap4.IMAP4Client`. Call `select` to select the mailbox you want to work with. Call `fetchUID` to retrieve the list of message identifiers for the mailbox, and then use `fetchMessage` to download each message, as demonstrated in [Example 7-6](#).

Example 7-6. `imapdownload.py`

```
from twisted.protocols import imap4
from twisted.internet import protocol, defer
import email

class IMAPDownloadProtocol(imap4.IMAP4Client):

    def serverGreeting(self, capabilities):

        login = self.login(self.factory.username, self.factory.password)
        login.addCallback(self._ _loggedIn)
        login.chainDeferred(self.factory.deferred)

    def _ _loggedIn(self, result):

        return self.select(self.factory.mailbox).addCallback(
            self._ _selectedMailbox)

    def _ _selectedMailbox(self, result):

        # get a list of all message IDs
        allMessages = imap4.MessageSet(1, None)
        return self.fetchUID(allMessages, True).addCallback(
```

```
self._ _gotUIDs)
```

```
def _ _gotUIDs(self, uidResults):
    self.messageUIDs = [result['UID'] for result in uidResults.values( )]
    self.messageCount = len(self.messageUIDs)
    print "%i messages in %s." % (self.messageCount, self.factory.mailbox)
    return self.fetchNextMessage( )
```

```
def fetchNextMessage(self):
    if self.messageUIDs:
        nextUID = self.messageUIDs.pop(0)
        messageListToFetch = imap4.MessageSet(nextUID)
        print "Downloading message %i of %i" % (
            self.messageCount-len(self.messageUIDs), self.messageCount)
        return self.fetchMessage(messageListToFetch, True).addCallback(
            self._ _gotMessage)
    else:
        # all done!
        return self.logout( ).addCallback(
            lambda _: self.transportloseConnection( ))
```

```
def _ _gotMessage(self, fetchResults):
    messageData = fetchResults.values( )[0]['RFC822']
    self.factory.handleMessage(messageData)
    return self.fetchNextMessage( )
```

```
def connectionLost(self, reason):
    if not self.factory.deferred.called:
        # connection was lost unexpectedly!
        self.factory.deferred.errback(reason)
```

```
class IMAPDownloadFactory(protocol.ClientFactory):
    protocol = IMAPDownloadProtocol
```

```

def __init__(self, username, password, mailbox, output):
    self.username = username
    self.password = password
    self.mailbox = mailbox
    self.output = output
    self.deferred = defer.Deferred( )

def handleMessage(self, messageData):
    parsedMessage = email.message_from_string(messageData)
    self.output.write(parsedMessage.as_string(unixfrom=True))
    self.output.write('\r\n')

def clientConnectionFailed(self, connection, reason):
    self.deferred.errback(reason)

if __name__ == "__main__":
    from twisted.internet import reactor
    import sys, getpass

    def handleError(error):
        print >> sys.stderr, "Error:", error.getErrorMessage( )
        reactor.stop( )

    if len(sys.argv) != 5:
        usage = "Usage: %s server user mailbox outputfile" % (
            sys.argv[0])
        print >> sys.stderr, usage
        sys.exit(1)

    server = sys.argv[1]
    user = sys.argv[2]
    mailbox = sys.argv[3]
    outputfile = file(sys.argv[4], 'w+b')

```

```

password = getpass.getpass("Password: ")
factory = IMAPDownloadFactory(user, password, mailbox, outputfile)
factory.deferred.addCallback(lambda _: reactor.stop()).addErrback(
    handleError)
reactor.connectTCP(server, 143, factory)
reactor.run( )

```

Run *imapdownload.py* from the command line with four arguments: the IMAP server, your login, the mailbox from which messages should be downloaded, and the name of the file to which they will be written. It will print out a progress report as it downloads the messages:

```

$ python imapdownload.py imap.myisp.com mylogin Inbox imap-Inbox.mbox
Password:
31 messages in Inbox.
Downloading message 1 of 31
Downloading message 2 of 31
Downloading message 3 of 31
...
Downloading message 30 of 31
Downloading message 31 of 31

```

7.5.2. How Does That Work?

imapdownload.py retains the basic structure of *imapfolders.py* from the previous lab. A subclass of `IMAP4Client` communicates with the server, and a subclass of `ClientFactory` creates the protocol and provides a `Deferred` for tracking the success or failure of the operation.

The `IMAPDownloadProtocol` starts by calling `self.login` to log in. The callback handler for `self.login` is `self.__loggedIn`, which calls `self.select` to select the mailbox and return another `Deferred`. The callback handler for `self.select`, `self.__selectedMailbox`, creates an `imap4.MessageSet` object, which represents a set of messages. The `MessageSet` is initialized with the arguments `1` and `None`, which means that it represents the set of messages from message number `1` to the end of the mailbox. This `MessageSet` object is then passed to `self.fetchUID`, instructing the server to return a list of the unique message identifiers in that set of messages.

The callback function for `self.fetchUID` is `self._gotUIDs`, which sets the attributes `self.messageUIDs` and `self.messageCount`. Then it returns the deferred result of `self.fetchNextMessage`, which starts the process of downloading the messages one by one. To download the next available message, `fetchNextMessage` creates a `MessageSet` matching only that message's UID. Then the `MessageSet` is passed to `self.fetchMessage`, with the `uid` keyword set to `true` to tell the server that the `MessageSet` is referring to messages by UID, not sequence number. The callback for `self.fetchMessage` is `self._gotMessage`, which passes the message data to the factory by calling `self.factory.handleMessage`. `_gotMessage` then returns another call to `self.fetchNextMessage`. This process creates a loop where `fetchNextMessage` will continue to be called until there are no messages left to download, at which point it calls `self.logout` to log out, and drops the connection.

As shown in `IMAPFolderListProtocol` in the previous lab, all of the work done in `IMAPDownloadProtocol` happens in the context of callback handlers for `self.login`, which is chained to `self.factory.deferred`. If everything works as expected, `self.factory.deferred` will be called back with the result of the last function in the chain, `self.transport loseConnection`. And if any of the IMAP methods fail, `self.factory.deferred` will handle the error.

[< Day Day Up >](#)

Chapter 8. Mail Servers

This chapter is about one of Twisted's greatest strengths: running mail and news servers. Twisted includes modules that you can use to build SMTP, POP3, IMAP, and NNTP servers from scratch, which can be incredibly useful when you have a server application that needs to send, receive, or store email. Server email integration has traditionally required a heavyweight mail server, with a bunch of custom shell scripts to push and pull data between the mail server and your application. But by using Twisted, you can design a mail or news server that does exactly what you need, and that doesn't even require a separate process. This chapter shows you how.

8.1. Accepting Mail with SMTP

As described in [Chapter 7](#), SMTP is the Simple Mail Transfer Protocol, the basic means by which email messages are delivered on the Internet. SMTP is the most popular messaging protocol in use today: everyone uses email, and email uses SMTP.

This lab demonstrates how to write a simple SMTP server using Twisted. It shows how to accept SMTP connections, decide what to do with the incoming message based on the email address, and then process the message data.

8.1.1. How Do I Do That?

Write classes to implement the `smtp.IMessage` and `smtp.IMessageDelivery` interfaces. Then create a `Factory` that uses your implementation of `IMessageDelivery` to initialize the `smtp.SMTP` protocol. [Example 8-1](#) accepts email for all addresses in a given domain and stores the messages to *maildir* directories.

Example 8-1. smtpserver.py

```
from twisted.mail import smtp, maildir
from zope.interface import implements
from twisted.internet import protocol, reactor, defer
import os
from email.Header import Header

class MaildirMessageWriter(object):
    implements(smtp.IMessage)

    def __init__(self, userDir):
        if not os.path.exists(userDir): os.mkdir(userDir)
        inboxDir = os.path.join(userDir, 'Inbox')
        self.mailbox = maildir.MaildirMailbox(inboxDir)
        self.lines = []

    def lineReceived(self, line):
```

```

self.lines.append(line)

def eomReceived(self):
    # message is complete, store it
    print "Message data complete."
    self.lines.append('') # add a trailing newline
    messageData = '\n'.join(self.lines)
    return self.mailbox.appendMessage(messageData)

def connectionLost(self):
    print "Connection lost unexpectedly!"
    # unexpected loss of connection; don't save
    del(self.lines)

class LocalDelivery(object):
    implements(smtp.IMessageDelivery)

    def __init__(self, baseDir, validDomains):
        if not os.path.isdir(baseDir):
            raise ValueError, "'%s' is not a directory" % baseDir
        self.baseDir = baseDir
        self.validDomains = validDomains

    def receivedHeader(self, helo, origin, recipients):
        myHostname, clientIP = helo
        headerValue = "by %s from %s with ESMTP ; %s" % (
            myHostname, clientIP, smtp.rfc822date( ))
        # email.Header.Header used for automatic wrapping of long lines
        return "Received: %s" % Header(headerValue)

    def validateTo(self, user):
        if not user.dest.domain in self.validDomains:
            raise smtp.SMTPBadRcpt(user)
        print "Accepting mail for %s..." % user.dest

```

```

    return lambda: MaildirMessageWriter(
        self._getAddressDir(str(user.dest)))

def _getAddressDir(self, address):
    return os.path.join(self.baseDir, "%s" % address)

def validateFrom(self, helo, originAddress):
    # accept mail from anywhere. To reject an address, raise
    # smtp.SMTPBadSender here.
    return originAddress

class SMTPFactory(protocol.ServerFactory):
    def __init__(self, baseDir, validDomains):
        self.baseDir = baseDir
        self.validDomains = validDomains

    def buildProtocol(self, addr):
        delivery = LocalDelivery(self.baseDir, self.validDomains)
        smtpProtocol = smtp.SMTP(delivery)
        smtpProtocol.factory = self
        return smtpProtocol

if __name__ == "__main__":
    import sys
    mailboxDir = sys.argv[1]
    domains = sys.argv[2].split(",")
    reactor.listenTCP(25, SMTPFactory(mailboxDir, domains))
    from twisted.internet import ssl
    # SSL stuff here... and certificates...
    reactor.run( )

```

This example uses the SMTP standard TCP port 25, so it can receive mail from other servers. If you're already running another SMTP server, you'll need to stop it before you run *smtpserver.py*, to make port 25 available.

Also, most operating systems don't give ordinary users the right to run services on TCP ports below 1024, which are reserved for system services. So you'll have to run *smtpserver.py* as root or from an administrator account.

Run *smtpserver.py* with two arguments: the directory to use for storing messages and a comma-delimited list of domains for which to accept mail. You can tell it to handle mail for as many domains as you like, but for the purposes of this example, make one of them `localhost`:

```
$ python smtpserver.py mail_storage localhost,example.com
```


Now that the server is running, you can try sending some mail. In the real world, you'd run your SMTP server on an Internet-connected computer with a public IP address, where all the other SMTP servers in the world (including your ISP's SMTP server, which your regular email client is configured to use for outgoing mail) could connect to it. However, let's assume that you're running *smtpserver.py*, and the other examples in this chapter, on a computer that's behind the firewall on your local network. In this case, it's best to use an email client configured to send mail through `localhost`.



Mozilla Thunderbird (<http://mozilla.org/thunderbird>) is a great email client to use for testing your servers. Thunderbird is free, open source, and runs on all popular operating systems. It also supports multiple profiles, so you can keep your test settings and messages separate from your real email. To set up multiple profiles, run Thunderbird with the `-ProfileManager` flag.

Try sending a message to `test@localhost`, as shown in [Figure 8-1](#).

Figure 8-1. Sending a test email to a local SMTP server



Your server should print a couple of lines showing that it received the message:

```
Accepting mail for test@localhost...
```

```
Message data complete.
```

You can then take a look at the message file that was created. *smtpserver.py* writes messages in maildir format, where each mailbox is a directory with the subdirectories *new*, *cur*, and *tmp*, and each message is a file with a unique name. Message files in a maildir directory are initially stored in *new*, and then moved to *cur* to indicate that they've been read. If you told *smtpserver.py* to use *mail_storage* as the base directory for storing email, the message you sent should have a unique filename in the directory [mail_storage/test@localhost/Inbox/new](#). The contents of that file will be the message you sent:

```
$ cd mail_storage

$ ls

test@localhost

$ cd test@localhost

$ ls Inbox/new

1115584078.M4515569P19924Q4.sparky

$ cat Inbox/new/1115584078.M4515569P19924Q4.sparky

Received: by [127.0.0.1] from 127.0.0.1 with ESMTP ; Sun, 08 May 2005 16:27:58 -0400
Message-ID: <427E764E.1000900@localhost>
Date: Sun, 08 May 2005 16:27:58 -0400
From: Test User <abe@localhost>
User-Agent: Mozilla Thunderbird 1.0.2 (X11/20050404)
To: test@localhost
Subject: My Test Message

Testing my SMTP server!
```

8.1.2. How Does That Work?

The `smtp.SMTP Protocol` class provides a very clean, high-level interface. Instead of asking you respond directly to the commands coming from the client, `smtp.SMTP` asks you to give it an object implementing the `smtp.IMessageDelivery` interface. `smtp.IMessageDelivery` requires three methods: `receivedHeader`, `validateTo`, and `validateFrom`.

The `receivedHeader` method is used to generate a `Received:` header that will be added to an incoming email message. SMTP servers are responsible for adding a `Received` header when they accept a message; these headers can be used later to see the path the message took en route to being delivered.

`receivedHeader` takes three arguments. The first, `hello`, is a tuple containing two strings: the server name by which the client addressed the server when it said `HELO`, and the client's IP address. The second argument, `origin`, is an `smtp.Address` object identifying who the message is coming from. The third argument, `recipients`, is a list of `smtp.Address` objects identifying who the message is being delivered to. From all that information, `receivedHeader` is asked to return a simple response: a string containing a valid SMTP `Received` header.

According to RFC 821, the `Received` header should be in the following form:

```
Received: FROM domain BY domain [VIA link] [WITH protocol] [ID id] [FOR path] ;
timestamp
```

The `VIA`, `WITH`, `ID`, and `FOR` parts are optional. The `LocalDelivery` object used in [Example 8-1](#) has a basic implementation of `receivedHeader` that generates a valid header string.



Email headers may look simple, but it's a mistake to naively assume you can just return a string in the form `HeaderName: value`. What about long value strings that need to be properly wrapped? What about Unicode characters? If you haven't planned for these, you could end up generating corrupt emails. Fortunately, there's a class in the Python standard library, `email.Header.Header`, that will do all the work of generating proper headers for you. Don't forget to use it!

The next method required by `smtp.IMessageDelivery` is `validateFrom`. This method gives your server a chance to accept or reject messages based on the address it's coming from. For example, if you had an application that allowed users to post to their weblogs through email, you might use `validateFrom` to make sure the message was coming from the email address of a user who had permission to post. (Keep in mind, though, that this isn't a bulletproof security mechanism; it's trivially easy to forge the sending address on an email message.) `validateFrom` takes two arguments: a tuple with the hostname used in by the client when it said `HELO` and the client's IP address, and an `smtp.Address` object identifying the sender. In [Example 8-1](#), the `LocalDelivery` object has a `validateFrom` method that always returns the sender's address, indicating that it's willing to accept mail from that sender. To reject a sender, you'd raise an `smtp.SMTPBadSender` exception instead.

The third method of `smtp.IMessageDelivery` is the most important. `validateTo` takes a single `smtp.User` object (which contains the address of the recipient and information about where the message came from) as an argument. It then either raises an `smtp.SMTPBadRecipient` exception, or returns a function that returns an object implementing `smtp.IMessage`.

That's a little confusing, and worth repeating: `validateTo` should return a function that will return an object implementing `smtp.IMessage` when it is called (with no arguments). The easy way to handle this quirk of the `IMessageDelivery` API is to return `lambda: myObject` instead of `myObject`, as demonstrated in [Example 8-1](#).

The SMTP server in [Example 8-1](#) is a little different from the typical email server. It doesn't have a fixed list of users, but will accept mail for any address within one of its domains. As long as the domain is valid, it

assigns that user a directory in the form `baseDir/user@domain`, and passes the directory to a `MaildirMessageWriter` object, which implements `smtp.IMessage`.

`smtp.IMessage` defines an interface for receiving an email message. There are three functions in `smtp.IMessage`. The first, `lineReceived`, will be called once for each line of the incoming email message, with the line data (which does not include the trailing newline) as an argument. The second method, `eomReceived`, is called after the entire message has been received. Return a `Deferred` result from `eomReceived` to let the client know when the message has been processed successfully. The third method, `connectionLost`, is called only if the connection is broken while message data is being received, and indicates that your class should discard whatever incomplete data has been received so far.

In [Example 8-1](#), `MaildirMessageWriter` uses the `maildir.MaildirMailbox` class provided by `twisted.mail` to write to the `Inbox` maildir in each user's directory. It isn't necessary to check whether the `Inbox` directory exists; `maildir.MaildirMailbox` will create it automatically.

[< Day Day Up >](#)

8.2. Using SMTP as a User Interface

SMTP is more than just a protocol for routing messages between people; it can also be used for communications in which the recipient is a computer program. Many server applications use SMTP to allow people to publish information via email. By sending mail to a special address, users can post to their weblogs, add a page to a Wiki, or import image files into their photo sharing services. Offering an SMTP interface to your application makes getting data in and out as easy as sending and receiving email. This lets people use your application as part of their existing email workflow, which makes it more likely that they're actually going to use that program you worked so hard to write. SMTP is also supported by many mobile phones, so it can be an easy way to enable mobile access to your applications.

8.2.1. How Do I Do That?

[Example 8-2](#) shows how you might offer an SMTP interface to an application. *smtpgoogle.py* is an SMTP server that takes email as input and uses it to run a Google "I'm Feeling Lucky" search. Then it sends a reply containing the search result. The code is similar to the basic SMTP server in [Example 8-1](#), but with application-specific classes implementing `smtp.IMessage` and `smtp.IMessageDelivery`.

Example 8-2. *smtpgoogle.py*

```
from twisted.mail import smtp
from twisted.web import google, client
from zope.interface import implements
from twisted.internet import protocol, reactor, defer
import os, email, email.Utils
from email import Header, MIMEBase, MIMEMultipart, MIMEText

class GoogleQueryPageFetcher(object):
    def fetchFirstResult(self, query):
        """
        Given a query, finds the first Google result, and
        downloads that page. Returns a Deferred, which will
        be called back with a tuple containing
        (firstMatchUrl, firstMatchPageData)
```

```

"""
# the twisted.web.google.checkGoogle function does an
# "I'm feeling lucky" search on Google
return google.checkGoogle(query).addCallback(
    self._gotUrlFromGoogle)

def _gotUrlFromGoogle(self, url):
    # grab the page
    return client.getPage(url).addCallback(
        self._downloadedPage, url)

def _downloadedPage(self, pageContents, url):
    # return a tuple containing both the url and page data
    return (url, pageContents)

class ReplyFromGoogle(object):
    implements(smtp.IMessage)

    def __init__(self, address, upstreamServer):
        self.address = address
        self.lines = []
        self.upstreamServer = upstreamServer

    def lineReceived(self, line):
        self.lines.append(line)

    def eomReceived(self):
        message = email.message_from_string("\n".join(self.lines))
        fromAddr = email.Utils.parseaddr(message['From'])[1]
        query = message['Subject']
        searcher = GoogleQueryPageFetcher( )
        return searcher.fetchFirstResult(query).addCallback(
            self._sendPageToEmailAddress, query, fromAddr)

```

```

def _sendPageToEmailAddress(self, pageData, query, destAddress):
    pageUrl, pageContents = pageData
    msg = MIMEMultipart.MIMEMultipart( )
    msg['From'] = self.address
    msg['To'] = destAddress
    msg['Subject'] = "First Google result for '%s'" % query
    body = MIMEText.MIMEText(
        "The first Google result for '%s' is:\n\n%s" % (
            query, pageUrl))
    # create a text/html attachment with the page data
    attachment = MIMEBase.MIMEBase("text", "html")
    attachment['Content-Location'] = pageUrl
    attachment.set_payload(pageContents)
    msg.attach(body)
    msg.attach(attachment)

    return smtp.sendmail(
        self.upstreamServer, self.address, destAddress, msg)

def connectionLost(self):
    pass

class GoogleMessageDelivery(object):
    implements(smtp.IMessageDelivery)

    def __init__(self, googleSearchAddress, upstreamSMTPServer):
        self.googleSearchAddress = googleSearchAddress
        self.upstreamServer = upstreamSMTPServer

    def receivedHeader(self, helo, origin, recipients):
        myHostname, clientIP = helo
        headerValue = "by %s from %s with ESMTP ; %s" % (
            myHostname, clientIP, smtp.rfc822date( ))

```

```

# email.Header.Header used for automatic wrapping of long lines
return "Received: %s" % Header.Header(headerValue)

def validateTo(self, user):
    if not str(user.dest).lower( ) == self.googleSearchAddress:
        raise smtp.SMTPBadRcpt(user.dest)
    else:
        return lambda: ReplyFromGoogle(self.googleSearchAddress,
                                       self.upstreamServer)

def validateFrom(self, helo, originAddress):
    # accept mail from anywhere. To reject an address, raise
    # smtp.SMTPBadSender here.
    return originAddress

class SMTPServerFactory(protocol.ServerFactory):
    def __init__(self, googleSearchAddress, upstreamSMTPServer):
        self.googleSearchAddress = googleSearchAddress
        self.upstreamSMTPServer = upstreamSMTPServer

    def buildProtocol(self, addr):
        delivery = GoogleMessageDelivery(self.googleSearchAddress,
                                       self.upstreamSMTPServer)

        smtpProtocol = smtp.SMTP(delivery)

        smtpProtocol.factory = self

        return smtpProtocol

if __name__ == "__main__":
    import sys

    googleSearchAddress = sys.argv[1]
    upstreamSMTPServer = sys.argv[2]

    reactor.listenTCP(
        25, SMTPServerFactory(googleSearchAddress, upstreamSMTPServer))

```

```
reactor.run( )
```


Run *smtpgoogle.py* from the command line with two arguments. The first is the email address you want to use for Google searches: you'll send mail to this address to search Google, and you'll get a reply from this address with the result. The second argument is the upstream SMTP server you want to use for sending the reply emails; typically this is your ISP's mail server:

```
$ python smtpgoogle.py google@myhostname.mydomain smtp.myisp.com
```

If you're running this command behind a firewall, you might have to fake the address you use for Google searches in order to send the reply emails. The address `google@localhost`, for example, might be rejected by your upstream mail server as an invalid sender address. As long as you're using a mail client configured to send all mail through localhost, you should be able to use any address; *smtpgoogle.py* will use that address for Google searches, and refuse to accept mail for any other address.

Once the server is running, try sending an email to the address you specified. The subject of the email should be the query you want to send to Google. [Figure 8-2](#) shows a query email being sent.

Figure 8-2. Sending a query to the *smtpgoogle.py* search service



smtpgoogle.py should process your query and send a reply to whatever From: address you used when sending the email. Check your mail, and you should get an email similar to that in [Figure 8-3](#) with the first Google result.

Figure 8-3. Reply containing result of a Google search



8.2.2. How Does That Work?

Example 8-2 defines the `GoogleQueryPageFetcher` class, which does the work of finding the first Google result for a query and then downloading that page. The function `fetchFirstResult` returns a `Deferred` object that will be called back with a tuple containing the URL and contents of the first matching page.

The `ReplyFromGoogle` class takes this feature and makes it available to SMTP by implementing `smtp.IMessage`. The key is the `eomReceived` function, which is called once the entire message has been received. The `smtp.IMessage` interface says that `eomReceived` should return a `Deferred`. Because of this, `ReplyFromGoogle` is free to run a series of asynchronous operations while processing the email, as long as it eventually returns a successful value or raises an exception. Rather than just writing the message data to disk, `ReplyFromGoogle.eomReceived` runs the Google search and sets up a callback to take the search result and send it out by email. It constructs a message using classes in Python's `email` module, and sends it back to the address that the query came from.

This technique of doing all the work in the context of `eomReceived` is a good approach to use when you expect that it won't take more than a second or two to process the incoming message. At other times, you might need to do something that's going to take a while. In this case, you don't want to leave the SMTP client hanging there waiting for a response, especially because it will eventually get tired of waiting and time out. So you might choose to add the incoming message to a queue for processing, and to immediately return a successful result for `eomReceived`. If something goes wrong later, you can always send an email back to the sender informing them of what happened.

[< Day Day Up >](#)

8.3. Providing POP3 Access to Mailboxes

The POP3 protocol allows mail clients to periodically download new mail from a server. POP3 support is a requirement for most applications that store mail. It's also the easiest way to let people pull their messages out of your application and store them on their computer.

8.3.1. How Do I Do That?

To make a Twisted POP3 server, first write a class to represent a user's Inbox. This class should implement `twisted.mail.pop3.IMailbox`, which defines methods for reading and deleting messages from a mailbox. Then set up a `Portal` that checks each user's login credentials and gives them access to their Inbox. [Example 8-3](#) offers POP access to the maildir mailboxes created by the SMTP server in [Example 8-1](#).

Example 8-3. pop3server.py

```
from twisted.mail import pop3, maildir
from twisted.cred import portal, checkers, credentials, error as credError
from twisted.internet import protocol, reactor, defer
from zope.interface import implements
import os

class UserInbox(maildir.MaildirMailbox):
    """
    maildir.MaildirMailbox already implements the pop3.IMailbox
    interface, so methods need to be defined only to
    override the default behavior. For non-maildir mailboxes,
    you'd have to implement all of pop3.IMailbox:
    """
    def __init__(self, userdir):
        inboxDir = os.path.join(userdir, 'Inbox')
        maildir.MaildirMailbox.__init__(self, inboxDir)

class POP3Protocol(pop3.POP3):
```

```
debug = True
```

```
def sendLine(self, line):
```

```
    if self.debug: print "POP3 SERVER:", line
    pop3.POP3.sendLine(self, line)
```

```
def lineReceived(self, line):
```

```
    if self.debug: print "POP3 CLIENT:", line
    pop3.POP3.lineReceived(self, line)
```

```
class POP3Factory(protocol.Factory):
```

```
    protocol = POP3Protocol
```

```
    portal = None
```

```
def buildProtocol(self, address):
```

```
    p = self.protocol( )
    p.portal = self.portal
    p.factory = self
    return p
```

```
class MailUserRealm(object):
```

```
    implements(portal.IRealm)
```

```
    avatarInterfaces = {
```

```
        pop3.IMailbox: UserInbox,
    }
```

```
def __init__(self, baseDir):
```

```
    self.baseDir = baseDir
```

```
def requestAvatar(self, avatarId, mind, *interfaces):
```

```
    for requestedInterface in interfaces:
        if self.avatarInterfaces.has_key(requestedInterface):
            # make sure the user dir exists
            userDir = os.path.join(self.baseDir, username)
```

```

        if not os.path.exists(userDir):
            os.mkdir(userDir)

        # return an instance of the correct class
        avatarClass = self.avatarInterfaces[requestedInterface]
        avatar = avatarClass(userDir)

        # null logout function (FIXME: explain why)
        logout = lambda: None

        return defer.succeed(requestedInterface, avatar, logout)

# none of the requested interfaces was supported
raise KeyError("None of the requested interfaces is supported")

class CredentialsChecker(object):
    implements(checkers.ICredentialsChecker)
    credentialInterfaces = (credentials.IUsernamePassword,
                            credentials.IUsernameHashedPassword)

    def __init__(self, passwords):
        "passwords: a dict-like object mapping usernames to passwords"
        self.passwords = passwords

    def requestAvatarId(self, credentials):
        username = credentials.username
        if self.passwords.has_key(username):
            realPassword = self.passwords[username]
            checking = defer.maybeDeferred(
                credentials.checkPassword, realPassword)
            # pass result of checkPassword, and the username that was
            # being authenticated, to self._checkedPassword
            checking.addCallback(self._checkedPassword, username)
            return checking
        else:
            raise credError.UnauthorizedLogin("No such user")

```

```

def _checkedPassword(self, matched, username):
    if matched:
        # password was correct
        return username
    else:
        raise credError.UnauthorizedLogin("Bad password")


def passwordFileToDict(filename):
    passwords = {}
    for line in file(filename):
        if line and line.count(':'):
            username, password = line.strip().split(':')
            passwords[username] = password
    return passwords

if __name__ == "__main__":
    import sys
    dataDir = sys.argv[1]
    factory = POP3Factory( )
    factory.portal = portal.Portal(MailUserRealm(dataDir))
    passwordFile = os.path.join(dataDir, 'passwords.txt')
    passwords = passwordFileToDict(passwordFile)
    passwordChecker = CredentialsChecker(passwords)
    factory.portal.registerChecker(passwordChecker)
    reactor.listenTCP(110, factory)
    reactor.run( )

```

This example, *pop3server.py*, uses the directory structure created by *smtpserver.py* in [Example 8-1](#), and illustrated in [Figure 8-4](#). A base directory called *mail_storage* has directories for each email address, each of which contains a *maildir* directory called *Inbox*.

Figure 8-4. The mail directory structure



Before you run *pop3server.py*, create a file called *passwords.txt* in your base *mail_storage* directory. This file should contain a list of usernames and passwords, separated by colons:

```

testuser@localhost:password

bob@localhost:password
  
```

Run *pop3server.py* with the name of the base mail directory as the only argument:


```
$ python pop3server.py mail_storage
```

Now configure your mail client to download mail from [localhost](#) using POP3. Use a full email address as the username, and the corresponding password. Then you should be able to download all the messages you sent to that email address while running *smtpserver.py* from [Example 8-1](#). [Figure 8-5](#) illustrates the process.

8.3.2. How Does That Work?

There are two major pieces that `pop3.POP3Protocol` requires to create a working POP3 server. First, you need to have a class implementing `pop3.IMailbox`, which gives the server methods for reading and deleting messages in a user's mailbox. Second, you need to have a `twisted.cred.portal.Portal` object that will take a username and password, make sure they are valid, and then return the mailbox object for that user.

Figure 8-5. Downloading messages from the POP3 server



In [Example 8-3](#), each user's mail is kept in a *maildir* directory. The `maildir.MaildirMailbox` class helpfully implements `pop3.IMailbox` already, so it isn't necessary to write a special class. If you were serving mail that wasn't in a *maildir* directory, you'd have to implement `pop3.IMailbox` yourself, by providing the following methods:

```
def listMessages(self, index=None):
```

Return a list of integers representing the sizes of all the messages in this mailbox, in bytes. If `index` is not `None`, return an integer representing the size of that message.

```
def getMessage(self, index):
```

Return a file-like object containing the message at `index`.

```
def getUidl(self, index):
```

Return a unique identifier string for the message at `index`. This value will be used by POP3 clients to determine whether they've seen a message before. `getUidl` should never return the same value for different messages, and it should consistently return the same value for a specific message.

```
def deleteMessage(self, index):
```

Mark the message at `index` for deletion. The number of messages in the mailbox should not change, and the message shouldn't actually be deleted until the `sync` method is called.

```
def undeleteMessages(self):
```

Cancel pending deletions. Any messages that have been marked for deletion using `deleteMessage` should be restored to their previous state.

```
def sync(self):
```

Delete any messages that have been marked for deletion, and perform any other housecleaning tasks. This method will be called when a POP3 client sends the `QUIT` command.

Once you've set up a `pop3.IMailbox` interface for your mailboxes, you need to give the server a way to load the appropriate mailbox for each user based on their username and password. This is done using the Twisted authentication framework, `twisted.cred`. (For a complete discussion of `twisted.cred`, see [Chapter 6](#).)

The `MailUserRealm` class in [Example 8-3](#) needs to work with `pop3.POP3` only, so it offers just one interface: `pop3.IMailbox`. Still, it's designed in a fairly generic way. The class defines a dictionary called `avatarInterfaces`, which maps the `pop3.IMailbox` interface to `UserInbox`, a class that implements that interface. When `requestAvatar` is called, `MailUserRealm` loops through list of requested interfaces and tries to find a matching interface in `avatarInterfaces`. If it finds a matching interface, it constructs an avatar based on the interface and the requested `avatarID`. In this case, the `avatarID` is the email address whose mailbox should be opened. The `MailUserRealm` checks to make sure that mailbox exists, creates it if needed, and then creates the avatar by passing the user's mailbox directory to the class whose interface matched the requested interface, which in this case will always be `UserInbox`. Finally, it returns a tuple containing three values: the interface that matched, the avatar (which implements that interface), and a function to clean up the avatar when the user is done with his session. In this case, there isn't anything to do at logout, so `MailUserRealm` uses an anonymous function that doesn't actually do anything.

The `requestAvatarId` method takes a credentials object that implements one of the interfaces listed in `credentialsInterfaces`; in this case, either `credentials.IUsernamePassword` or `credentials.IUsernameHashedPassword`. Both of these interfaces have a `checkPassword` method that returns a `Deferred Boolean` value saying whether the password matched. Using `checkPassword` lets your code work with both plain-text passwords and encrypted password hashes. In the specific case of a POP3 server, accepting credentials that implement `credentials.IUsernameHashedPassword` allows the server to accept MD5 passwords.

Once you've defined classes for your implementations of `pop3.IMailbox`, `portal.IRealm` and `credentials.ICredentialsChecker`, it doesn't take much code to put them together into a working POP3 server. In [Example 8-3](#), `POP3Factory` has a custom `buildProtocol` method that creates a `POP3Protocol` object and sets its `portal` attribute. `POP3Protocol` is a simple class that inherits from `pop3.POP3` and adds an optional debugging mode: when `debug` is true, it will print all the commands received from the client and the replies sent back from the server. This technique can be very useful when you want to see exactly what a protocol is doing.

[< Day Day Up >](#)

8.4. Providing IMAP Access to Mailboxes

IMAP is a powerful and full-featured protocol for mail management. But its many features are both a blessing and a curse. IMAP is a great protocol to use: it provides all the necessary tools to store, organize, and mail on a central server. But IMAP's complexity makes it an intimidating protocol to implement: the base IMAP protocol spec in RFC 2060 runs to more than 80 dense pages. IMAP also puts a lot of burden on the mail server. IMAP servers have to support message parsing (to allow the client to download only selected parts of a message), message searching (using a special query language), and the ability to reference messages using two completely different sets of numeric identifiers (message sequence numbers and unique IDs).

This complexity has historically caused all but the most dedicated developers to steer clear of IMAP, settling for the simpler but less capable POP3. So the fact that `twisted.mail` includes IMAP support is a great opportunity for developers. It makes it possible for you to write your own custom IMAP server, but without having to deal with all the nasty details of the IMAP protocol.

8.4.1. How Do I Do That?

To make an IMAP server, write classes to implement the `IAccount`, `IMailbox`, `IMessage`, and `IMessagePart` interfaces defined in `twisted.mail.imap4`. Then set up a realm that makes your `IAccount` implementation available as an avatar. Wrap the realm in a `Portal`, and set up a `Factory` that will pass the `Portal` to an `imap4.IMAP4Server` Protocol. [Example 8-4](#) demonstrates a complete IMAP server.

Example 8-4. `imapserver.py`

```
from twisted.mail import imap4, maildir

from twisted.internet import reactor, defer, protocol

from twisted.cred import portal, checkers, credentials

from twisted.cred import error as credError

from twisted.python import filepath

from zope.interface import implements

import time, os, random, pickle

MAILBOXDELIMITER = "."

class IMAPUserAccount(object):

    implements(imap4.IAccount)
```

```

def __init__(self, userDir):
    self.dir = userDir
    self.mailboxCache = {}
    # make sure Inbox exists
    inbox = self._getMailbox("Inbox", create=True)

def listMailboxes(self, ref, wildcard):
    for box in os.listdir(self.dir):
        yield box, self._getMailbox(box)

def select(self, path, rw=True):
    "return an object implementing IMailbox for the given path"
    return self._getMailbox(path)

def _getMailbox(self, path, create=False):
    """
    Helper function to get a mailbox object at the given
    path, optionally creating it if it doesn't already exist.
    """
    # According to the IMAP spec, Inbox is case-insensitive
    pathParts = path.split(MAILBOXDELIMITER)
    if pathParts[0].lower() == 'inbox': pathParts[0] = 'Inbox'
    path = MAILBOXDELIMITER.join(pathParts)

    if not self.mailboxCache.has_key(path):
        fullPath = os.path.join(self.dir, path)
        if not os.path.exists(fullPath):
            if create:
                maildir.initializeMaildir(fullPath)
            else:
                raise KeyError, "No such mailbox"
        self.mailboxCache[path] = IMAPMailbox(fullPath)

```

```
return self.mailboxCache[path]

def create(self, path):
    "create a mailbox at path and return it"
    self._getMailbox(path, create=True)

def delete(self, path):
    "delete the mailbox at path"
    raise imap4.MailboxException("Permission denied.")

def rename(self, oldname, newname):
    "rename a mailbox"
    oldPath = os.path.join(self.dir, oldname)
    newPath = os.path.join(self.dir, newname)
    os.rename(oldPath, newPath)

def isSubscribed(self, path):
    "return a true value if user is subscribed to the mailbox"
    return self._getMailbox(path).metadata.get('subscribed', False)

def subscribe(self, path):
    "mark a mailbox as subscribed"
    box = self._getMailbox(path)
    box.metadata['subscribed'] = True
    box.saveMetadata()
    return True

def unsubscribe(self, path):
    "mark a mailbox as unsubscribed"
    box = self._getMailbox(path)
    box.metadata['subscribed'] = False
    box.saveMetadata()
    return True
```

```

class ExtendedMaildir(maildir.MaildirMailbox):
    """
    Extends maildir.MaildirMailbox to expose more
    of the underlying filename data
    """
    def __iter__(self):
        "iterates through the full paths of all messages in the maildir"
        return iter(self.list)

    def __len__(self):
        return len(self.list)

    def __getitem__(self, i):
        return self.list[i]

    def deleteMessage(self, filename):
        index = self.list.index(filename)
        os.remove(filename)
        del(self.list[index])

class IMAPMailbox(object):
    implements(imap4.IMailbox)

    def __init__(self, path):
        self.maildir = ExtendedMaildir(path)
        self.metadataFile = os.path.join(path, '.imap-metadata.pickle')
        if os.path.exists(self.metadataFile):
            self.metadata = pickle.load(file(self.metadataFile, 'r+b'))
        else:
            self.metadata = {}
        self.initMetadata()
        self.listeners = []
        self._assignUIDs()

```

```

def initMetadata(self):
    if not self.metadata.has_key('flags'):
        self.metadata['flags'] = {} # dict of message IDs to flags
    if not self.metadata.has_key('uidvalidity'):
        # create a unique integer ID to identify this version of
        # the mailbox, so the client could tell if it was deleted
        # and replaced by a different mailbox with the same name
        self.metadata['uidvalidity'] = random.randint(1000000, 9999999)
    if not self.metadata.has_key('uids'):
        self.metadata['uids'] = {}
    if not self.metadata.has_key('uidnext'):
        self.metadata['uidnext'] = 1 # next UID to be assigned

def saveMetadata(self):
    pickle.dump(self.metadata, file(self.metadataFile, 'w+b'))

def _assignUIDs(self):
    # make sure every message has a uid
    for messagePath in self.maildir:
        messageFile = os.path.basename(messagePath)
        if not self.metadata['uids'].has_key(messageFile):
            self.metadata['uids'][messageFile] =
self.metadata['uidnext']
            self.metadata['uidnext'] += 1
    self.saveMetadata()

def getHierarchicalDelimiter(self):
    return MAILBOXDELIMITER

def getFlags(self):
    "return list of flags supported by this mailbox"
    return [r'\Seen', r'\Unseen', r'Deleted',
            r'\Flagged', r'\Answered', r'\Recent']

```

```

def getMessageCount(self):
    return len(self.maildir)

def getRecentCount(self):
    return 0

def getUnseenCount(self):
    def messageIsUnseen(filename):
        filename = os.path.basename(filename)
        uid = self.metadata['uids'].get(filename)
        flags = self.metadata['flags'].get(uid, [])
        if not r'\Seen' in flags:
            return True
    return len(filter(messageIsUnseen, self.maildir))

def isWriteable(self):
    return True

def getUIDValidity(self):
    return self.metadata['uidvalidity']

def getUID(self, messageNum):
    filename = os.path.basename(self.maildir[messageNum-1])
    return self.metadata['uids'][filename]

def getUIDNext(self):
    return self.folder.metadata['uidnext']

def _uidMessageSetToSeqDict(self, messageSet):
    """
    take a MessageSet object containing UIDs, and return
    a dictionary mapping sequence numbers to filenames

```

```

"""
# if messageSet.last is None, it means 'the end', and needs to
# be set to a sane high number before attempting to iterate
# through the MessageSet
if not messageSet.last:
    messageSet.last = self.metadata['uidnext']

allUIDs = []

for filename in self.maildir:
    shortFilename = os.path.basename(filename)
    allUIDs.append(self.metadata['uids'][shortFilename])

allUIDs.sort()

seqMap = {}

for uid in messageSet:
    # the message set covers a span of UIDs. not all of them
    # will necessarily exist, so check each one for validity
    if uid in allUIDs:
        sequence = allUIDs.index(uid)+1
        seqMap[sequence] = self.maildir[sequence-1]

return seqMap

def _seqMessageSetToSeqDict(self, messageSet):
    """
    take a MessageSet object containing message sequence numbers,
    and return a dictionary mapping sequence number to filenames
    """
    # if messageSet.last is None, it means 'the end', and needs to
    # be set to a sane high number before attempting to iterate
    # through the MessageSet
    if not messageSet.last: messageSet.last = len(self.maildir)-1
    seqMap = {}

    for messageNo in messageSet:
        seqMap[messageNo] = self.maildir[messageNo-1]

    return seqMap

```

```

def fetch(self, messages, uid):
    if uid:
        messagesToFetch = self._uidMessageSetToSeqDict(messages)
    else:
        messagesToFetch = self._seqMessageSetToSeqDict(messages)
    for seq, filename in messagesToFetch.items():
        uid = self.getUID(seq)
        flags = self.metadata['flags'].get(uid, [])
        yield seq, MaildirMessage(file(filename).read(), uid, flags)

def addListener(self, listener):
    self.listeners.append(listener)
    return True

def removeListener(self, listener):
    self.listeners.remove(listener)
    return True

def requestStatus(self, path):
    return imap4.statusRequestHelper(self, path)

def addMessage(self, msg, flags=None, date=None):
    if flags is None: flags = []
    return self.maildir.appendMessage(msg).addCallback(
        self._addedMessage, flags)

def _addedMessage(self, _, flags):
    # the first argument is the value returned from
    # MaildirMailbox.appendMessage. It doesn't contain any meaningful
    # information and can be discarded. Using the name "_" is a Twisted
    # idiom for unimportant return values.
    self._assignUIDs()
    messageFile = os.path.basename(self.maildir[-1])

```

```

messageID = self.metadata['uids'][messageFile]

self.metadata['flags'][messageID] = flags

self.saveMetadata()

def store(self, messageSet, flags, mode, uid):

    if uid:

        messages = self._uidMessageSetToSeqDict(messageSet)

    else:

        messages = self._seqMessageSetToSeqDict(messageSet)

    setFlags = {}

    for seq, filename in messages.items():

        uid = self.getUID(seq)

        if mode == 0: # replace flags

            messageFlags = self.metadata['flags'][uid] = flags

        else:

            messageFlags = self.metadata['flags'].setdefault(uid, [])

            for flag in flags:

                # mode 1 is append, mode -1 is delete

                if mode == 1 and not messageFlags.count(flag):

                    messageFlags.append(flag)

                elif mode == -1 and messageFlags.count(flag):

                    messageFlags.remove(flag)

            setFlags[seq] = messageFlags

    self.saveMetadata()

    return setFlags

def expunge(self):

    "remove all messages marked for deletion"

    removed = []

    for filename in self.maildir:

        uid = self.metadata['uids'].get(os.path.basename(filename))

        if r"Deleted" in self.metadata['flags'].get(uid, []):

            self.maildir.deleteMessage(filename)

            # you could also throw away the metadata here

```

```

        removed.append(uid)

    return removed

def destroy(self):
    "complete remove the mailbox and all its contents"
    raise imap4.MailboxException("Permission denied.")

from cStringIO import StringIO
import email

class MaildirMessagePart(object):
    implements(imap4.IMessagePart)

    def __init__(self, mimeType):
        self.message = mimeType
        self.data = str(self.message)

    def getHeaders(self, negate, *names):
        """
        Return a dict mapping header name to header value. If *names
        is empty, match all headers; if negate is true, return only
        headers _not_ listed in *names.
        """
        if not names: names = self.message.keys()
        headers = {}
        if negate:
            for header in self.message.keys():
                if header.upper() not in names:
                    headers[header.lower()] = self.message.get(header, '')
        else:
            for name in names:
                headers[name.lower()] = self.message.get(name, '')
        return headers

```

```

def getBodyFile(self):
    "return a file-like object containing this message's body"
    bodyData = str(self.message.get_payload())
    return StringIO(bodyData)

def getSize(self):
    return len(self.data)

def getInternalDate(self):
    return self.message.get('Date', '')

def isMultipart(self):
    return self.message.is_multipart()

def getSubPart(self, partNo):
    return MaildirMessagePart(self.message.get_payload(partNo))

class MaildirMessage(MaildirMessagePart):
    implements(imap4.IMessage)

    def __init__(self, messageData, uid, flags):
        self.data = messageData
        self.message = email.message_from_string(self.data)
        self.uid = uid
        self.flags = flags

    def getUID(self):
        return self.uid

    def getFlags(self):
        return self.flags

class MailUserRealm(object):

```

```

implements(portal.IRealm)

avatarInterfaces = {
    imap4.IAccount: IMAPUserAccount,
}

def __init__(self, baseDir):
    self.baseDir = baseDir

def requestAvatar(self, avatarId, mind, *interfaces):
    for requestedInterface in interfaces:
        if self.avatarInterfaces.has_key(requestedInterface):
            # make sure the user dir exists (avatarId is username)
            userDir = os.path.join(self.baseDir, avatarId)
            if not os.path.exists(userDir):
                os.mkdir(userDir)

            # return an instance of the correct class
            avatarClass = self.avatarInterfaces[requestedInterface]
            avatar = avatarClass(userDir)

            # null logout function: take no arguments and do nothing
            logout = lambda: None

            return defer.succeed((requestedInterface, avatar, logout))

    # none of the requested interfaces was supported
    raise KeyError("None of the requested interfaces is supported")

def passwordFileToDict(filename):
    passwords = {}
    for line in file(filename):
        if line and line.count(':'):
            username, password = line.strip().split(':')
            passwords[username] = password
    return passwords

```

```

class CredentialsChecker(object):
    implements(checkers.ICredentialsChecker)
    credentialInterfaces = (credentials.IUsernamePassword,
                            credentials.IUsernameHashedPassword)

    def __init__(self, passwords):
        "passwords: a dict-like object mapping usernames to passwords"
        self.passwords = passwords

    def requestAvatarId(self, credentials):
        """
        check to see if the supplied credentials authenticate.
        if so, return an 'avatar id', in this case the name of
        the IMAP user.

        The supplied credentials will implement one of the classes
        in self.credentialInterfaces. In this case both
        IUsernamePassword and IUsernameHashedPassword have a
        checkPassword method that takes the real password and checks
        it against the supplied password.
        """
        username = credentials.username
        if self.passwords.has_key(username):
            realPassword = self.passwords[username]
            checking = defer.maybeDeferred(
                credentials.checkPassword, realPassword)
            # pass result of checkPassword, and the username that was
            # being authenticated, to self._checkedPassword
            checking.addCallback(self._checkedPassword, username)
            return checking
        else:
            raise credError.UnauthorizedLogin("No such user")

    def _checkedPassword(self, matched, username):
        if matched:

```

```

    # password was correct

    return username

else:

    raise credError.UnauthorizedLogin("Bad password")

class IMAPServerProtocol(imap4.IMAP4Server):

    "Subclass of imap4.IMAP4Server that adds debugging."

    debug = True

    def lineReceived(self, line):

        if self.debug:

            print "CLIENT:", line

            imap4.IMAP4Server.lineReceived(self, line)

    def sendLine(self, line):

        imap4.IMAP4Server.sendLine(self, line)

        if self.debug:

            print "SERVER:", line

class IMAPFactory(protocol.Factory):

    protocol = IMAPServerProtocol

    portal = None # placeholder

    def buildProtocol(self, address):

        p = self.protocol()

        p.portal = self.portal

        p.factory = self

        return p

if __name__ == "__main__":

    import sys

    dataDir = sys.argv[1]

```

```

portal = portal.Portal(MailUserRealm(dataDir))

passwordFile = os.path.join(dataDir, 'passwords.txt')

passwords = passwordFileToDict(passwordFile)

passwordChecker = CredentialsChecker(passwords)

portal.registerChecker(passwordChecker)

factory = IMAPFactory()

factory.portal = portal

reactor.listenTCP(143, factory)

reactor.run()

```

Run *imapserver.py* from the command line with the name of the base mail directory as the only argument. This should be the same directory you used for the SMTP and POP3 servers in [Examples 8-1](#) and [8-3](#):


```
$ python imapserver.py mail_storage
```

Once the server is running, set up your mail client to connect to [localhost](#) using IMAP. You should be able to see the Inbox folder, create folders and subfolders, subscribe to folders, view messages, mark messages as read or unread, and move messages between folders, as shown in [Figure 8-6](#).

8.4.2. How Does That Work?

Compared to the other examples in this chapter, there's a lot of code required to make an IMAP server. But don't let that intimidate you. Most of the code in [Example 8-4](#) is in the classes `IMAPUserAccount`, `IMAPMaildir`, `MaildirMessagePart`, and `MaildirMessage`, which respectively implement the interfaces `imap4.IAccount`, `imap4.IMailbox`, `imap4.IMessagePart`, and `imap4.IMessage`. These interfaces have a lot of methods, because the IMAP server needs to be able to do a lot of different things. However, most of the methods themselves are pretty simple, taking just a few lines of code. The following subsections go through the interfaces one at a time, to look at how they're used in [Example 8-4](#).

Figure 8-6. Working with messages on the IMAP server



8.4.2.1. IAccount

The `imap4.IAccount` interface defines a user account, and provides access to the user's mailboxes. `imap4.IAccount` defines methods for listing, creating, deleting, renaming, and subscribing to mailboxes. Mailboxes are hierarchal, with a server-defined delimiter character. In [Example 8-4](#), the delimiter character is a period, so the folder `MailingLists.Twisted` would be considered a subfolder of `MailingLists`. In this case, the user's mailboxes are a set of maildir directories kept within a single parent directory. The use of a period as a delimiter makes it easier to keep all the maildirs in a single flat directory structure while still keeping track of their hierarchy. You could feel free to use another delimiter character, such as a forward slash (`/`), if it were more convenient for your needs.

According to RFC 2060, each IMAP user will have a folder called `Inbox` available in her account at all times. The name `Inbox` is case-insensitive, however, so different mail clients may ask for `INBOX`, `Inbox`, or `inbox`. Make sure you account for this in your code.

The `select` and `create` methods of `IAccount` return objects implementing `IMailbox`. The `list` method returns an iterable of tuples, with each tuple containing a path and an object implementing `IMailbox`.

8.4.2.2. IMailbox

The `imap4.IMailbox` interface represents a single mailbox on the IMAP server. It has methods for getting information about the mailbox, reading and writing messages, and storing metadata. There are a couple of considerations to keep in mind when you write a class to implement `IMailbox`. First, note that an IMAP mailbox is more than just a collection of messages. It also is responsible for managing metadata about those messages and the mailbox itself. In [Example 8-4](#), the `IMAPMaildir` class keeps metadata in a dictionary, which is pickled and stored in a hidden file in the maildir directory for persistence between sessions. These are some of the specific kinds of metadata you'll need to track:

Message UIDs

Every message in an IMAP mailbox has a permanent unique identifier. These are sequential, and are maintained over the life of the mailbox. The first ever message in a mailbox will have a UID of 1, the second a UID of 2, etc. These are different from simple sequence numbers in that they continue to build over the lifetime of a mailbox. For example, if you added 1000 messages to a new IMAP mailbox, they would be assigned the UIDs 1–1001. If you then deleted all those messages and added a single new message, it would be given a UID of 1002, even though there wouldn't be any other messages in the mailbox. UIDs are used by the client for caching purposes, to avoid repeatedly downloading the same message. In `IMailbox`, the `getUID` function returns the UID of a message, given its sequence number. The `getUIDNext` function returns the UID number that will be assigned to the next message added to the mailbox.

Message flags

Every message in the mailbox can have an arbitrary number of flags associated with it. The flags are set by the client to keep track of metadata about that message, such as whether it's been read, replied to, or flagged. RFC 2060 defines a set of system flags that all IMAP clients should use the same way: `\Seen`, `\Answered`, `\Flagged`, `\Deleted`, `\Draft`, and `\Recent`. The `IMailbox` `getFlags` methods returns the list of flags supported by the mailbox. The `store` method sets the flags on a group of messages.

The mailbox UID validity identifier

There can be times when a mailbox keeps the same name, but changes its list of UIDs. The most common example of this is when a mailbox is deleted and a new mailbox with the same name is created. This could cause confusion for a mail client, since it may have a cached copy of the message with UID 1, which is now different from the message on the server with UID 1. To prevent this, IMAP has the concept of a UID validity identifier. Each mailbox has a unique number associated with it. As long as this number remains the same, the client can be confident that its UID numbers are still valid. If this number changes, the client knows to forget all its cached UID information. You should assign a UID validity identifier number for each mailbox, and return it as the result of `getUIDValidity`.

The mailbox subscription status

IMAP clients may not want or need to display all the mailboxes that actually exist on the server. The client can tell the server which mailboxes it is interested in by subscribing to those mailboxes. Subscribing doesn't do anything special other than toggling a subscribed bit on the mailbox. The subscription status of each mailbox is stored on the server, so that it can be maintained from session to session and between different clients.

The second thing to be aware of when implementing `IMailbox` is that there are two different numbering schemes that clients may use to refer to messages. The first is UIDs, persistent unique identifiers. The second is sequence numbers, which are a simple list of numbers from 1 to the number of messages in the mailbox. The `fetch` and `store` methods of `IMailbox` take an `imap4.MessageSet` object along with a Boolean `uid` argument. The `MessageSet` is an iterable list of numbers, but you have to check the `uid` argument to determine whether it's a list of UIDs or a list of sequence numbers. The `IMAPMaildir` class in [Example 8-4](#) uses two methods, `_uidMessageSetToSeqDict` and `_seqMessageSetToSeqDict`, to take either type of `MessageSet` and normalize it into a dictionary mapping sequence numbers to the filenames it uses internally to identify messages. Note that the lists returned by `fetch` and `store` always use sequence numbers, whether or not the `uid` argument was true.

The last property of a `MessageSet` may be set to `None`, which means that the `MessageSet` covers all messages from its start to the end of the mailbox. You can't actually iterate through a `MessageSet` in this state, though, so you should set `last` to a value just beyond the last message in the mailbox before you attempt to use the `MessageSet`.

The IMAP protocol includes support for server-to-client notification. A client will generally keep an open connection to the IMAP server, so rather than having the client periodically ask the server if there are any new messages, the server can send a message to the client to alert it as soon as messages have arrived. The `IMailbox` interface includes methods for managing these notifications. The `addListener` method registers an object implementing `imap4.IMailboxListener`. If you keep track of this object, you can use it later to notify the client when a new message arrives. The `IMAPMaildir` class in [Example 8-4](#) keeps track of listeners, but doesn't actually use them. [Example 8-5](#) shows how you might use listeners to notify the client of new messages.

Example 8-5. Using listener objects for notification

```
# run this code to let the client know when a new message
# appears in the mailbox

for listener in self.listeners:

    listener.newMessages(self.getMessageCount(), self.getRecentCount())
```

8.4.3. IMessagePart and IMessage

In IMAP, an email message is not just a blob of data: it has a structure that can be accessed one part at a time. In its simplest form, a message is a group of headers and a body. More complex messages can have a multi-part body, with alternative versions of the body content (such as HTML and plain text) and attachments (which may themselves be other messages with their own structure).

The `IMessagePart` interface provides methods for investigating the structure of one part of a multi-part message. `IMessage` inherits from `IMessagePart` and adds the `getUID` and `getFlags` methods for retrieving metadata about the message. Implementing `IMessagePart` would be a chore if not for the excellent `email` module in the Python standard library, which contains a complete set of classes for parsing and working with email messages. In [Example 8-4](#), the `MaildirMessage` class uses the `email.message_from_string` function to parse the message data into an `email.Message.Message` object. `MaildirMessagePart` takes an `email.Message.Message` object and wraps it in the `IMessagePart` interface.

8.4.4. Putting It All Together

Once you've implemented `IAccount`, `IMailbox`, `IMessagePart`, and `IMessage`, just tie the pieces together to get a working IMAP server. [Example 8-4](#) uses the same classes, `MailUserRealm` and

CredentialsChecker, as the POP3 server in [Example 8-3](#), except that the realm is set up to return IMAPMaildir avatars when the `imap4.IMailbox` interface is requested. The `IMAPFactory` object creates `IMAPServerProtocol` objects and sets their `portal` attribute to a `Portal` wrapping the realm and credentials checkers. The `IMAPServerProtocol` class is another example of how you can inherit from a `Twisted Protocol` class and add some print statements for debugging.

[< Day Day Up >](#)

Chapter 9. NNTP Clients and Servers

Usenet is a long-standing network of servers used for public discussion on the Internet. Each discussion forum in Usenet is called a newsgroup, and each Usenet server can host any number of newsgroups. Messages in a Usenet newsgroup are referred to as articles. Usenet servers communicate with each other to keep their copies of each newsgroup up-to-date, so that an article posted to a newsgroup on one server will eventually propagate to all the servers that host that newsgroup. This setup allows many people to participate in Usenet discussions without putting the load on any one central server.

The Usenet system dates back to before the Internet and TCP/IP had become widely accepted. Originally, computers participating in Usenet would connect to each other directly using dial-up modem connections, and then push articles back and forth using UUCP, the Unix-to-Unix Copy Protocol. After TCP/IP became the standard way to transfer data between computers, a new protocol was developed for Usenet communications. This Network News Transfer Protocol, or NNTP, is defined in RFC 977 (<http://www.faqs.org/rfc/rfc977.txt>). NNTP is used by Usenet clients for reading and posting articles to servers, as well as for server-to-server article transfers.

Support for NNTP in Twisted is provided by the `twisted.news` package. This chapter demonstrates how to use `twisted.news` to build Usenet clients and servers.

9.1. Listing the Newsgroups on a Server

This lab demonstrates how to use the `twisted.news.nntp` module to perform one of the most common tasks in Usenet: retrieving a list of the available newsgroups on a server.

9.1.1. How Do I Do That?

Use a subclass of `twisted.news.nntp.NNTPClient` as your Protocol. `NNTPClient` is one of the older protocol implementations in Twisted, and it's starting to show its age. It was developed before the best practices for writing Twisted client protocols had really been understood. In particular, you'll notice that it doesn't make use of `Deferreds`. Instead, `NNTPClient` has an API that provides methods for sending commands to the server, and you write handler methods for receiving the server's reply.

To get the list of newsgroups from the server, call the `fetchGroups` method of `NNTPClient`. Use the `gotAllGroups` method as shown in [Example 9-1](#) to handle the result, and `getAllGroupsFailed` to handle an error.

Example 9-1. `nntplist.py`

```
from twisted.news import nntp

from twisted.internet import protocol, defer

class NNTPGroupListerProtocol(nntp.NNTPClient):

    def connectionMade(self):

        nntp.NNTPClient.connectionMade(self)

        self.fetchGroups( )

    def gotAllGroups(self, groups):

        groupnames = [groupInfo[0] for groupInfo in groups]

        self.factory.deferred.callback(groupnames)

        self.quit( )

    def getAllGroupsFailed(self, error):

        self.factory.deferred.errback(error)
```

```

def connectionLost(self, error):
    if not self.factory.deferred.called:
        self.factory.deferred.errback(error)

class NNTPGroupListerFactory(protocol.ClientFactory):
    protocol = NNTPGroupListerProtocol

    def __init__(self):
        self.deferred = defer.Deferred()

if __name__ == "__main__":
    from twisted.internet import reactor

    def printGroups(groups):
        for group in groups:
            print group
        reactor.stop()

    def handleError(error):
        print >> sys.stderr, error.getErrorMessage()
        reactor.stop()

    factory = NNTPGroupListerFactory()
    factory.deferred.addCallback(printGroups).addErrback(handleError)

    reactor.connectTCP('news-server.maine.rr.com', 119, factory)
    reactor.run()

```

Run *nttplist.py* with the hostname of an NNTP server as the only argument. It will download and print the list of available newsgroups:

```
$ python nttplist.py freetext.usenetserver.com
```

```
aaaustin.jobs  
aacc.general  
aapg.general  
ab.agriculture  
...  
zipworld.help  
zoom.cheesedog  
zoomnet.general  
zz.unity.chat  
zz.unity.netlink  
zzz.3
```

9.1.2. How Does That Work?

NNTP doesn't require authentication, so `NNTPGroupListerProtocol` only has to call one method: `self.fetchGroups()`. When the server responds with a list of newsgroups, the `getAllGroups` method is called, with the newsgroup list as an argument. This list is a set of tuples in the form `(groupName, articleCount)`. `NNTPGroupListerProtocol`'s `getAllGroups` method extracts the group names and uses them to call back the `Factory`'s `Deferred` object.

The `getAllGroupsFailed` method is the error handler for `fetchGroups`. If an error occurs, it will be passed to the `factory`'s `Deferred`.

[< Day Day Up >](#)

9.2. Downloading Usenet Articles

The core of Usenet, of course, is downloading and reading articles. This lab shows how to learn which articles are available in a group, and then download the most recent ones.

9.2.1. How Do I Do That?

Call `NNTPClient`'s `fetchGroup` method to get the article count and first and last message numbers for a newsgroup. Then call `fetchArticle` to download each article. [Example 9-2](#) demonstrates the technique.

Example 9-2. `nntpdownload.py`

```
from twisted.news import nntp
from twisted.internet import protocol, defer
import time, email

class NNTPGroupDownloadProtocol(nntp.NNTPClient):

    def connectionMade(self):
        nntp.NNTPClient.connectionMade(self)
        self.fetchGroup(self.factory.newsgroup)

    def gotGroup(self, groupInfo):
        articleCount, first, last, groupName = groupInfo
        first = int(first)
        last = int(last)
        start = max(first, last-self.factory.articleCount)
        self.articlesToFetch = range(start+1, last+1)
        self.articleCount = len(self.articlesToFetch)
        self.fetchNextArticle( )

    def fetchNextArticle(self):
        if self.articlesToFetch:
```

```

        nextArticleIdx = self.articlesToFetch.pop(0)

        print "Fetching article %i of %i..." % (
            self.articleCount-len(self.articlesToFetch),
            self.articleCount),

        self.fetchArticle(nextArticleIdx)

    else:

        # all done

        self.quit( )

        self.factory.deferred.callback(0)

def gotArticle(self, article):

    print "OK"

    self.factory.handleArticle(article)

    self.fetchNextArticle( )

def getArticleFailed(self, errorMessage):

    print errorMessage

    self.fetchNextArticle( )

def getGroupFailed(self, errorMessage):

    self.factory.deferred.errback(Exception(errorMessage))

    self.quit( )

    self.transportloseConnection( )

def connectionLost(self, error):

    if not self.factory.deferred.called:

        self.factory.deferred.errback(error)

class NNTPGroupDownloadFactory(protocol.ClientFactory):

    protocol = NNTPGroupDownloadProtocol

def __init__(self, newsgroup, outputfile, articleCount=10):

    self.newsgroup = newsgroup

    self.articleCount = articleCount

```

```

        self.output = outputfile

        self.deferred = defer.Deferred( )

def handleArticle(self, articleData):

    parsedMessage = email.message_from_string(articleData)

    self.output.write(parsedMessage.as_string(unixfrom=True))

    self.output.write('\r\n\r\n')

if __name__ == "__main__":

    from twisted.internet import reactor

    import sys

def handleError(error):

    print >> sys.stderr, error.getErrorMessage( )

    reactor.stop( )

if len(sys.argv) != 4:

    print >> sys.stderr, "Usage: %s nntpserver newsgroup outputfile"

    sys.exit(1)

server, newsgroup, outfile = sys.argv[1:4]

factory = NNTPGroupDownloadFactory(newsgroup, file(outfile, 'w+b'))

factory.deferred.addCallback(

    lambda _: reactor.stop( )).addErrback(

        handleError)

reactor.connectTCP(server, 119, factory)

reactor.run( )

```

Run *nntpdownload.py* with the name of an NNTP server, a newsgroup, and the filename to which the messages should be written. It will connect to the server, download the most recent 10 messages from that newsgroup, and then quit:

```
$ python nntpdownload.py freetext.usenetserver.com comp.lang.python \
```

```
> comp.lang.python-latest.mbox
Fetching article 1 of 10... OK
Fetching article 2 of 10... OK
Fetching article 3 of 10... OK
Fetching article 4 of 10... OK
Fetching article 5 of 10... OK
Fetching article 6 of 10... OK
Fetching article 7 of 10... OK
Fetching article 8 of 10... OK
Fetching article 9 of 10... OK
Fetching article 10 of 10... OK
```

9.2.2. How Does That Work?

The `NNTPGroupDownloadProtocol` class, a subclass of `nntp.NNTPClient`, does most of the work in `nntpdownload.py`. The `self.fetchGroup` method asks the server for information about the newsgroup. When the server responds, `gotGroup` is called with the returned information: the total number of articles in the group, the index of the first article, the index of the last article, and the group name.

`NNTPGroupDownloadProtocol` then goes back the number of articles specified by `self.factory.articleCount` (unless there aren't that many messages, in which case it just goes back to the first available article) and uses Python's `range` function to create a list of every number from the starting message index to the ending message index. Then it calls `fetchNextArticle` to begin downloading the set of messages.

`fetchNextArticle` takes the remaining list of article indexes and downloads the first one with a call to `self.fetchArticle`. The `gotArticle` method, called when the article has been successfully downloaded, passes the article data to `self.factory.handleArticle`, and then calls `self.fetchArticle` again. If an article download fails, the `gotArticleFailed` method will be called. `gotArticleFailed` prints an error message, but doesn't abort the entire operation; instead, it simply goes on to the next message.



An alternative to the approach used here is to use the `fetchNewNews` method, which takes a date and returns a list of all the articles posted since. Unfortunately, the underlying `NEWNEWS` command is not supported by many servers.

Because Usenet articles are in the same format as email, they can be stored in the same Unix *mbox* format used by the mail client examples shown in [Chapter 7](#). The `NNTPGroupDownloadFactory`'s `handleArticle` method parses the message using the `email` module and writes it to the output file in *mbox* format, followed by two blank lines to ensure that it will be clearly delimited from the next article in the file.

[< Day Day Up >](#)

9.3. Posting a Message to an NNTP Server

While you're connected to an NNTP server, you can post messages to Usenet. Usenet articles are in the same basic format as email, but with some slightly stricter rules about required headers. You can read the full article format specification in RFC 1036 (<http://www.faqs.org/rfc/rfc1036.txt>). After you post an article through NNTP, your local NNTP server will pass it on to the other servers it knows about. From there, the article will continue to be passed from server to server until it's available throughout the Usenet network.

9.3.1. How Do I Do That?

Construct an article using the `email.Message` module (see [Example 9-3](#)). Select the newsgroup to which you'll be posting, and then post the article.

Example 9-3. `nttpost.py`

```
from twisted.news import nntp
from twisted.internet import protocol, defer
import time, email

class NNTPPostProtocol(nntp.NNTPClient):

    def connectionMade(self):
        nntp.NNTPClient.connectionMade(self)
        self.fetchGroup(self.factory.newsgroup)

    def gotGroup(self, groupInfo):
        # post the article to the current newsgroup

        self.postArticle(self.factory.articleData)

    def postedOk(self):
        self.factory.deferred.callback(None)
```

```

def postFailed(self, errorMessage):
    self.factory.deferred.errback(Exception(errorMessage))

def connectionLost(self, error):
    if not self.factory.deferred.called:
        self.factory.deferred.errback(error)

class NNTPPostFactory(protocol.ClientFactory):
    protocol = NNTPPostProtocol

    def __init__(self, newsgroup, articleData):
        self.newsgroup = newsgroup
        self.articleData = articleData
        self.deferred = defer.Deferred()

from email.Message import Message
from email.Utils import make_msgid

def makeArticle(sender, newsgroup, subject, body):
    article = Message()
    article["From"] = sender
    article["Newsgroups"] = newsgroup
    article["Subject"] = subject
    article["Message-Id"] = make_msgid()
    article.set_payload(body)
    return article.as_string(unixfrom=False)

if __name__ == "__main__":
    from twisted.internet import reactor
    import sys

    def handleError(error):

```

```

print >> sys.stderr, error.getErrorMessage( )

reactor.stop( )

if len(sys.argv) != 3:
    print >> sys.stderr, "Usage: %s server newsgroup" % sys.argv[0]
    sys.exit(1)

server, newsgroup = sys.argv[1:3]
sender = raw_input("From: ")
subject = raw_input("Subject: ")
bodyLines = []
while True:
    line = raw_input( )
    if line == ".": break
    bodyLines.append(line)
body = "\n".join(bodyLines)
articleData = makeArticle(sender, newsgroup, subject, body)
print articleData
factory = NNTPPostFactory(newsgroup, articleData)
factory.deferred.addCallback(
    lambda _: reactor.stop( )).addErrback(
    handleError)
reactor.connectTCP(server, 119, factory)
reactor.run( )

```

Run *nttpost.py* with two arguments: the newsgroup and the NNTP server. It will prompt you to enter your article, connect to the server, and post your article to the newsgroup:

```

$ python nttpost.py alt.local.test localhost
From: abe@fettig.net
Subject: Test Message
Enter article body below, followed by a single period:
Hello Usenet World!

```

Posting message.... done!



Don't post test messages to public newsgroups, except for `alt.test`, which is set aside specifically for testing purposes. If you want to run a private NNTP server so you can post test messages without disturbing anyone, see "[Running a Basic NNTP Server](#)," later in this chapter.

9.3.2. How Does That Work?

In [Example 9-3](#), the `makeArticle` function uses the `email.Message.Message` class to create an article in the proper format for posting to Usenet. It sets the following headers:

From

The email address of the person posting the article. This header is the same as in an email message.

Newsgroups

The list of newsgroups to which the article is being posted. If the message is being posted to multiple newsgroups, they should be separated by commas.

Subject

The subject, just like in an email message.

Message-Id

A globally unique identifier for this article, in the form `<uniqueid@sending.host>`. This is the same as the `Message-Id` header in an email message. It's important to use something truly unique, as the message ID will be used to identify this specific article as it moves from server to server in Usenet. The `email.Utils` module provides the helpful function `make_msgid` for generating unique message IDs.

Date

The date and time the article was created. This header is the same as in an email message. The function `formatdate` in `email.Utils` will take the floating-point number returned from `time.time` or `time.gmtime` and return a string in the proper format. If called with no arguments, as in [Example 9-3](#), it returns the formatted current time.

The body of the article is a standard text message, which you add to the `Message` object using `set_payload`.

The `NNTPPostProtocol` class in [Example 9-3](#) posts an article to the server using the `postArticle` method of `nntp.NNTPClient`. The `postedOK` method will be called if the article is posted successfully; the `postFailed` method will be called if it fails. Note that `postArticle` doesn't take the name of the

newsgroup as an argument: the article will be posted to whatever newsgroups are listed in the Newsgroups header.

[< Day Day Up >](#)

9.4. Running a Basic NNTP Server

The `twisted.news` package includes classes for building NNTP servers. The server architecture is designed in two layers: the `Factory` and `Protocol`, which communicate with clients; and the news storage interface, which is responsible for reading and storing articles. `twisted.news` comes with working examples of the news storage interface, which you can use to create a functional NNTP server in just a few lines of code.

9.4.1. How Do I Do That?

Create a `database.NewsShelf` object, which implements the `database.INewsStorage` interface. Pass the `NewsShelf` object to a `news.NNTPFactory` object, and listen on port 119. As [Example 9-4](#) shows, this is very easy to do.

Example 9-4. `tinynntpserver.py`

```
from twisted.internet import reactor

from twisted.news import database, news, nntp

GROUPS = [
    'local.programming',
    'local.programming.python',
    'local.knitting',
]

SMTP_SERVER = 'upstream-server.com'
STORAGE_DIR = 'storage'

newsStorage = database.NewsShelf(SMTP_SERVER, STORAGE_DIR)

for group in GROUPS:
    newsStorage.addGroup(group, [])

factory = news.NNTPFactory(newsStorage)

reactor.listenTCP(119, factory)


reactor.run( )
```

Run this example from the command line, without any arguments:

```
$ python tinyntpserver.py
```


Then connect to [localhost](#) using a newsreader application. You should be able to see the list of available newsgroups, as in [Figure 9-1](#).

Figure 9-1. Browsing the list of newsgroups



Subscribe to the newsgroups, and you should be able to read and post articles. If you connect with multiple clients, you'll be able to start discussions and reply to each other's articles, as shown in [Figure 9-2](#).

Figure 9-2. Reading and posting messages



9.4.2. How Does That Work?


The `database.NewsShelf` class is an implementation of `database.INewsStorage` that stores articles using a `twisted.persisted.dirdbm.Shelf`. `dirdbm.Shelf` is a useful class that works like a dictionary, but writes its data to a directory so that it can persist after the program exists. The `NewsShelf` class is initialized with two arguments: the hostname of an SMTP server (which it will use for sending notification messages to the server administrator) and the directory where it should store article data.

Once you've created a `NewsShelf` object, all you have to do is pass it to a `news.NNTPFactory` object. This factory uses `nntp.NNTPServer` for a protocol, which is designed to work with any implementation of `database.INewsStorage`.

[< Day Day Up >](#)

9.5. Using NNTP as a User Interface

NNTP was designed to be a protocol for working with Usenet. But this doesn't prevent it from being used to access other kinds of messaging systems. Like the email protocols discussed in [Chapter 7](#), you can use NNTP as an interface, a way to let users interact with your application's data. For example, you could provide an NNTP interface to a web discussion board. This would allow users familiar with Usenet to participate in the discussion board using their Usenet client, taking advantage of features like offline message reading, message threading, and spellcheck. NNTP is a good protocol to use any time you want to offer a public (nonauthenticated) means of reading and writing messages. This example demonstrates how you could use `twisted.news` to provide an NNTP interface to a popular type of public message: RSS news feeds.



9.5.1. How Do I Do That?

Write a class that implements `twisted.news.database.INewsStorage` and makes your data available as a set of newsgroups and articles. If you need to do an asynchronous task in an `INewsStorage` method, you can return a `Deferred`. This lets you write an NNTP server, such as that in [Example 9-5](#), which acts as a proxy to data that lives elsewhere on the network.

Example 9-5. `rss2nntp.py`

```
from twisted.internet import reactor, defer

from twisted.news import database, news, nntp

from twisted.web import client, microdom

from zope.interface import implements

from cStringIO import StringIO

from email.Message import Message

import email.Utils

import socket, time, md5

GROUPS = {

    "rss.slashdot": "http://www.slashdot.org/slashdot.rdf",

    "rss.abefettig": "http://fettig.net/xml/rss2.xml",
```

```
}

```

```
class RssFeed(object):
    refreshRate = 60*60 # hourly refresh

    def __init__(self, groupName, feedUrl):
        self.title = ""
        self.groupName = groupName
        self.feedUrl = feedUrl
        self.articles = []
        self.articlesById = {}
        self.lastRefreshTime = 0
        self.refreshing = None

    def refreshIfNeeded(self):
        timeSinceRefresh = time.time( ) - self.lastRefreshTime
        if timeSinceRefresh > self.refreshRate:
            if not self.refreshing:
                self.refreshing = client.getPage(self.feedUrl).addCallback(
                    self._gotFeedData).addErrback(
                        self._getDataFailed)
                d = defer.Deferred( )
                self.refreshing.chainDeferred(d)
                return d
            else:
                return defer.succeed(None)

    def _gotFeedData(self, data):
        print "Loaded feed data from %s" % self.feedUrl
        self.refreshing = None
        self.lastRefreshTime = time.time( )

        # this is a naive and brittle way to parse RSS feeds.
```

```

# It should work for most well-formed feeds, but will choke
# if the feed has a structure that doesn't meet its
# expectations. In the real world, you'd want to use a
# more robust means of parsing feeds, such as FeedParser
# (http://feedparser.org) or Yarn (http://yarnproject.org).

```

```

xml = microdom.parseString(data)

self.title = xml.documentElement.getElementsByTagName(
    'title')[0].childNodes[0].data

items = xml.documentElement.getElementsByTagName('item')

for item in items:
    rssData = {}

    for field in 'title', 'link', 'description':
        nodes = item.getElementsByTagName(field)

        if nodes:
            rssData[field] = nodes[0].childNodes[0].data

        else:
            rssData[field] = ''

    guid = md5.md5(
        rssData['title'] + rssData['link']).hexdigest()

    articleId = "<%s@%s>" % (guid, socket.getfqdn())

    if not self.articlesById.has_key(articleId):
        article = Message()

        article['From'] = self.title

        article['Newsgroups'] = self.groupName

        article['Message-Id'] = articleId

        article['Subject'] = rssData['title']

        article['Date'] = email.Utils.formatdate()

        body = "%s\r\n\r\n%s" % (
            rssData['description'], rssData['link'])

        article.set_payload(body)

        self.articles.append(article)

        self.articlesById[articleId] = article

```

```

def _getDataFailed(self, failure):
    print "Failed to load RSS data from %s: %s" % (
        self.feedUrl, failure.getErrorMessage( ))
    self.refreshing = None
    return failure

def _refreshComplete(self, _):
    # schedule another refresh
    reactor.callLater(self.refreshRate, self.refresh)

class RssFeedStorage(object):
    "keeps articles in memory, loses them when the process exits"
    implements(database.INewsStorage)

    def __init__(self, feeds):
        "feeds is a dict of {groupName:url}"
        self.feeds = {}
        for groupName, url in feeds.items( ):
            self.feeds[groupName] = RssFeed(groupName, url)

    def refreshAllFeeds(self):
        refreshes = [feed.refreshIfNeeded( ) for feed in self.feeds.values( )]
        return defer.DeferredList(refreshes)

    def _refreshAllFeedsAndCall(self, func, *args, **kwargs):
        "refresh all feeds and then return the results of calling func"
        return self.refreshAllFeeds( ).addCallback(
            lambda _: func(*args, **kwargs))

    def _refreshFeedAndCall(self, groupName, func, *args, **kwargs):
        "refresh one feed and then return the results of calling func"
        if self.feeds.has_key(groupName):
            feed = self.feeds[groupName]

```

```

        return feed.refreshIfNeeded( ).addCallback(
            lambda _: func(*args, **kwargs))
    else:
        return defer.fail(KeyError(groupName))

def listRequest(self):
    """
    List information about the newsgroups on this server.
    Returns a Deferred which will call back with a list of tuples
    in the form
    (groupname, messageCount, firstMessage, postingAllowed)
    """
    return self._refreshAllFeedsAndCall(self._listRequest)

def _listRequest(self):
    groupInfo = []
    for feed in self.feeds.values( ):
        # set to 'y' to indicate that posting is allowed
        postingAllowed = 'n'
        groupInfo.append(
            (feed.groupName, len(feed.articles), 0, postingAllowed))
    return groupInfo

def listGroupRequest(self, groupname):
    "return the list of message indexes for the group"
    return self._refreshFeedAndCall(groupname, self._listGroupRequest,
                                    groupname)

def _listGroupRequest(self, groupname):
    feed = self.feeds[groupname]
    return range(len(feed.articles))

def subscriptionRequest(self):
    "return the list of groups the server recommends to new users"

```

```

return defer.succeed(self.feeds.keys( ))

def overviewRequest(self):
    """
    Return a list of headers that will be used for giving
    an overview of a message. twisted.news.database.OVERVIEW_FMT
    is such a list.
    """
    return defer.succeed(database.OVERVIEW_FMT)

def groupRequest(self, groupName):
    """
    Return a tuple of information about the group:
    (groupName, articleCount, startIndex, endIndex, flags)
    """
    return self._refreshFeedAndCall(groupName,
                                    self._groupRequest,
                                    groupName)

def _groupRequest(self, groupName):
    feed = self.feeds[groupName]
    groupInfo = (groupName,
                 len(feed.articles),
                 len(feed.articles),
                 0,
                 {})
    return defer.succeed(groupInfo)

def xoverRequest(self, groupName, low, high):
    """
    Return a list of tuples, once for each article between low and high.
    Each tuple contains the article's values of the headers that
    were returned by self.overviewRequest.

```

```

"""
return self._refreshFeedAndCall(groupName,
                                self._processXOver,
                                groupName, low, high,
                                database.OVERVIEW_FMT)

def xhdrRequest(self, groupName, low, high, header):
    """
    Like xoverRequest, except that instead of returning all the
    header values, it should return only the value of a single header.
    """
    return self._refreshFeedAndCall(groupName,
                                    self._processXOver,
                                    groupName, low, high,
                                    [header])

def _processXOver(self, groupName, low, high, headerNames):
    feed = self.feeds[groupName]
    if low is None: low = 0
    if high is None: high = len(feed.articles)-1
    results = []
    for i in range(low, high+1):
        article = feed.articles[i]
        articleData = article.as_string(unixfrom=False)
        headerValues = [i]
        for header in headerNames:
            # check for special headers
            if header == 'Byte-Count':
                headerValues.append(len(articleData))
            elif header == 'Line-Count':
                headerValues.append(len(articleData.split('\n')))
            else:
                headerValues.append(article.get(header, ''))

```

```

        results.append(headerValues)
    return defer.succeed(results)

def articleExistsRequest(self, groupName, id):
    feed = self.feeds[groupName]
    return defer.succeed(feed.articlesById.has_key(id))

def articleRequest(self, groupName, index, messageId=None):
    """
    Return the contents of the article specified by either
    index or message ID
    """
    feed = self.feeds[groupName]
    if messageId:
        message = feeds.articlesById(messageId)
        # look up the index
        index = feed.articles.index(message)
    else:
        message = feed.articles[index]
        # look up the message ID
        for mId, m in feed.articlesById.items():
            if m == message:
                messageId = mId
                break
    messageData = message.as_string(unixfrom=False)
    return defer.succeed((index, id, (StringIO(messageData))))

def headRequest(self, groupName, index):
    "return the headers of them message at index"
    group = self.groups[groupName]
    article = group.articles[index]
    return defer.succeed(article.getHeaders())

```

```

def bodyRequest(self, groupName, index):
    "return the body of the message at index"
    group = self.groups[groupName]
    article = group.articles[index]
    return defer.succeed(article.body)

def postRequest(self, message):
    "post the message."
    return defer.fail(Exception("RSS feeds are read-only."))

class DebuggingNNTPProtocol(nntp.NNTPServer):
    debug = True

    def lineReceived(self, line):
        if self.debug:
            print "CLIENT:", line
        nntp.NNTPServer.lineReceived(self, line)

    def sendLine(self, line):
        nntp.NNTPServer.sendLine(self, line)
        if self.debug:
            print "SERVER:", line

class DebuggingNNTPFactory(news.NNTPFactory):
    protocol = DebuggingNNTPProtocol

if __name__ == "__main__":
    factory = DebuggingNNTPFactory(RssFeedStorage(GROUPS))
    reactor.listenTCP(119, factory)
    reactor.run( )


```

Run `rss2nntp.py` without any arguments:

```
$ python rss2nntp.py
```

Then connect to localhost using a news reader. The `DebuggingNNTPProtocol` class in `rss2nntp.py` causes the server to print a log of all the commands and replies sent between the client and server, so you'll be able to see what's going on behind the scenes. Figure 9-3 shows how the server will download RSS feeds on demand and present the contents of the feeds through NNTP.

Figure 9-3. Reading an RSS feed through NNTP



9.5.2. How Does That Work?

Although it has a lot more code, the `rss2nntp.py` program in Example 9-5 follows the same design as the minimal NNTP server in Example 9-4. The difference is that this time the program includes its own implementation of `database.InewsStorage`, instead of using one of the storage backends that come with `twisted.news`.

The `RssFeedStorage` class has all the methods required by `INewsStorage`. You can identify these messages because they end with `Request`. The `RssFeedStorage` object keeps a collection of `RssFeed` objects in a list called `feeds`. Each `RssFeed` object loads messages from the RSS feed at a certain URL.

RSS feeds have to be periodically polled for new messages. The `RssFeed` object has a method called `refreshIfNecessary` that will compare `self.lastRefreshTime` to `self.refreshRate` and decide whether the feed needs to be refreshed. If it does, `refreshIfNecessary` will return a `Deferred` that issues a callback after the feed has been downloaded and checked for new messages. Otherwise, it will return a `Deferred` that calls back immediately. If you want to make sure that the feed is up-to-date before you run a certain function, you can call `refreshIfNecessary` and assign the function as a callback handler:

```
myfeed.refreshIfNecessary( ).addCallback(  
    lambda _: myFunctionThatNeedsFreshData)
```

The `RssFeedStorage` class in [Example 9-5](#) has a method called `_refreshFeedAndCall` that sets up a function to be the callback handler for `refreshIfNecessary`. The method `_refreshAllFeedsAndCall` works the same way, but uses a `DeferredList` to manage calling `refreshIfNecessary` on all available feeds. These methods are used in places where `RssFeedStorage` wants to make sure it has up-to-date feed data before it returns a result.

When implementing a complex interface like `INewsStorage`, there are bound to be bugs. You might return data in the wrong format, confusing the NNTP client on the other end. To make it easier to debug problems during development, [Example 9-5](#) includes the `DebuggingNNTPProtocol` class, which inherits from `nntp.NNTPProtocol` and adds print statements, so you can view the commands and replies sent between the client and server.

< Day Day Up >

Chapter 10. SSH

SSH, the Secure SHell, is an essential tool for many developers and administrators. SSH provides a way to establish encrypted, authenticated connections. The most common use of an SSH connection is to get a remote shell, but it's possible to do many other things through SSH as well, including transferring files and tunneling other connections.

The `twisted.conch` package adds SSH support to Twisted. This chapter shows how you can use the modules in `twisted.conch` to build SSH servers and clients.

10.1. Setting Up a Custom SSH Server

The command line is an incredibly efficient interface for certain tasks. System administrators love the ability to manage applications by typing commands without having to click through a graphical user interface. An SSH shell is even better, as it's accessible from anywhere on the Internet.

You can use `twisted.conch` to create an SSH server that provides access to a custom shell with commands you define. This shell will even support some extra features like command history, so that you can scroll through the commands you've already typed.

10.1.1. How Do I Do That?

Write a subclass of `twisted.conch.recvline.HistoricRecvLine` that implements your shell protocol. `HistoricRecvLine` is similar to `twisted.protocols.basic.LineReceiver`, but with higher-level features for controlling the terminal.

To make your shell available through SSH, you need to implement a few different classes that `twisted.conch` needs to build an SSH server. First, you need the `twisted.cred` authentication classes : a portal, credentials checkers, and a realm that returns avatars. Use `twisted.conch.avatar.ConchUser` as the base class for your avatar. Your avatar class should also implement `twisted.conch.interfaces.ISession`, which includes an `openShell` method in which you create a `Protocol` to manage the user's interactive session. Finally, create a `twisted.conch.ssh.factory.SSHFactory` object and set its `portal` attribute to an instance of your portal.

[Example 10-1](#) demonstrates a custom SSH server that authenticates users by their username and password . It gives each user a shell that provides several commands.

Example 10-1. sshserver.py

```
from twisted.cred import portal, checkers, credentials
from twisted.conch import error, avatar, recvline, interfaces as conchinterfaces
from twisted.conch.ssh import factory, userauth, connection, keys, session, common
from twisted.conch.insults import insults
from twisted.application import service, internet
from zope.interface import implements
import os

class SSHDemoProtocol(recvline.HistoricRecvLine):
```

```

def __init__(self, user):
    self.user = user

def connectionMade(self):
    recvline.HistoricRecvLine.connectionMade(self)
    self.terminal.write("Welcome to my test SSH server.")
    self.terminal.nextLine( )
    self.do_help( )
    self.showPrompt( )

def showPrompt(self):
    self.terminal.write("$ ")

def getCommandFunc(self, cmd):
    return getattr(self, 'do_' + cmd, None)

def lineReceived(self, line):
    line = line.strip( )
    if line:
        cmdAndArgs = line.split( )
        cmd = cmdAndArgs[0]
        args = cmdAndArgs[1:]
        func = self.getCommandFunc(cmd)
        if func:
            try:
                func(*args)
            except Exception, e:
                self.terminal.write("Error: %s" % e)
                self.terminal.nextLine( )
        else:
            self.terminal.write("No such command.")
            self.terminal.nextLine( )
    self.showPrompt( )

```

```

def do_help(self, cmd=''):
    "Get help on a command. Usage: help command"
    if cmd:
        func = self.getCommandFunc(cmd)
        if func:
            self.terminal.write(func.__doc__ )
            self.terminal.nextLine( )
            return

    publicMethods = filter(
        lambda funcname: funcname.startswith('do_'), dir(self))
    commands = [cmd.replace('do_', '', 1) for cmd in publicMethods]
    self.terminal.write("Commands: " + " ".join(commands))
    self.terminal.nextLine( )

def do_echo(self, *args):
    "Echo a string. Usage: echo my line of text"
    self.terminal.write(" ".join(args))
    self.terminal.nextLine( )

def do_whoami(self):
    "Prints your user name. Usage: whoami"
    self.terminal.write(self.user.username)
    self.terminal.nextLine( )

def do_quit(self):
    "Ends your session. Usage: quit"
    self.terminal.write("Thanks for playing!")
    self.terminal.nextLine( )
    self.terminal loseConnection( )

def do_clear(self):
    "Clears the screen. Usage: clear"

```

```
self.terminal.reset( )
```

```
class SSHDemoAvatar(avatar.ConchUser):
    implements(conchinterfaces.ISession)

    def __init__(self, username):
        avatar.ConchUser.__init__(self)
        self.username = username
        self.channelLookup.update({'session':session.SSHSession})

    def openShell(self, protocol):
        serverProtocol = insults.ServerProtocol(SSHDemoProtocol, self)
        serverProtocol.makeConnection(protocol)
        protocol.makeConnection(session.wrapProtocol(serverProtocol))

    def getPty(self, terminal, windowSize, attrs):
        return None

    def execCommand(self, protocol, cmd):
        raise NotImplementedError

    def closed(self):
        pass

class SSHDemoRealm:
    implements(portal.IRealm)

    def requestAvatar(self, avatarId, mind, *interfaces):
        if conchinterfaces.IConchUser in interfaces:
            return interfaces[0], SSHDemoAvatar(avatarId), lambda: None
        else:
            raise Exception, "No supported interfaces found."
```

```

def getRSAKeys( ):
    if not (os.path.exists('public.key') and os.path.exists('private.key')):
        # generate a RSA keypair
        print "Generating RSA keypair..."
        from Crypto.PublicKey import RSA
        KEY_LENGTH = 1024
        rsaKey = RSA.generate(KEY_LENGTH, common.entropy.get_bytes)
        publicKeyString = keys.makePublicKeyString(rsaKey)
        privateKeyString = keys.makePrivateKeyString(rsaKey)
        # save keys for next time
        file('public.key', 'w+b').write(publicKeyString)
        file('private.key', 'w+b').write(privateKeyString)
        print "done."
    else:
        publicKeyString = file('public.key').read( )
        privateKeyString = file('private.key').read( )
    return publicKeyString, privateKeyString

if __name__ == "__ _main_ _":
    sshFactory = factory.SSHFactory( )
    sshFactory.portal = portal.Portal(SSHDemoRealm( ))
    users = {'admin': 'aaa', 'guest': 'bbb'}
    sshFactory.portal.registerChecker(
        checkers.InMemoryUsernamePasswordDatabaseDontUse(**users))

    pubKeyString, privKeyString = getRSAKeys( )
    sshFactory.publicKeys = {
        'ssh-rsa': keys.getPublicKeyString(data=pubKeyString)}
    sshFactory.privateKeys = {
        'ssh-rsa': keys.getPrivateKeyObject(data=privKeyString)}

    from twisted.internet import reactor
    reactor.listenTCP(2222, sshFactory)
    reactor.run( )

```

sshsrvr.py will run an SSH server on port 2222. Connect to this server with an SSH client using the username **admin** and password **aaa**, and try typing some commands:

```
$ ssh admin@localhost -p 2222
admin@localhost's password: aaa

>>> Welcome to my test SSH server.

Commands: clear echo help quit whoami

$ whoami

admin

$ help echo

Echo a string. Usage: echo my line of text

$ echo hello SSH world!

hello SSH world!

$ quit

Connection to localhost closed.
```



If you've already been using an SSH server on your local machine, you might get an error when you try to connect to the server in this example. You'll get a message saying something like "Remote host identification has changed" or "Host key verification failed," and your SSH client will refuse to connect.

The reason you get this error message is that your SSH client is remembering the public key used by your regular [localhost](#) SSH server. The server in [Example 10-1](#) has its own key, and when the client sees that the keys are different, it gets suspicious that this new server may be an impostor pretending to be your regular [localhost](#) SSH server. To fix this problem, edit your `~/.ssh/known_hosts` file (or wherever your SSH client keeps its list of recognized servers) and remove the [localhost](#) entry.

10.1.2. How Does That Work?

The `SSHDemoProtocol` class in [Example 10-1](#) inherits from `twisted.conch.recvline.HistoricRecvLine`. `HistoricRecvLine` is a protocol with built-in features for building command-line shells. It gives your shell features that most people take for granted in a modern shell, including backspacing, the ability to use the arrow keys to move the cursor forwards and backwards on the current line, and a command history that can be accessed using the up and down arrows. `twisted.conch.recvline` also provides a plain `RecvLine` class that works the same way, but without the command history.

The `lineReceived` method in `HistoricRecvLine` is called whenever a user enters a line. [Example 10-1](#) shows how you might override this method to parse and execute commands. There are a couple of differences between `HistoricRecvLine` and a regular `Protocol`, which come from the fact that with `HistoricRecvLine` you're actually manipulating the current contents of a user's terminal window, rather than just printing out text. To print a line of output, use `self.terminal.write`; to go to the next line, use `self.nextLine`.

The `twisted.conch.avatar.ConchUser` class represents the actions available to an authenticated SSH user. By default, `ConchUser` doesn't allow the client to do anything. To make it possible for the user to get a shell, make his avatar implement `twisted.conch.interfaces.ISession`. The `SSHDemoAvatar` class in [Example 10-1](#) doesn't actually implement all of `ISession`; it only implements enough for the user to get a shell. The `openShell` method will be called with a `twisted.conch.ssh.session.SSHSessionProcessProtocol` object that represents the encrypted client's end of the encrypted channel. You have to perform a few steps to connect the client's protocol to your shell protocol so they can communicate with each other. First, wrap your protocol class in a `twisted.conch.insults.insults.ServerProtocol` object. You can pass extra arguments to `insults.ServerProtocol`, and it will use them to initialize your protocol object. This sets up your protocol to use a virtual terminal. Then use `makeConnection` to connect the two protocols to each other. The client's protocol actually expects `makeConnection` to be called with a an object implementing the lower-level `twisted.internet.interfaces.ITransport` interface, not a `Protocol`; the `twisted.conch.session.wrapProtocol` function wraps a `Protocol` in a minimal `ITransport` interface.



The library traditionally used for manipulating a Unix terminal is called *curses*. So the Twisted developers, never willing to pass up the chance to use a pun in a module name, chose the name *insults* for this library of classes for terminal programming.

To make a realm for your SSH server, write a class that has a `requestAvatar` method. The SSH server will call `requestAvatar` with the username as `avatarId` and `twisted.conch.interfaces.IAvatar` as one of the interfaces. Return your subclass of `twisted.conch.avatar.ConchUser`.

There's only one more thing you'll need to have a complete SSH server: a unique set of public and private keys. [Example 10-1](#) demonstrates how you can use the `Crypto.PublicKey.RSA` module to generate these keys. `RSA.generate` takes a key length as the first argument and an entropy-generating function as the second argument; the `twisted.conch.ssh.common` module provides the `entropy.get_bytes` function for this purpose. `RSA.generate` returns a `Crypto.PublicKey.RSA.RSAobj` object. You extract public and private key strings from the `RSAobj` by passing it to the `getPublicKeyString` and `getPrivateKeyString` functions from the `twisted.conch.ssh.keys` module. [Example 10-1](#) saves its keys to disk after generating them the first time it runs: you need to keep these keys preserved between clients so clients can identify and trust your sever.





Note that you wouldn't want to call `RSA.generate` after your program has entered the Twisted event loop. `RSA.generate` is a blocking function that can take quite some time to complete.

To run the SSH server , create a `twisted.conch.ssh.factory.SSHFactory` object. Set its `portal` attribute to a portal using your realm, and register a credentials checker that can handle `twisted.cred.credentials.IUsernamePassword` credentials. Set the `SSHFactory`'s `publicKeys` attribute to a dictionary that matches encryption algorithms to key string objects. To get the RSA key string object, pass your public key as the `data` keyword to `keys.getPublicKeyString`. Then set the `privateKeys` attribute to a dictionary that matches protocols to key objects. To get the RSA private key object , pass your private key as the `data` keyword to `keys.getPrivateKey`. Both `getPublicKeyString` and `getPrivateKey` can take a `filename` keyword instead, to load a key directly from a file. Once the `SSHFactory` has the keys, it's ready to go. Call `reactor.listenTCP` to have it start listening on a port and you've got an SSH server .

[< Day Day Up >](#)

10.2. Using Public Keys for Authentication

The SSH server in [Example 10-1](#) used usernames and passwords for authentication. But heavy SSH users will tell you that one of the nicest features of SSH is its support for key-based authentication. With key-based authentication, the server is given a copy of a user's private key. When the user tries to log in, the server asks her to prove her identity by signing some data with her private key. The server then checks the signed data against its copy of the user's public key.

In practice, using public keys for authentication is nice, because it saves the user from having to manage a lot of passwords. A user can use the same key for multiple servers. She can choose to password-protect her key for extra security, or she can use a key with no password for a completely transparent login process.

This lab shows you how to set up a Twisted SSH server to use public key authentication. It uses the same server code as [Example 10-1](#), but with a new authentication backend.

10.2.1. How Do I Do That?

Store a public key for each user. Write a credentials checker that accepts credentials implementing `twisted.conch.credentials.ISSHPrivateKey`. Verify the user's credentials by checking to make sure that his public key matches the key you have stored, and that his signature proves that the user possesses the matching private key. [Example 10-2](#) shows how to do this.

Example 10-2. pubkeyssh.py

```
from sshserver import SSHDemoRealm, getRSAKeys
from twisted.conch import credentials, error
from twisted.conch.ssh import keys, factory
from twisted.cred import checkers, portal
from twisted.python import failure
from zope.interface import implements
import base64

class PublicKeyCredentialsChecker:
    implements(checkers.ICredentialsChecker)
    credentialInterfaces = (credentials.ISSHPrivateKey,)

    def __init__(self, authorizedKeys):
        self.authorizedKeys = authorizedKeys
```

```

def requestAvatarId(self, credentials):
    if self.authorizedKeys.has_key(credentials.username):
        userKey = self.authorizedKeys[credentials.username]
        if not credentials.blob == base64.decodestring(userKey):
            raise failure.Failure(
                error.ConchError("I don't recognize that key"))
        if not credentials.signature:
            return failure.Failure(error.ValidPublicKey( ))
        pubKey = keys.getPublicKeyObject(data=credentials.blob)
        if keys.verifySignature(pubKey, credentials.signature,
                                credentials.sigData):
            return credentials.username
        else:
            return failure.Failure(
                error.ConchError("Incorrect signature"))
    else:
        return failure.Failure(error.ConchError("No such user"))

if __name__ == "__main__":
    sshFactory = factory.SSHFactory( )
    sshFactory.portal = portal.Portal(SSHDemoRealm( ))
    authorizedKeys = {
        "admin":
"AAAAB3NzaC1yc2EAAAABIWAAAIEAxIfv4ICpuKFAGAr2cJsQjUZsZ4VAsA1c9TXYEc2Ue1lp781q0rm/
nQTlK9lg+YEBRxCPCgymaz60cjGspqqoQ35qPiwJ4xgVUeYKfxs+ZS13YGIODVfsqLYxLl33b6yCnE0bfBjEPmb9P
OkL2TA1owlBfTL2+t+Hbx+c1DCwE="
    }
    sshFactory.portal.registerChecker(
        PublicKeyCredentialsChecker(authorizedKeys))

    pubKeyString, privKeyString = getRSAKeys( )
    sshFactory.publicKeys = {

```

```

    'ssh-rsa': keys.getPublicKeyString(data=pubKeyString) }

sshFactory.privateKeys = {

    'ssh-rsa': keys.getPrivateKeyObject(data=privKeyString) }

from twisted.internet import reactor

reactor.listenTCP(2222, sshFactory)

reactor.run( )

```

To test this example, you'll need to generate a public key, if you don't have one already. The OpenSSH SSH implementation that comes with most Linux distributions (and also with Mac OS X) includes a command-line utility named *ssh-keygen* that you can use to generate a new private/public key pair:

```

$ ssh-keygen -t rsa

Generating public/private rsa key pair.

Enter file in which to save the key (/home/abe/.ssh/id_rsa):

Enter passphrase (empty for no passphrase):

Enter same passphrase again:

Your identification has been saved in /home/abe/.ssh/id_rsa.

Your public key has been saved in /home/abe/.ssh/id_rsa.pub.

The key fingerprint is:

6b:13:3a:6e:c3:76:50:c7:39:c2:e0:8b:06:68:b4:11 abe@sparky

```



Windows users can generate keys with PuTTYgen, which is distributed along with the popular free PuTTY SSH client (<http://www.chiark.greenend.org.uk/~sgtatham/putty/download.html>).

Once you've generated a key, you can get the public key from the file `~/.ssh/id_rsa.pub`. Edit [Example 10-2](#) to use your public key for the `admin` user in the `authorizedKeys` dictionary. Then run `pubkeyssh.py` to start the server on port 2222. You should log right in without being prompted for a password:

```

$ ssh admin@localhost -p 2222

>>> Welcome to my test SSH server.

```

```
Commands: clear echo help quit whoami
```

```
$
```

If you try to log in as a user who doesn't possess the matching private key, you'll be denied access:

```
$ ssh admin@localhost -p 2222
Permission denied (publickey).
```

10.2.2. How Does That Work?

Example 10-2 reuses most of the SSH server classes from **Example 10-1**. To support public key authentication, it uses a new credentials checker class named `PublicKeyCredentialsChecker`. `PublicKeyCredentialsChecker` accepts credentials implementing `ISSHPrivateKey`, which have the attributes `username`, `blob`, `signature`, and `sigData`. To verify the key, `PublicKeyCredentialsChecker` goes through three tests. First, it makes sure it has a public key on file for the user `username`. Next, it verifies that the public key provided in `blob` matches the public key it has on file for that user.

It's possible that the user may have provided just the public key at this point, but not a signed token. If the public key was valid, but no signature was provided, `PublicKeyCredentialsChecker.requestAvatar` raises the special exception `twisted.conch.error.ValidPublicKey`. The SSH server will understand the meaning of this exception and ask the client for the missing signature.

Finally, the `PublicKeyCredentialsChecker` uses the function `twisted.conch.ssh.keys.verifySignature` to check whether the data in `signature` really is the data in `sigData` signed with the user's private key. If `verifySignature` returns a true value, authentication is successful, and `requestAvatarId` returns `username` as the avatar ID.



You can support both username/password and key-based authentication in an SSH server. Just register both credentials checkers with your portal.

10.3. Providing an Administrative Python Shell

[Example 10-1](#) demonstrated how to provide an interactive shell through SSH. That example implemented its own language with a small set of commands. But there's another kind of shell that you can run over SSH: the same interactive Python prompt you know and love from the command line.

10.3.1. How Do I Do That?

The `twisted.conch.manhole` and `twisted.conch.manhole_ssh` modules have classes designed to provide a remote interactive Python shell inside your running server. Create a `manhole_ssh.TerminalRealm` object and set its `chainedProtocolFactory.protocolFactory` attribute to a function that will return `manhole.Manhole` objects. [Example 10-3](#) demonstrates a web server that can be modified on the fly using SSH and `twisted.conch.manhole`.

Example 10-3. manholeserver.py

```
from twisted.internet import reactor

from twisted.web import server, resource

from twisted.cred import portal, checkers

from twisted.conch import manhole, manhole_ssh

class LinksPage(resource.Resource):

    isLeaf = 1

    def __init__(self, links):
        resource.Resource.__init__(self)
        self.links = links

    def render(self, request):
        return "<ul>" + "".join([
            "<li><a href='%s'%>%s</a></li>" % (link, title)
            for title, link in self.links.items() ]) + "</ul>"

links = {'Twisted': 'http://twistedmatrix.com/'}
```

```

    'Python': 'http://python.org'}

site = server.Site(LinksPage(links))

reactor.listenTCP(8000, site)

def getManholeFactory(namespace, **passwords):

    realm = manhole_ssh.TerminalRealm( )

    def getManhole(_): return manhole.Manhole(namespace)

    realm.chainedProtocolFactory.protocolFactory = getManhole

    p = portal.Portal(realm)

    p.registerChecker(

        checkers.InMemoryUsernamePasswordDatabaseDontUse(**passwords))

    f = manhole_ssh.ConchFactory(p)

    return f


reactor.listenTCP(2222, getManholeFactory(globals( ), admin='aaa'))

reactor.run( )

```

manholeserver.py will start up a web server on port 8000 and an SSH server on port 2222. [Figure 10-1](#) shows what the home page looks like when the server starts.

Figure 10-1. The default manholeserver.py web page



Now log in using SSH. You'll get a Python prompt, with full access to all the objects in the server. Try modifying the `links` dictionary:

```

$ ssh admin@localhost -p 2222

admin@localhost's password: aaa

```

```

>>> dir( )

['LinksPage', '__builtins__', '__doc__', '__file__', '_ _name_ _', 'checkers',
'getManholeFactory', 'links', 'manhole', 'manhole_ssh', 'portal', 'reactor',
'resource', 'server', 'site']

>>> links

{'Python': 'http://python.org', 'Twisted': 'http://twistedmatrix.com/'}

>>> links["Abe Fettig"] = "http://fettig.net"

>>> links["O'Reilly"] = "http://oreilly.com"

>>> links


{'Python': 'http://python.org', "O'Reilly": 'http://oreilly.com', 'Twisted': 'http://
twistedmatrix.com/', 'Abe Fettig': 'http://fettig.net'}

>>>

```

Then refresh the home page of the web server. [Figure 10-2](#) shows how your changes will be reflected on the web site.

Figure 10-2. The modified manholeserver.py web page



10.3.2. How Does That Work?

[Example 10-3](#) defines a function called `getManholeFactory` that makes running a manhole SSH server trivially easy. `getManholeFactory` takes an argument called `namespace`, which is a dictionary defining which Python objects to make available, and then a number of keyword arguments representing usernames and passwords. It constructs a `manhole_ssh.TerminalRealm` and sets its `chainedProtocolFactory.protocolFactory` attribute to an anonymous function that returns `manhole.Manhole` objects for the requested namespace. It then sets up a portal using the realm and a dictionary of usernames and passwords, attaches the portal to a `manhole_ssh.ConchFactory`, and returns the factory.

Like its name implies, `manhole` provides a portal to something that is off-limits to the she is allowed in, she can do anything she wants. You can pass a dictionary of Python objects as `namespace` only for the sake of convenience (to limit the set of objects the user has to look through), not for security. Only administrative users should have permission to use the `manhole` server.

[Example 10-3](#) creates a `manhole` factory using the built-in `globals()` function, which returns a dictionary of all the objects in the current global namespace. When you log in through SSH, you can see all the global objects in `manholeserver.py`, including the `links` dictionary. Because this dictionary is also being used to generate the home page of the web site, any changes you make through SSH are instantly reflected on the Web.



The `manhole_ssh.ConchFactory` class includes its own default public/private key pair. For your own projects you shouldn't rely on these built-in keys. Instead, generate your own and set the `publicKeys` and `privateKeys` attributes of the `ConchFactory`. See [Example 10-1](#), earlier in this chapter, for an example of how to do this.

< Day Day Up >

10.4. Running Commands on a Remote Server

This lab demonstrates how to write an SSH client. You can use `twisted.conch` to communicate with a server using SSH: logging in, executing commands, and capturing the output.

10.4.1. How Do I Do That?

There are several classes that work together to make up a `twisted.conch.ssh` SSH client. The `Transport.SSHClientTransport` class sets up the connection and verifies the identity of the server. The `userauth.SSHUserAuthClient` logs in using your authentication credentials. The `connection.SSHConnection` class takes over once you've logged in, and creates one or more `channel.SSHChannel` objects, which you then use to communicate with the server over a secure channel. [Example 10-4](#) shows how you can use these classes to make an SSH client that logs into a server, runs a command, and prints the output.

Example 10-4. `sshclient.py`

```
from twisted.conch import error

from twisted.conch.ssh import transport, connection, keys, userauth, channel, common

from twisted.internet import defer, protocol, reactor

class ClientCommandTransport(transport.SSHClientTransport):

    def __init__(self, username, password, command):

        self.username = username

        self.password = password

        self.command = command

    def verifyHostKey(self, pubKey, fingerprint):

        # in a real app, you should verify that the fingerprint matches
        # the one you expected to get from this server

        return defer.succeed(True)

    def connectionSecure(self):

        self.requestService(

            PasswordAuth(self.username, self.password,
```

```
ClientConnection(self.command))
```

```
class PasswordAuth(userauth.SSHUserAuthClient):
    def __init__(self, user, password, connection):
        userauth.SSHUserAuthClient.__init__(self, user, connection)
        self.password = password

    def getPassword(self, prompt=None):
        return defer.succeed(self.password)

class ClientConnection(connection.SSHConnection):
    def __init__(self, cmd, *args, **kwargs):
        connection.SSHConnection.__init__(self)
        self.command = cmd

    def serviceStarted(self):
        self.openChannel(CommandChannel(self.command, conn=self))

class CommandChannel(channel.SSHChannel):
    name = 'session'

    def __init__(self, command, *args, **kwargs):
        channel.SSHChannel.__init__(self, *args, **kwargs)
        self.command = command

    def channelOpen(self, data):
        self.conn.sendRequest(
            self, 'exec', common.NS(self.command), wantReply=True).addCallback(
                self._gotResponse)

    def _gotResponse(self, _):
        self.conn.sendEOF(self)
```

```

def dataReceived(self, data):
    print data

def closed(self):
    reactor.stop( )

class ClientCommandFactory(protocol.ClientFactory):
    def __init__(self, username, password, command):
        self.username = username
        self.password = password
        self.command = command

    def buildProtocol(self, addr):
        protocol = ClientCommandTransport(
            self.username, self.password, self.command)
        return protocol

if __name__ == "__main__":
    import sys, getpass
    server = sys.argv[1]
    command = sys.argv[2]
    username = raw_input("Username: ")
    password = getpass.getpass("Password: ")
    factory = ClientCommandFactory(username, password, command)
    reactor.connectTCP(server, 22, factory)
    reactor.run( )

```

Run *sshclient.py* with two arguments: a hostname and a command. It will ask for your username and password, log into the server, execute the command, and print the output. For example, you could run the *who* command to get a list of who's currently logged in to the server:

```

$ python sshclient.py myserver.example.com who
Username: abe

```

Password: *password*

```
root    pts/0      Jun 11 21:35 (192.168.0.13)
phil    pts/2      Jun 22 13:58 (192.168.0.1)
phil    pts/3      Jun 22 13:58 (192.168.0.1)
```

10.4.2. How Does That Work?

The `ClientCommandTransport` in [Example 10-4](#) handles the initial connection to the SSH server. Its `verifyHostKey` method checks to make sure the server's public key matches your expectations. Typically, you'd remember each server the first time you connected, and then check on subsequent connections to make sure that another server wasn't maliciously trying to pass itself off as the server you expected. Here, it just returns a `True` value without bothering to check the key. The `connectionSecure` method is called as soon as the initial encrypted connection has been established. This is the appropriate time to send your login credentials, by passing a `userauth.SSHUserAuthClient` to `self.requestService`, along with a `connection.SSHConnection` object that should manage the connection after authentication succeeds.

The `PasswordAuth` inherits from `userauth.SSHUserAuthClient`. It has to implement only a single method, `getPassword`, which returns the password it will use to log in. If you wanted to use public key authentication, you'd implement the methods `getPublicKey` and `getPrivateKey` instead, returning the appropriate key as a string in each case.

The `ClientConnection` class in [Example 10-4](#) will have its `serviceStarted` method called as soon as the client has successfully logged in. It calls `self.openChannel` with a `CommandChannel` object, which is a subclass of `channel.SSHChannel`. This object is used to work with an authenticated channel to the SSH server. Its `channelOpen` method is called when the channel is ready. At this point, you can call `self.conn.sendRequest` to send a command to the server. You have to encode data sent over SSH as a specially formatted network string; to get a string in this format, pass it to the `twisted.conch.common.NS` function. Set the keyword argument `wantReply` to `True` if you're interested in getting a response from the command; this setting will cause `sendRequest` to return a `Deferred` that will be called back when the command is completed. (If you don't set `wantReply` to `true`, `sendRequest` will return `None`.) As data is received from the server, it will be passed to `dataReceived`. Once you're done using the channel, close it by calling `self.conn.sendEOF`. The `closed` method will be called to let you know when the channel has been successfully closed.

[< Day Day Up >](#)

Chapter 11. Services, Processes, and Logging

Once you've built an application that behaves the way you want, the next step is to think about how you're going to deploy it. How will you start and stop the process? Under which user account should it run? How will you keep track of what's going on? Twisted provides a number of tools that you can use to manage how your application behaves in these areas. You can run your application in a background process, and limit its permissions by having it run as a specific user. You can run multiple services in the same process. And you can use logging to record errors and track your program's usage.

11.1. Running a Twisted Application as a Daemon

Just as servers are different from regular applications, server processes are different from regular processes. A server needs to be available all the time, to all users, so it can't be tied to one user's session. Server processes run in the background and are usually started and stopped automatically by the operating system. In Unix and Unix-like operating systems, such long-running background processes are traditionally known as *daemons*.

Twisted comes with a program called *twistd* that you can use to run your application as a background process. *twistd* can also help your program to do other things you'd expect from a well-behaved server: write log messages to the system log, run in a *chrooted* environment where it has limited directory access, and run with the permissions of an unprivileged user.



For more information on using *twistd* to limit your program's file access and permissions, see [Example 11-3](#).

11.1.1. How Do I Do That?

First, encapsulate each logical service in your application in a class implementing `twisted.application.service.IService`. [Example 11-1](#) shows how easy this is to do for a typical server based on a Protocol and Factory.

Example 11-1. reverse.py

```
from twisted.application import service, internet
from twisted.internet import protocol, reactor
from twisted.protocols import basic

def reverse(string):
    return string[::-1]

class ReverserProtocol(basic.LineReceiver):
    def lineReceived(self, line):
        if hasattr(self, 'handle_' + line):
            getattr(self, 'handle_' + line)( )
```

```

    else:
        self.sendLine(reverse(line))

def handle_quit(self):
    self.transport.loseConnection()

class ReverserFactory(protocol.ServerFactory):
    protocol = ReverserProtocol

class ReverserService(internet.TCPServer):
    def __init__(self):
        internet.TCPServer.__init__(self, 2323, ReverserFactory())

```

Next, write a Python script that defines a variable named `application` pointing to an object created by calling `twisted.application.service.Application`. Add your service to the application, and run the script using the command `twistd -y yourappname`. [Example 11-2](#) does this for the service from [Example 11-1](#).

Example 11-2. `reverse_app.py`

```

from twisted.application import service
import reverse

application = service.Application("Reverser")
reverserService = reverse.ReverserService()
reverserService.setServiceParent(application)

```

Run this application using `twistd`. It will start the process in the background, and immediately return:

```

$ twistd -y reverse_app.py
$

```

At this point, the server is running as a background process. It runs a tiny protocol that sends back a reversed copy of every line it receives, unless that line is **quit**, in which case it closes the connection. You can connect to the server on port 2323 using Telnet:

```
$ telnet localhost 2323

Trying 127.0.0.1...

Connected to sparky.

Escape character is '^]'.

hello world!

!dlrow olleh

quit

Connection closed by foreign host.
```

twistd creates in the current directory a file called *twistd.pid*, which contains the process ID of the daemon process. To stop the application, kill this process. You can do this easily on Unix-like operating systems by running the command **kill 'cat twistd.pid'**. *twistd* also creates a logfile called *twistd.log*, which you can use to monitor the activity of your server while it's running.

11.1.2. How Does That Work?

The `twisted.application.service` module provides the interface `IService`, which represents part of an application that provides a specific service. `IService` objects have `startService` and `stopService` methods that can be used to control the service. Services can be grouped together into a hierarchy, so that each service manages a set of child services. An application is made up of one or more services.

[Example 11-1](#) defines a protocol and factory, `ReverserProtocol` and `ReverserFactory`. Instead of starting the factory directly by calling `reactor.listenTCP`, it creates a subclass of `twisted.application.internet.TCPServer`. The `TCPServer` class lets you define a service that sets up a factory to listen on a port. Initialize a `TCPServer` with the same arguments you'd pass to `reactor.connectTCP`. The `TCPServer` won't start the factory immediately, however; it will wait until its `startService` method is called. `TCPServer` also provides a `stopService` method that stops listening on the port.

[Example 11-2](#) takes the `ReverserService` from [Example 11-1](#) and makes it into an application suitable for running with *twistd*. To create an application object, call `twisted.application.service.Application` with a string representing the name of your application. `service.Application` is actually not a class, but a function that creates a `twisted.python.components.Componentized` object. `Componentized` objects are multifaceted: internally, they contain multiple objects, which they can expose in order to implement different interfaces. The application object returned by `service.Application` is three objects in one. First, it's a `twisted.application.service.MultiService` object, which is a service that contains other services. When this service is started or stopped, all its child services will be started or stopped along with it.

Second, the application is a `twisted.application.service.Process` object, meaning that it will be the top-level object in a process whose permissions can be managed by the operating system. And third, it's a `twisted.persisted.sob.Persistent` object, which means that its state can be preserved between sessions by writing it to disk.

Attach a service to an application by calling `service.setServiceParent(application)`. This step registers the service as a child of the application, so it will be started and stopped automatically when the application is run with *twistd*.

The `-y` flag tells *twistd* that you're passing it a Python file with your application in the `application` variable. *twistd* is capable of loading applications from other formats, including Python pickle files and XML files, but using `-y` and a Python script is the most straightforward. You can think of the script you pass to *twistd* as being the configuration file for your application. It's best to define your application's services elsewhere, and then use a minimal script to tie it together into an application object for *twistd*.

An interesting thing that *twistd* does by default is save a pickled version of your application object at shutdown in a file called *YourAppName-shutdown.tap*. Although it's in a different format than your Python script, this file can also be used to run your application with *twistd*. After running [Example 11-2](#), you should have a file named *Reverser-shutdown.tap* in the directory where you started *twistd*. You could run your application from this file by passing it to *twistd* with the `-f` flag:

```
$ twistd -f Reverser-shutdown.tap
```

The potentially useful thing about this feature is that the *.tap* file contains the state of the application object just before shutdown, including any configuration changes made while the program was running. This information could be useful if you want your program to include its own configuration interface, perhaps allowing the administrator to change the port your server will listen on. In practice, however, this knowledge is rarely needed. If you're not planning to use this feature, and don't want *.tap* files cluttering up your filesystem, disable it by passing the `-o` flag to *twistd*.

Another useful *twistd* flag is `-n`, which tells the application not to run as a background process. This option is useful for testing purposes. It will run in the foreground and print log messages to stdout.

[< Day Day Up >](#)

11.2. Setting Limits on an Application's Permissions

Most operating systems reserve ports below 1024 for system-wide servers. To enforce this reservation, only users with root permissions are allowed to run programs that bind to these ports. But running a server with root permissions tends to greatly magnify security issues. Security breaches happen when a malicious user tricks your application into doing something you didn't intend. This problem is never desirable, but the possibility for damage is especially high if your application has access to every file on the computer.

To limit the potential for damage, a well-behaved Unix server will run under a privileged account for just long enough to listen on the necessary ports, and then switch its identity to that of another user with minimal permissions. *twistd* makes it easy to use this technique for running your application.



This example is specific to Unix-like operating systems, such as Linux and Mac OS X. Twisted doesn't provide a way to switch user IDs on Windows.

11.2.1. How Do I Do That?

Pass `uid` and `gid` keyword arguments when you call `twisted.application.service.Application`. Once your application has started listening on the ports it needs, *twistd* will change your application's user and group to those you specified. [Example 11-3](#) creates a server that runs on the reserved Telnet port, 23, and reads the contents of files from disk. By running it with a set user ID and group ID, it's limited to reading files that are available to its user and group.

Example 11-3. `catserver.py`

```
from twisted.application import service, internet
from twisted.internet import protocol, reactor
from twisted.protocols import basic
import os

class FileDumpProtocol(basic.LineReceiver):
    def lineReceived(self, line):
        if hasattr(self, 'handle_' + line):
            getattr(self, 'handle_' + line)( )
        else:
```

```

        self.listDir(line)

def listDir(self, filename):
    try:
        f = open(filename)
        for line in f:
            self.transport.write(line)
    except Exception, e:
        self.sendLine("ERROR: %s" % e)

def handle_quit(self):
    self.transport.loseConnection( )

class FileDumpFactory(protocol.ServerFactory):
    protocol = FileDumpProtocol

UID = 1000
GID = 1000

fileDumpService = internet.TCPServer(23, FileDumpFactory( ))
application = service.Application('Cat Server', uid=UID, gid=GID)
fileDumpService.setServiceParent(application)

```

Modify the UID and GID values in [Example 11-3](#) to match a valid user and group on your system. Start *catserver.py* as root using *twistd* with the `-n` option to keep it in the foreground. It will start a server on port 23. (If you're already running a Telnet server on port 23, modify [Example 11-3](#) to use a different port.) You'll see a log message informing you that *twistd* has switched to your user and group:

```

$ twistd -noy catserver.py

2005/06/25 17:32 EDT [-] Log opened.

2005/06/25 17:32 EDT [-] twistd 2.0.0 (/usr/bin/python2.3 2.3.5) starting up

2005/06/25 17:32 EDT [-] reactor class: twisted.internet.selectreactor.SelectReactor

2005/06/25 17:32 EDT [-] Loading catserver.py...

2005/06/25 17:32 EDT [-] Loaded.

```

```

2005/06/25 17:32 EDT [-] _ _builtin_ _FileDumpFactory starting on 2323
2005/06/25 17:32 EDT [-] Starting factory <_ _builtin_ _FileDumpFactory instance at
0xb7b2cd2c>
2005/06/25 17:32 EDT [-] set uid/gid 1000/1000

```

Telnet to localhost and enter some filenames. You will be able to access only files that your application's user has the right to read:

```

$ telnet localhost
Trying 127.0.0.1...
Connected to sparky.
Escape character is '^]'.
/etc/passwd
root:x:0:0:root:/root:/bin/bash
daemon:x:1:1:daemon:/usr/sbin:/bin/sh
bin:x:2:2:bin:/bin:/bin/sh
sys:x:3:3:sys:/dev:/bin/sh
...
sshd:x:110:65534:./var/run/sshd:/bin/false
bind:x:112:117:./var/cache/bind:/bin/false
/etc/shadow
ERROR: [Errno 13] Permission denied: '/etc/shadow'
quit
Connection closed by foreign host.

```

11.2.2. How Does That Work?

[Example 11-3](#) calls `twisted.application.service.Application` with `uid` and `gid` keyword arguments. `twisted` uses these values to set the process owner of the application after it has opened the ports. Behind the scenes, this process works by using the `privilegedStartService` method of `IService`. If a service provides the method `privilegedStartService`, it will be called at startup before the application switches users. After it switches to the unprivileged user, the application calls the `Service`'s

regular `startService` method. In the `twisted.application.internet.TCPServer` class, the code for listening on a port is in the `privilegedStartService` method, so it's able to bind to the port as root before the process switches to an unprivileged user.

Typically, you wouldn't design a protocol like `FileDumpProtocol` in [Example 11-3](#), which lets any anonymous user dump the contents of any file on your system. But it's possible that you'd accidentally create a security hole in your application that would let a malicious user trick it into reading arbitrary files. By running it as an unprivileged user, you prevent such a security hole from revealing sensitive files on your system, such as `/etc/shadow`, which contains user/password hashes.



[Example 11-3](#) defines the application classes and builds the `application` object in the same file. This is OK for short examples like this one, but the best practice is to set up your `application` object in a separate, minimal file.

11.2.3. What About...

...running the application in a chroot environment? An alternative way to limit the potential damage of a security flaw in your application is to run it in a chroot "jail," where the operating system makes it impossible for the process to see or access any files outside of one specific directory. `twistd` has built-in support for this: just run it with the flag `-chroot directory`.

[< Day Day Up >](#)

11.3. Managing Multiple Services

One of the most powerful features of Twisted is its ability to run multiple services in a single process. You can write an application that shares objects and data with many different protocols at the same time. You can also manage the different services in an application at runtime, starting and stopping them individually without having to restart your application.

11.3.1. How Do I Do That?

Add more than one service to an application object and run the application using *twistd*. You can iterate through the current services in your application by wrapping the application object in the `service.IServiceCollection` interface. Call `startService` and `stopService` to start or stop one of the services. [Example 11-4](#) creates an application that offers both web and Telnet interfaces to the same data, and a web administration interface that lets you selectively start and stop services.

Example 11-4. multiservice.py

```
from twisted.application import service, internet
from twisted.internet import protocol, reactor, defer
from twisted.protocols import basic
from twisted.web import resource, server as webserver

class Reverser:
    def __init__(self):
        self.history = []

    def reverse(self, string):
        self.history.append(string)
        reversed = string[::-1]
        return reversed

class ReverserLineProtocol(basic.LineReceiver):
    def lineReceived(self, line):
        if hasattr(self, 'handle_' + line):
            getattr(self, 'handle_' + line)( )
        else:
```

```

        self.sendLine(self.factory.reverser.reverse(line))

def handle_quit(self):
    self.transport.loseConnection()

class ReverserLineFactory(protocol.ServerFactory):
    protocol = ReverserLineProtocol

    def __init__(self, reverser):
        self.reverser = reverser

class ReverserPage(resource.Resource):
    def __init__(self, reverser):
        self.reverser = reverser

    def render(self, request):
        if request.args.has_key("string"):
            string = request.args["string"][0]
            reversed = self.reverser.reverse(string)
        else:
            reversed = ""

        return """
<html><body><form>
<input type='text' name='string' value='%s' />
<input type='submit' value='Go' />
<h2>Previous Strings</h2>
<ul>
%s
</ul>
</form></body></html>
""" % (reversed,
        "\n".join(["<li>%s</li>" % s for s in self.reverser.history]))

```

```

class ServiceAdminResource(resource.Resource):

    def __init__(self, app):
        self.app = app

    def render_GET(self, request):
        request.write("""
        <html><body>
        <h1>Current Services</h1>
        <form method='post'>
        <ul>
        """)
        for srv in service.IServiceCollection(self.app):
            if srv.running:
                checked = "checked='checked'"
            else:
                checked = ""
            request.write("""
            <input type='checkbox' %s name='service' value='%s'>%s<br />
            """ % (checked, srv.name, srv.name))
        request.write("""
        <input type='submit' value='Go' />
        </form>
        </body></html>
        """)
        return ''

    def render_POST(self, request):
        actions = []
        serviceList = request.args.get('service', [])
        for srv in service.IServiceCollection(self.app):
            if srv.running and not srv.name in serviceList:
                stopping = defer.maybeDeferred(srv.stopService)
                actions.append(stopping)

```

```

        elif not srv.running and srv.name in serviceList:

            # wouldn't work if this program were using reserved ports

            # and running under an unprivileged user id

            starting = defer.maybeDeferred(srv.startService)

            actions.append(starting)

        defer.DeferredList(actions).addCallback(

            self._finishedActions, request)

        return webserver.NOT_DONE_YET

    def _finishedActions(self, results, request):

        request.redirect('/')

        request.finish( )

application = service.Application("Reverser")

reverser = Reverser( )

lineService = internet.TCPServer(2323, ReverserLineFactory(reverser))

lineService.setName("Telnet")

lineService.setServiceParent(application)

webRoot = resource.Resource( )

webRoot.putChild('', ReverserPage(reverser))

webService = internet.TCPServer(8000, webserver.Site(webRoot))

webService.setName("Web")

webService.setServiceParent(application)

webAdminRoot = resource.Resource( )

webAdminRoot.putChild('', ServiceAdminPage(application))

webAdminService = internet.TCPServer(8001, webserver.Site(webAdminRoot))

webAdminService.setName("WebAdmin")

webAdminService.setServiceParent(application)

```

Run *multiservice.py* using *twistd*. It will start a server that offers two different interfaces to a *Reverser* object, which reverses strings. You can connect to the server using telnet on port 2323:

```
$ telnet localhost 2323

Trying 127.0.0.1...
Connected to sparky.
Escape character is '^]'.

this is a test

tset a si siht

another test


tset rehtona

quit

Connection closed by foreign host.
```

You can also access the server using a web browser on port 8000. [Figure 11-1](#) shows how the history data is shared between the Telnet service and the web service.

Figure 11-1. The multiservice.py web interface



[Example 11-4](#) also runs a second web server on port 8001. This server provides the interface shown in [Figure 11-2](#) for starting and stopping services.

Now, if you try to telnet to port 2323, you find that the service is no longer available:

```
$ telnet localhost 2323

Trying 127.0.0.1...

telnet: Unable to connect to remote host: Connection refused
```

Figure 11-2. Stopping the Telnet service through the web administration interface



11.3.2. How Does That Work?

Example 11-4 creates three Resource objects: `lineService`, `webService`, and `webAdminService`. It uses `setServiceParent` to register each of them as a child of application. The `ReverserLineFactory` used by `lineService` is initialized with a `Reverser` object; this same object is passed to the `ReverserPage` that `webService` uses to handle web requests. Since both services are using the same object, they're able to transparently share data.

The `webAdminService` in **Example 11-4** uses a `ServiceAdminPage` object to provide a web interface for starting and stopping resources. `ServiceAdminPage` is initialized with the application object so that it can access all available services. As a `twisted.python.components.Componentized` object, there's not much you can do with the application directly. Instead, you expose one of its internal objects by wrapping it in the interface you want to use. To loop through all the services, the `ServiceAdminPage` class uses the `service.IServiceCollection` interface, which returns an iterable object. `ServiceAdminPage` renders a form with an input checkbox for each service. When you submit this form, `ServiceAdminPage` loops through the services again and compares their current state with the checkbox value. If the service is running, but the box wasn't checked, it stops the service; if the service wasn't running, but the box was checked, it starts the service.



The web administration service in **Example 11-4** even lets you stop it. That's probably not something you want to allow in a real application!

11.4. Logging Events and Errors

Server logfiles provide an important way to keep track of what's going on in your application. Logfiles let you see how many users your application has, how frequently it's being used, and what it's being used for. Logfiles also collect errors and debugging information, making it much easier to track down problems.

As [Example 11-2](#) demonstrated, *twistd* creates a logfile named *twistd.log* automatically. By default, this logfile will capture several useful kinds of information. First, it will store anything that your application normally writes to stdout, including `print` statements. Second, it will record tracebacks for any uncaught exceptions. Third, it will capture log messages generated by twisted modules; many of the modules in Twisted automatically log events that you're likely to be interested in.

It's nice that *twistd* does all this for you, but sometimes you need more control. For example, you might have code in your application that catches exceptions and reports them to the user. *twistd* won't log these exceptions for you, but you might want to capture the tracebacks for debugging. It can also be a chore to wade through a giant logfile containing a mix of usage reporting, debug messages, and errors. This is especially true for error messages: if everything is in the same file, the only way to tell whether your application is generating errors is to search through the file. It's much better to divert error messages to their own log: that way you can just glance at the file to see whether it has any contents and you'll know immediately whether your application is generating errors.

Twisted included a framework for logging that you can use to generate your own log messages. Using the Twisted logging framework also gives you more control over how log events and logfiles are managed, so you can do things like keep separate logfiles for different types of events.

11.4.1. How Do I Do That?

Use the `twisted.python.log` module to generate log messages. Use the `twisted.python.logfile` module to write logfiles to disk and rotate logfiles. [Example 11-5](#) demonstrates a `Protocol` that logs user activity and exceptions, and shows how to log errors to a separate file.

Example 11-5. `logger.py`

```
from twisted.internet import protocol

from twisted.protocols import basic

from twisted.application import service, internet

from twisted.python import log, logfile

import time

class ChatProtocol(basic.LineReceiver):

    def lineReceived(self, line):
```

```

log.msg("Got command:", line)

parts = line.split( )

cmd = parts[0]

args = parts[1:]

if hasattr(self, 'do_'+cmd):
    try:
        getattr(self, 'do_'+cmd)(*args)
    except Exception, e:
        log.err(e)
        self.sendLine("Error: %s" % e)
else:
    log.msg("User sent invalid command", cmd, args)
    self.sendLine("Invalid command '%s'" % cmd)

```

```

def do_time(self):
    self.sendLine(str(time.strftime("%x %X")))

```

```

def do_echo(self, *strings):
    self.sendLine(" ".join(strings))

```

```

def do_quit(self):
    self.transportloseConnection( )

```

```

class ErrorLog(log.FileLogObserver):
    def emit(self, logEntryDict):
        if not logEntryDict.get('isError'): return
        log.FileLogObserver.emit(self, logEntryDict)

```

```

class ErrLogService(service.Service):
    def __init__(self, logName, logDir):
        self.logName = logName

```

```

self.logDir = logDir

self.maxLogSize = 1000000

def startService(self):
    # logfile is a file-like object that supports rotation
    self.logFile = logfile.LogFile(
        self.logName, self.logDir, rotateLength=self.maxLogSize)
    self.logFile.rotate( ) # force rotation each time restarted
    self.errlog = ErrorLog(self.logFile)
    self.errlog.start( )

def stopService(self):
    self.errlog.stop( )
    self.logFile.close( )
    del(self.logFile)

application = service.Application("LogDemo")

# quick and dirty way to create a service from a protocol
chatFactory = protocol.ServerFactory( )
chatFactory.protocol = ChatProtocol
chatService = internet.TCPServer(2323, chatFactory)
chatService.setServiceParent(application)

ERR_LOG_DIR = "." # use an absolute path for real apps
ERR_LOG_NAME = "chaterrors.log"

ErrLogService(ERR_LOG_NAME, ERR_LOG_DIR).setServiceParent(application)

```

Run the `logger.py` application in [Example 11-5](#) using `twistd`:

```

$ twistd -noy logger.py
2005/06/23 15:27 PDT [-] Log opened.

```

```

2005/06/23 15:27 PDT [-] twisted 2.0.0 (/usr/bin/python2.3 2.3.5) starting up
2005/06/23 15:27 PDT [-] reactor class: twisted.internet.selectreactor.SelectReactor
2005/06/23 15:27 PDT [-] Loading logger.py...
2005/06/23 15:27 PDT [-] Loaded.
2005/06/23 15:27 PDT [-] twisted.internet.protocol.ServerFactory starting on 2323
2005/06/23 15:27 PDT [-] Starting factory <twisted.internet.protocol.ServerFactory
instance at 0xb7921ccc>

```

It will start a server on port 2323. You can connect to this server using Telnet and issue the commands `time`, `echo`, and `quit`. If you attempt to call a command with the wrong syntax, the server will raise an exception, and you'll get an error message:

```

$ telnet localhost 2323

Trying 127.0.0.1...
Connected to sparky.
Escape character is '^]'.

time

06/23/05 15:22:41

echo hello

hello

time time

Error: do_time( ) takes exactly 1 argument (2 given)

quit

Connection closed by foreign host.

```

Meanwhile, the server will be printing its log to *stdout* for you to see:

```

2005/06/23 15:27 PDT [ChatProtocol,0,127.0.0.1] Got command: time
2005/06/23 15:27 PDT [ChatProtocol,0,127.0.0.1] Got command: echo hello
2005/06/23 15:27 PDT [ChatProtocol,0,127.0.0.1] Got command: time time
2005/06/23 15:27 PDT [ChatProtocol,0,127.0.0.1] Traceback (most recent call last):
      Failure: exceptions.TypeError: do_time( ) takes exactly 1 argument (2 given)

```

```
2005/06/23 15:27 PDT [ChatProtocol,0,127.0.0.1] Got command: quit
```

Shut down the server, and there should be a file in the same directory named *chaterrors.log*. This file will contain only the exceptions that were logged:

```
$ cat chaterrors.log
```

```
2005/06/23 15:25 PDT [ChatProtocol,0,127.0.0.1] Traceback (most recent call last):
      Failure: exceptions.TypeError: do_time( ) takes exactly 1 argument (2 given)
```

11.4.2. How Does That Work?


The `ChatProtocol` class in [Example 11-5](#) uses the functions `twisted.python.log.msg` and `twisted.python.log.err`. These are used to write log messages to the default log. `log.msg` takes a series of strings and writes them on a single line; `log.err` takes an `Exception` or `twisted.python.Failure` object and writes the traceback.



Behind the scenes, the `twisted.python.log` module creates exactly one global `LogPublisher` object. The `LogPublisher` is in charge of routing log messages to `LogObserver` objects, which then write the messages to a file or do something else useful with them.

The `lineReceived` method of `chatProtocol` tries to perform a method call based on the command sent from the client. If this method call raises an exception, it sends an error message to the client. But it also calls `log.err` with the exception. This step creates a record in the logfile containing the exception and a full traceback.

The `ErrorLog` class in [Example 11-5](#) is a subclass of `log.FileLogObserver`. `FileLogObserver` is an object that observes log events and writes them to a file. The `emit` method is called with a dictionary containing information about the log message. If the log message is an error, it will have a true value for the key `isError`. `ErrorLog` uses the `isError` key to filter out log messages that aren't errors.



You can pass extra information to log observers by adding keyword arguments when you call `log.msg`. For example, you could say:

```
log.msg('test', debugLevel=1)
```

which could cause the dictionary passed to `LogObserver.emit` to have a key named `'debugLevel'` with a value of 1.

The `ErrLogService` class implements a service that uses the `ErrorLog` class to get any errors being logged and write them to a separate file. Instead of just passing an open file handle to `ErrorLog`, `ErrorLogService` passes a `twisted.python.logfile.LogFile` object. A `LogFile` object represents a rotating logfile. When the logfile reaches a certain size, or when you call `LogFile.rotate`, `LogFile` moves the current logfile to a file named *filename.1*, and starts using a fresh file. If *filename.1* exists, the current *filename.1* will be renamed *filename.2*, and so on. You initialize a `LogFile` object with two arguments: the directory where the logfiles should be stored and the name of the logfile. You can also pass an optional `rotateLength` keyword argument to set the size at which the logfile should be rotated.

[< Day Day Up >](#)

Colophon

Our look is the result of reader comments, our own experimentation, and feedback from distribution channels. Distinctive covers complement our distinctive approach to technical topics, breathing personality and life into potentially dry subjects.

The image on the cover of *Twisted Network Programming Essentials* shows a ball of snakes. When the ground begins to thaw in spring, things heat up for some species of snakes. Males emerge from their hibernation dens cold, hungry, and randy! An estimated 50,000 male snakes can fill a location such as a limestone quarry, waiting patiently for nearby females to emerge. When they do, the mating frenzy begins, and it can last up to three weeks.

As many as 100 to 1,000 males will compete to mate with a single female, sometimes surrounding her before she can fully emerge from her den. The males wrap around the female, becoming a living ball that can grow to be two feet high. The constant writhing of the snakes can even propel the ball over rocks and tree roots.

In some cases, the size of the snake ball will crush the female to death. However, this does not always deter the males, who may continue to mate with her.

A female will normally mate with only one male in the ball; once a male has successfully copulated with her, he releases a pheromone that temporarily makes all other males in the ball impotent. When the female selects her partner, the ball unravels and the unsuccessful males go in search of another female.

Since it is difficult for snakes to determine the gender of their potential partner, males detect the female by using their flicking tongues to sense the female's pheromones, which stimulate the males to mate. The male rubs his chin against the grain of the female's scales to squeeze out her pheromones. It is believed that the male can also determine the position of the female by detecting the direction of her pheromones and then aligning himself with her body accordingly.

One interesting phenomenon that is still not completely understood is that of the "she-male" snake—a male that gives off female pheromones when it emerges from the ground. One theory is that weaker male snakes emerging from the cold ground may do this so that other males will surround them in a ball to warm them up and protect them from predators. Studies have shown that "she-males" in this situation will return to being normal males after about three hours. Another theory is that "she-males" use their pheromones to confuse other males, who will try to mate with the "she-male" rather than vying for the true female.

Marlowe Shaeffer was the production editor for *Twisted Network Programming Essentials*. Nancy Kotary was the copyeditor, and Sada Preisch was the proofreader. Marlowe Shaeffer and Claire Cloutier provided quality control. Ellen Troutman Zaig wrote the index.

Karen Montgomery designed the cover of this book, based on a series design by Edie Freedman. The cover image is a 19th-century engraving from the Dover Pictorial Archive. Karen Montgomery produced the cover layout with Adobe InDesign CS using Adobe's ITC Garamond font.

David Futato designed the interior layout. This book was converted by Keith Fahlgren to FrameMaker 5.5.6. The text font is Linotype Birka; the heading font is Adobe Myriad Condensed; and the code font is LucasFont's TheSans Mono Condensed. The illustrations that appear in the book were produced by Robert Romano, Jessamyn Read, and Lesley Borash using Macromedia FreeHand MX and Adobe Photoshop CS. The tip and warning icons were drawn by Christopher Bing. This colophon was written by Jansen Fernald.

< Day Day Up >

Index

[SYMBOL] [A] [B] [C] [D] [E] [F] [G] [H] [I] [K] [L] [M] [N] [O] [P] [Q] [R] [S] [T] [U] [V] [W] [X] [Z]

< Day Day Up >

< Day Day Up >

Index

[SYMBOL] [A] [B] [C] [D] [E] [F] [G] [H] [I] [K] [L] [M] [N] [O] [P] [Q] [R] [S] [T] [U] [V] [W] [X] [Z]

.tap file
/ (slash), trailing slashes in URIs
_checkedPassword method
_gotMessageLines function
_gotMXRecord function
_gotQueryResults function
_refreshAllFeedsAndCall function
_refreshFeedAndCall function

< Day Day Up >

Index

[SYMBOL] [A] [B] [C] [D] [E] [F] [G] [H] [I] [K] [L] [M] [N] [O] [P] [Q] [R] [S] [T] [U] [V] [W] [X] [Z]

- addCallback function 2nd
- addErrback function 2nd
- addListener method (IMailbox)
- anonymous functions
- answers to questions from Twisted community
- asynchronous results
- authentication
 - against a database table
 - HTTP Authorization header 2nd
 - in Twisted server
 - Perspective Broker
 - POP3 server
 - SSH server
 - username and password
 - using public keys
 - twisted.cred classes
 - users with different capabilities
 - web pages requiring
- avatar IDs 2nd
 - requesting
 - requesting with database query
- Avatar objects
 - IMAP server
 - multiple, for users with different capabilities
 - Perspective Broker
 - requesting
 - separation from credential verification
 - SSH server
 - twisted.conch.avatar.ConchUser 2nd
- avatarInterfaces dictionary

< Day Day Up >

Index

[SYMBOL] [A] [B] [C] [D] [E] [F] [G] [H] [I] [K] [L] [M] [N] [O] [P] [Q] [R] [S] [T] [U] [V] [W] [X] [Z]

background processes (daemons), running Twisted applications as
BasicClientFactory class
Binary object (xmlrpc)
BSD variants
 Twisted, PyOpenSSL, and PyCrypto, prepackaged
buildMessage function

< Day Day Up >

Index

[SYMBOL] [A] [B] [C] [D] [E] [F] [G] [H] [I] [K] [L] [M] [N] [O] [P] [Q] [R] [S] [T] [U] [V] [W] [X] [Z]

- CallbackAndDisconnectProtocol.connectionMade method
- callRemote method (soap.Proxy) 2nd
- callRemote method (xmlrpc.Proxy) 2nd
- chainDeferred method 2nd
- channel.SSHChannel class 2nd
- checkHTTPError function
- checkPassword method
 - IUsernameHashedPassword
 - IUsernamePassword 2nd
- checkStatus function
- child resources
 - getChild method (Resource)
- chroot environment, running an application in
- client connections
 - acceptance on network server
 - ClientFactory and Protocol classes
 - sending and receiving data
- client.downloadPage function
- client.getPage function 2nd 3rd 4th
- client.HTTPClientFactory class
- client.HTTPDownloader class
- ClientCommandTransport class
- clientConnectionFailed method
- clientConnectionLost method
- ClientContextFactory class
- ClientFactory class 2nd 3rd
- clients
 - HTTP proxy
 - IMAP 2nd
 - server notification of messages
 - Mozilla Thunderbird email client
 - NNTP
 - Perspective Broker
 - supporting authentication
 - SOAP
 - SSH
 - XML-RPC
- command history
- command-line shells
- community resources
- Componentized objects 2nd
- ConchFactory class
- ConchUser class 2nd
- conditional HTTP GET requests
- connection.SSHConnection class 2nd

- connectionLost function (IMessage)
- ConnectionPool object 2nd
- connectionSecure method
- ConnectionTestFactory class
 - clientConnectionFailed
- connectSSL function
- consumeErrors argument (DeferredList)
- Content-Length header 2nd
- Content-Type header
- create method (IAccount)
- credentials
- credentials checkers
 - combining with realm in Portal
 - IMAP server
 - InMemoryPasswordDatabaseDontUse class
 - PublicKeyCredentialsChecker
 - SSH server 2nd
- credentials.IUsernameHashedPassword
- credentials.IUsernamePassword
- Crypto.PublicKey.RSA module
- Crypto.PublicKey.RSA.RSAobj class
- Ctrl-C, exiting event loop

< Day Day Up >

Index

[SYMBOL] [A] [B] [C] [D] [E] [F] [G] [H] [I] [K] [L] [M] [N] [O] [P] [Q] [R] [S] [T] [U] [V] [W] [X] [Z]

- daemon, running Twisted application as
- data types, XML-RPC
- database connections, pooling
- database.INewsStorage interface 2nd
- database.NewsShelf class 2nd
- DataForwardingProtocol class 2nd
- DateTime object (xmlrpc)
- DB-API compatible Python modules for databases
- DebuggingNTTPProtocol class
- Deferred class
 - callback method
 - chainDeferred method
 - errback method
- Deferred objects
 - chaining
 - downloading a web page
 - handling errors
 - managing group of
 - returning from callback handler
 - web page written to file while downloading
- DeferredList class
 - consumeErrors argument
- DELETE command (POP3)
- delete method (POP3Client)
- DELETE requests, HTTP
- dirdbm.Shelf class
- DNS (Domain Name System), looking up SMTP server
- doc/examples directory
- documentation
 - API, viewing without a browser
 - using Twisted documentation
- downloadComplete function
- downloadError function
- downloading
 - messages from IMAP mailbox
 - messages from POP3 server
 - monitoring progress
 - Usenet articles
 - web pages
- downloadPage function
- downloadToTempFile function
- downloadWithProgress function

Index

[\[SYMBOL\]](#) [\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[X\]](#) [\[Z\]](#)

- [echo server \(example\)](#)
- [email](#)
 - [headers](#)
- [email module \(Python\)](#)
 - [creating email message](#)
- [email.Message module](#)
- [email.Message.Message class 2nd](#)
- [email.message_from_string function](#)
- [encodeForm function](#)
- [entropy.get_bytes function](#)
- [eomReceived method \(IMessage\) 2nd](#)
- [errback handlers](#)
 - [checkHTTPError function](#)
- [Error object](#)
- [errors, logging](#)
- [ETag header](#)
- [event handlers](#)
- [event loop](#)
 - [implementation by reactor](#)
- [event-driven framework](#)
- [events, logging](#)
- [examples directory](#)

Index

[[SYMBOL](#)] [[A](#)] [[B](#)] [[C](#)] [[D](#)] [[E](#)] [[F](#)] [[G](#)] [[H](#)] [[I](#)] [[K](#)] [[L](#)] [[M](#)] [[N](#)] [[O](#)] [[P](#)] [[Q](#)] [[R](#)] [[S](#)] [[T](#)] [[U](#)] [[V](#)] [[W](#)] [[X](#)] [[Z](#)]

- Failure objects
- [fetchArticle](#) method
- [fetchGroup](#) method (NNTPClient)
- [fetchGroups](#) method (NNTPClient)
- [fetchNextArticle](#) method
- Fielding, Roy Thomas
- File class 2nd
- flags, IMAP messages
- freenode network, IRC channels
- function calls, XML-RPC
- FunctionHandledRequest class
- functions
 - event handler
 - returning Deferred object from 2nd
 - XML-RPC, calling

Index

[SYMBOL] [A] [B] [C] [D] [E] [F] [G] [H] [I] [K] [L] [M] [N] [O] [P] [Q] [R] [S] [T] [U] [V] [W] [X] [Z]

- generate function (RSA)
- GET requests (HTTP)
 - conditional
- getAllGroupsFailed method 2nd
- getChild method (Resource class)
- getManholeFactory function
- getMX method (MXCalculator)
- getPage function 2nd 3rd
- getPrivateKey function
- getPrivateKeyString function
- getPublicKeyString function 2nd
- getSMTPServer function
- gid (applications) 2nd
- globals function
- Google searches, SMTP interface
- gotAllGroups method 2nd
- gotHeaders method

Index

[SYMBOL] [A] [B] [C] [D] [E] [F] [G] [H] [I] [K] [L] [M] [N] [O] [P] [Q] [R] [S] [T] [U] [V] [W] [X] [Z]

- handlePost function
- headers
 - email
 - HTTP 2nd 3rd 4th
 - Usenet articles
- HistoricRecvLine class 2nd
- HomePage class
- host and port, TCP connections
- HOWTOs
- HTML forms, POST data from
- HTTP
 - conditional GET requests
 - GET, POST, PUT, and DELETE methods
 - information resources
 - remote function calls, using XML
 - SOAP
 - XML-RPC
 - sending requests to web resources
 - status codes
 - twisted.web package implementation
 - web client, uploading a file
 - web server
 - managing hierarchy of resources
 - parsing requests
 - POST data from HTML forms
 - responding to requests
 - running proxy server
 - serving files from disk 2nd
 - storing web data in SQL database
- HTTP Authorization header 2nd
- http.Request class
- HTTPChannel class
- HTTPClientFactory interface 2nd
- HTTPDownloader class
- HTTPEchoProtocol class
- HTTPFactory class
- HTTPProgressDownloader class
- HTTPStatusChecker class

Index

[SYMBOL] [A] [B] [C] [D] [E] [F] [G] [H] [I] [K] [L] [M] [N] [O] [P] [Q] [R] [S] [T] [U] [V] [W] [X] [Z]

- IAccount interface 2nd 3rd
- IAvatar interface
- ICredentialsChecker interface 2nd
 - implementation (example)
- If-Modified-Since header 2nd
- If-None-Match header 2nd
- IMailbox interface 2nd 3rd 4th
 - implement, methods for
 - new message notifications
- IMailboxListener interface
- IMAP
 - downloading messages from mailbox
 - listing mailboxes on server
 - mailboxes
 - message flags
 - messages
 - providing mailbox access
 - server-to-client notification
 - UIDs and sequence numbers 2nd
- imap4.MessageSet object
- IMAP4Client class 2nd
- IMAPDownloadProtocol class
- IMAPFolderListProtocol class
- IMAPServerProtocol class
- IMessage interface 2nd 3rd 4th
 - eomReceived method
- IMessageDelivery interface 2nd
- IMessagePart interface 2nd 3rd
- import twisted statement 2nd
- INamedUser interface
- INewsStorage interface 2nd
- InMemoryPasswordDatabaseDontUse class
- installing Twisted
 - adding utilities to your path
 - downloads and instructions
 - from source files
 - prepackaged versions for Mac OS X, Linux, and BSD
 - PyOpenSSL and PyCrypto packages
 - verifying installation
- insults.ServerProtocol object
- IPerspective interface
- IRC channels on freenode network
- IRealm interface 2nd
 - implementation (example)
- IService interface 2nd

privilegedStartService method
IServiceCollection interface 2nd
ISession interface 2nd
ISSHPrivateKey interface
ITransport interface
IUsernameHashedPassword interface
IUsernamePassword interface 2nd
checkPassword method

< Day Day Up >

[< Day Day Up >](#)

Index

[\[SYMBOL\]](#) [\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[X\]](#) [\[Z\]](#)

[key-based authentication, SSH server](#)
[keys module](#)
[keys.getPrivateKey](#)
[keys.getPublicKeyString](#)
[kill `cat twistd.pid` command](#)
[Kuchling, A. M.](#)

[< Day Day Up >](#)

Index

[\[SYMBOL\]](#) [\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[X\]](#) [\[Z\]](#)

- lambda functions
- Last-Modified header
- lineReceived method
 - [HistoricRecvLine](#)
 - [IMessage](#)
- LineReceiver class
- Linux
 - [Twisted utilities, adding to path](#)
 - [Twisted, PyOpenSSL, and PyCrypto, prepackaged](#)
- listenTCP function
- listSize method (POP3Client) 2nd
- listUidl method (POP3Client)
- Location: header
- log module
- log.startLogging method
- logfile module
- logging events and errors
- login method
 - [PBClient class](#)
 - [POP3Client](#)
 - [Portal class](#)

Index

[SYMBOL] [A] [B] [C] [D] [E] [F] [G] [H] [I] [K] [L] [M] [N] [O] [P] [Q] [R] [S] [T] [U] [V] [W] [X] [Z]

Mac OS X, adding Twisted utilities to path

mail

accepting with SMTP

downloading from POP3 server

SSL connections

IMAP mailbox, downloading messages from

listing mailboxes on IMAP server

POP3 access to mailboxes

providing IMAP access to mailboxes

sending using SMTP

SMTP server, looking up for domain

mailbox subscription status (IMAP)

mailbox UID validity identifier (IMAP)

MaildirMailbox class 2nd

mailing lists

MailUserRealm class

makeConnection method

manhole.Manhole objects 2nd

manhole_ssh.ConchFactory class

manhole_ssh.TerminalRealm object 2nd

manual pages

mbox file

Usenet articles, storage in

Message class

message flags (IMAP)

Message object (Python email module)

message UIDs (IMAP)

MessageSet class 2nd

MIME document

encodeForm function

MIMEBase messages

MIMEMultipart email messages

mimetypes module (Python)

mind argument (Portal.login)

Mozilla Thunderbird (email client)

multipart messages

multipart/form-data MIME document

multipart/form-encoded MIME document

multipart/mixed email messages

MultiService objects

MXCalculator class 2nd

MySQLdb module

Index

[SYMBOL] [A] [B] [C] [D] [E] [F] [G] [H] [I] [K] [L] [M] [N] [O] [P] [Q] [R] [S] [T] [U] [V] [W] [X] [Z]

- network server, writing
- network strings
- Nevow web server framework
- new message notifications (IMAP)
- NewPage class
- news.NNTPFactory object
- newsgroups
 - defined
 - listing on a server
- NewsShelf class 2nd
- nextLine method (HistoricRecvLine)
- NNTP (Network News Transfer Protocol)
 - downloading Usenet articles
 - listing newsgroups on a server
 - posting a message
 - running a basic server
 - using as user interface
- NNTPClient class
 - fetchArticle method
 - fetchGroup method
 - fetchGroups method 2nd
 - postArticle method
- NNTPFactory object
- NNTPGroupDownloadProtocol class
- NNTPGroupListerProtocol class
- noPage method
- notification of new messages (IMAP)
- NS function
- null values, SOAP support for

[< Day Day Up >](#)

Index

[\[SYMBOL\]](#) [\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[X\]](#) [\[Z\]](#)

[openShell method \(ISession\) 2nd](#)

[< Day Day Up >](#)

Index

[SYMBOL] [A] [B] [C] [D] [E] [F] [G] [H] [I] [K] [L] [M] [N] [O] [P] [Q] [R] [S] [T] [U] [V] [W] [X] [Z]

- pagePart method
- password-protected web page, accessing
- PasswordAuth class
- pb module
- pb.Avatar objects 2nd
- pb.IPerspective interface
- pb.Referenceable class
- pb.Root class
- PBClient class
- PBClientFactory class
- PBServerFactory class
- permissions, limiting for an application
- Persistent objects
- Perspective Broker
 - authentication
 - sharing Python objects
- pickled version of application
- Planet Twisted
- POP3
 - downloading mail from server
 - POP3 over SSL
 - Twisted POP3 server
- pop3.IMailbox interface
- POP3Client class 2nd
 - listSize method
 - retrieve method
- POP3DownloadFactory class
- POP3DownloadProtocol class
- POP3Protocol class
- port, TCP connections
- Portal objects 2nd
 - authenticating against database table
 - combining realm with credentials checkers
 - IMAP server
 - manhole
 - Perspective Broker authentication
 - POP3 server
 - SSH server 2nd
- POST requests, HTTP 2nd
 - sending XML-RPC function call to server
- postArticle method (NNTPClient)
- printError function 2nd
- printPage function 2nd
- printTime function
- private key object, RSA

- privilegedStartService method
- Process objects
- processes
 - multiple services in single process
 - running Twisted application as daemon
- progress, monitoring for downloads
- Protocol class
 - Twisted servers
- Proxy class
 - soap
 - xmlrpc
 - callRemote method
- proxy server, running
- ProxyClient class
- ProxyClientFactory class
- ProxyRequest class
- public key authentication
 - administrative Python shell over SSH
 - SSH
- public/private key pairs
 - ConchFactory class
 - SSH server
- PublicKeyCredentialsChecker class
- PUT requests, HTTP 2nd
- PyCrypto
 - installers for Windows
 - installing from source code
- pydoc utility
- PyOpenSSL
 - installers for Windows
 - installing from source code
- Python scripts directory
- python setup.py install command
- Python, xiii
 - administrative shell
 - database modules, DB-API interface
 - email module
 - email.Message module
 - mimetypes module
 - multiple installed versions
 - objects, sharing with Perspective Broker
 - range function
 - webbrowser module

< Day Day Up >

Index

[SYMBOL] [A] [B] [C] [D] [E] [F] [G] [H] [I] [K] [L] [M] [N] [O] [P] [Q] [R] [S] [T] [U] [V] [W] [X] [Z]

queries, database

 _getQueryResults function

questions, finding answers to

quit method (POP3Client)

< Day Day Up >

Index

[SYMBOL] [A] [B] [C] [D] [E] [F] [G] [H] [I] [K] [L] [M] [N] [O] [P] [Q] [R] [S] [T] [U] [V] [W] [X] [Z]

- range function (Python)
- reactor
 - opening TCP connection
 - starting and stopping 2nd
- reactor.callLater function 2nd
- reactor.connectSSL function
- reactor.connectTCP function
- reactor.listenTCP method 2nd
- reactor.run function
- reactor.stop function
- realms
 - IMAP server
 - pb.Avatar objects
 - SSH server 2nd 3rd
 - with multiple avatars
- receivedHeader (IMessageDelivery)
- receiving data on TCP connection
- Record_MX class
- Referenceable class
- refreshIfNecessary (RssFeed)
- registerChecker method
- remote function calls using XML over HTTP
 - SOAP
 - XML-RPC
- render method (Resource class)
- render_DELETE function
- render_GET function
- render_PUT function
- renderHomePage function
- Request class
 - finish method
 - setHeader method
 - setResponseCode method
- Request.args dictionary 2nd
- request.finish function
- request.redirect function
- requestAvatar method 2nd
- requestAvatarId method 2nd
- requestService method (SSHClientTransport class)
- Resource class 2nd
 - getChild method
- resources
 - HomePage, NewPage, and SavePage
 - lineService, webService, and webAdminService
 - updating with web client through REST

- web application
 - designing in terms of
 - managing
- REST (Representational State Transfer) architecture
 - using for web services
 - using web client to update resources
 - XML-RPC vs.
- RestResource class
- retrieve method (POP3Client) 2nd
- returnFileName function
- Reverser object
- Reverser-shutdown.tap file
- ReverserLineFactory class
- Root class
- root permissions, running server with
- RPC (Remote Procedure Calls)
 - enabling web services using XML-RPC
 - Twisted Spread system
- RSA private key object
- RSA.generate
- RSAobj class
- RSS (Really Simple Syndication) 2nd
 - defined
 - reading through NNTP
- RSS aggregators
- RSS feed (Planet Twisted)
- RssFeed objects
- RssFeedStorage class
- runQuery method (ConnectionPool)

< Day Day Up >

Index

[SYMBOL] [A] [B] [C] [D] [E] [F] [G] [H] [I] [K] [L] [M] [N] [O] [P] [Q] [R] [S] [T] [U] [V] [W] [X] [Z]

- SavePage class
- scripts directory (Python)
- security
 - limiting application permissions
- select method (IAccount)
- sendEOF function
- sending data on TCP connection
- sendmail function 2nd
- server-to-client notification (IMAP)
- server.Site class 2nd
- serverGreeting method
- ServerProtocol object
- servers
 - authentication
 - IMAP
 - listing mailboxes
 - network server, writing
 - NNTP
 - listing newsgroups
 - posting a message
 - running basic
 - Perspective Broker
 - POP3
 - downloading mail from
 - Protocol classes
 - running with root permissions
 - SMTP
 - accepting mail
 - looking up for domain
 - SMTP as user interface
 - SSH
 - administrative Python shell
 - setting up custom
 - using public keys for authentication
 - web servers
- service.IServiceCollection interface 2nd
- service.setServiceParent function
- ServiceAdminPage class
- services
 - IService interface
 - multiple, running in single process
- setHeader method (Request)
- setResponseCode method (Request)
- setServiceParent method 2nd
- Shelf class

shells

- administrative Python shell, provided through SSH
- interactive shell, providing through SSH

showPage callback handler

signature data, verifying

Site class 2nd

smart host

SMTP

- accepting mail
- looking up server for a domain
- sending mail with
- server for Usenet notification messages
- using as user interface

SMTP class

smtp.IMessage interface

smtp.IMessageDelivery interface

SOAP

- installing SOAP libraries
- web services, sharing
- soap.SOAPPublisher class
- software architecture style (REST)

source code

- installing Twisted from
- reading to understand Twisted

SQL database

- authenticating against
- connecting to
- storing web data in

SSH (Secure SHell)

- administrative Python shell
- client, writing
- public keys, using for authentication
- PyCrypto package
- setting up custom server

SSHChannel class 2nd

SSHClientTransport class

SSHConnection class 2nd

SSHFactory object

SSHSessionProcessProtocol object

SSHUserAuthClient class 2nd

SSL (Secure Socket Layer)

- POP3 server connections
- PyOpenSSL

startLogging method

startService method 2nd

static.File class 2nd

status codes, HTTP

StdioProxyProtocol class

stopReactor function

stopService method 2nd

strings, network

Sumo distribution, Twisted

- installing from source files

< Day Day Up >

Index

[SYMBOL] [A] [B] [C] [D] [E] [F] [G] [H] [I] [K] [L] [M] [N] [O] [P] [Q] [R] [S] [T] [U] [V] [W] [X] [Z]

TCP connections

- opening with reactor
- sending and receiving data

TCPServer class 2nd

terminal window, manipulating current contents

TerminalRealm object 2nd

time.localtime function

transport attribute (Protocol objects)

transport.SSHClientTransport class

trap method (Failure)

twistd program

- chroot directory flag
- f flag
- n flag
- y flag
- y yourappname command
- application user and group, changing
- logging capabilities
- running multiple services in single process

twistd.pid file

Twisted

- download and installation web site

Twisted Spread

twisted-python list

twisted-web list

twisted.appliation.service.IService

twisted.application.internet.TCPServer 2nd

twisted.application.service module

twisted.application.service.Application

- uid and gid keyword arguments 2nd

twisted.application.service.MultiService object

twisted.application.service.Process object

twisted.conch package

twisted.conch.common.NS function

twisted.conch.manhole module

twisted.conch.manhole_ssh module

twisted.conch.session.wrapProtocol function

twisted.conch.ssh SSH client

twisted.conch.ssh.common module

twisted.conch.ssh.keys module

twisted.conch.ssh.keys.verifySignature

twisted.cred package

- authentication classes
- terminology

twisted.cred.checker.ICredentialsChecker class

- twisted.cred.portal.IRealm interface 2nd
- twisted.cred.portal.Portal class 2nd
- twisted.enterprise package
- twisted.enterprise.adbapi.ConnectionPool object 2nd
- twisted.internet module
- twisted.internet.ssl.ClientContextFactory class
- twisted.mail.imap4 package
- twisted.mail.pop3client.POP3Client class
- twisted.mail.relaymanager.MXCalculator class 2nd
- twisted.news package
- twisted.persisted.dirdbm.Shelf class
- twisted.persisted.sob.Persistent object
- twisted.protocols.dns.Record_MX class
- twisted.protocols.smtp module
- twisted.protocols.smtp.sendmail function 2nd
- twisted.python.components.Componentized object 2nd
- twisted.python.failure.Failure object
- twisted.python.log module
- twisted.python.logfile module
- twisted.spread.pb module
- twisted.web package
 - XML-RPC support
- twisted.web.client package
 - downloadPage function
 - getPage function
- twisted.web.error.Error
- twisted.web.http module
- twisted.web.http.Request class
- twisted.web.proxy module
- twisted.web.resource module
 - shortcomings of classes
- twisted.web.resource.Resource class
- twisted.web.server module
 - shortcomings of classes
- twisted.web.soap.Proxy class
- twisted.web.static module
- twisted.web.xmlrpc.Proxy object
- twisted.web.xmlrpc.XMLRPC class
- twisted.web2

Index

[SYMBOL] [A] [B] [C] [D] [E] [F] [G] [H] [I] [K] [L] [M] [N] [O] [P] [Q] [R] [S] [T] [U] [V] [W] [X] [Z]

- uid and gid for applications 2nd
- Unchanged status code
- uploading a file to a web page
- URIs
 - trailing slashes
- URLs
 - IMAP specification
 - MySQLdb module
 - Nevow
 - NNTP specification
 - SMTP specification
 - Twisted downloads
 - Usenet article format specification
- Usenet
 - downloading articles
 - listing newsgroups on a server
 - posting messages to NNTP server
 - running an NNTP server
 - using NNTP as user interface
- user interface
 - NNTP as
 - SMTP as
- userauth.SSHUserAuthClient class 2nd
- userCredentials.checkPassword method
- utilities (Twisted), adding to your path

[< Day Day Up >](#)

Index

[\[SYMBOL\]](#) [\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[X\]](#) [\[Z\]](#)

[validateFrom \(IMessageDelivery\)](#)
[validateTo \(IMessageDelivery\)](#)
[validation service \(W3C\), uploading file to](#)
[verifyHostKey method](#)
[verifySignature function](#)
[virtual terminals](#)

[< Day Day Up >](#)

Index

[SYMBOL] [A] [B] [C] [D] [E] [F] [G] [H] [I] [K] [L] [M] [N] [O] [P] [Q] [R] [S] [T] [U] [V] [W] [X] [Z]

- W3C validation service, uploading file to
- web browser, using web application through
- web clients
 - accessing password-protected page
 - checking for web page changes
 - downloading web pages
 - monitoring download progress
 - uploading a file
 - using to update resources through REST
- web pages
 - checking for changes
 - downloading
 - writing to disk while downloading
 - password-protected, accessing
 - uploading a file
- web servers
 - managing hierarchy of resources
 - parsing HTTP requests
 - POST data from HTML forms
 - responding to HTTP requests
 - running HTTP proxy server
 - storing web data in SQL database
- web services
 - calling XML-RPC functions
 - enabling, using XML-RPC
 - installing SOAP libraries
 - REST architecture, using
 - sharing Python objects using Perspective Broker
 - sharing with SOAP
- webbrowser module (Python)
- Wiki, designing with REST architecture
- WikiPage class
- Windows
 - adding Twisted utilities to your path
 - Twisted, downloading and installing
- WordCounter class
- WordCountProxy class
- WordParser class
- wrapProtocol function

Index

[SYMBOL] [A] [B] [C] [D] [E] [F] [G] [H] [I] [K] [L] [M] [N] [O] [P] [Q] [R] [S] [T] [U] [V] [W] [X] [Z]

[XML, making remote function calls over HTTP with SOAP](#)

[XML-RPC](#)

[calling functions](#)

[enabling web services using](#)

[XMLRPC class 2nd](#)

[xmlrpc.Binary object](#)

[xmlrpc.DateTime object](#)

[xmlrpc.Proxy class](#)

[callRemote method](#)

